

2023-24

A report on

Rainwater Harvesting Potential for Delhi Technological University

prepared by

Prof. S. Anbu Kumar

&

Mr. Gour Anunay Ashokkumar

Contents

Executive Summary.....	1
1. Overview.....	2
2. Methodology.....	3
3. Results.....	5
Scenario 1: Present Condition.....	5
Scenario 2. - Master Plan.....	7
Comparison of Rainwater Harvesting Potential in Both Scenarios....	11
4. Conclusion.....	12
Annexures.....	13



DELHI TECHNOLOGICAL UNIVERSITY
(formerly known as Delhi College of Engineering)

Executive Summary

This report presents a detailed analysis of the rainwater harvesting (RWH) potential at Delhi Technological University (DTU), formerly known as Delhi College of Engineering. The study evaluates the potential for capturing and utilizing rainwater from various surface types across the university campus recognizing the importance of sustainable water management.

The assessment covers a total area of 663,154.03 square meters, with an overall potential run-off of 266,874.38 cubic meters per year. Two primary scenarios were considered: the present condition and the future condition as per the master plan. In the present condition, the analysis reveals a total run-off potential of 238,341.75 cubic meters per year, necessitating the installation of around 73 rainwater harvesting pits. Under the master plan scenario, the potential run-off increases to 266,874.38 cubic meters per year; the university will require around 120 pits to manage the runoff effectively.

The methodology involved data collection on surface types, ground coverage areas, average annual rainfall, and runoff coefficients. Calculations were based on standard formulas and guidelines, and two scenarios were analyzed to provide a comprehensive view of current and future RWH potential.

Based on the analysis, it is recommended to implement the required number of rainwater harvesting pits as detailed in the scenarios to maximize water conservation. Regular maintenance of RWH systems is essential to ensure efficient operation. Monitoring systems may be established to collect data on rainwater collection and usage which may help in performance evaluation and improvement. Additionally, future expansions and improvements to RWH infrastructure should be considered as the university grows.

1. Overview

Rainwater harvesting (RWH) is a sustainable and effective method of water management that involves collecting, storing, and utilizing rainwater for various purposes. Given the increasing pressures on water resources, implementing RWH systems is essential for ensuring water security, especially in urban and institutional settings. This report assesses the rainwater harvesting potential at Delhi Technological University (DTU), formerly known as Delhi College of Engineering.

DTU, with its expansive campus and numerous buildings, presents a significant opportunity for rainwater harvesting. This report aims to analyze the potential for capturing rainwater from various surface types, including rooftops, roads, paved areas, open land, and green belts within the university premises. By examining different scenarios of current and planned construction phases, the report provides a comprehensive understanding of the required infrastructure to maximize rainwater harvesting. Two primary scenarios are considered:

Present Condition (Scenario 1): This scenario determines the present requirement of Rooftop Rainwater Harvesting System (RTRWHS) considering the RWH potential for the buildings constructed under Phase I. The blocks constructed under the Part 1 of Phase II construction have been constructed with RTRWHS with the following details:

Table 1. Details of existing Rooftop Rain Water Harvesting Structures at Delhi Technological University

Sr. No.	Location of RWH Structure	Rooftop Area (m ²)	Size of Pit(s) LxBxH	Pit Volume (Cum.)	Quantum of Run off available (Cum/Year)
1	Academic Block 3	1809.00	5.5x2.0x2.0 mtr.	22.00	1620.33
2	Academic Block 3		8.0x2.0x2.0 mtr.	32.00	
3	Academic Block 4	2285.00	5.5x2.0x2.0 mtr.	22.00	1399.93
4	Academic Block 4		8.0x2.0x2.0 mtr.	32.00	
5	APJ Hostel	491.00	5.5x2.0x2.0 mtr.	22.00	274.7
6	APJ Hostel		8.0x2.0x2.0 mtr.	32.00	
Totals				162.00	3294.96

Master Plan (Scenario 2): This scenario determines the requirement of Rooftop Rainwater Harvesting System (RTRWHS) considering the RWH potential after completion of the entire phased construction of the University as per the Master Plan.

The methodology employed in this analysis includes an examination of ground coverage areas, application of appropriate runoff coefficients, and consideration of the average annual rainfall. The report also includes an evaluation of the number and size of RWH pits required to capture and utilize the runoff effectively.

This report is prepared by Prof. S. Anbu Kumar, Professor, Department of Civil Engineering and Mr. Gour Anunay Ashokkumar, Assistant Professor, Department of Environmental Engineering. It aims to support the university in implementing robust rainwater harvesting systems, contribute to water conservation, and promote sustainable practices within the university campus.

2. Methodology

The methodology for assessing the rainwater harvesting (RWH) potential at Delhi Technological University (DTU) involves a systematic approach to evaluate the various factors influencing rainwater collection and utilization. The process includes the following steps:

a. Data Collection

Data on surface types, ground coverage areas, rainfall intensity, and runoff coefficients were collected. Specific data points include:

- *Surface Types*: Different surfaces such as rooftops, roads, paved areas, open land, and green belts as shown in the figure below.




Fig. 1 Types of surface

- *Ground Coverage Area*: The area in square meters (sqm) for each surface type.
- *Rainfall Intensity*: The average annual rainfall for the North-West District of the NCT of Delhi was determined to be 621.5 mm (IMD, Delhi).
- *Runoff Coefficient*: The coefficient indicating the fraction of rainfall that becomes runoff for each surface type, based on the Manual of Artificial Recharge of Ground Water (CGWB, 2007) as shown in Table 2.

Table 2. Runoff Coefficient

Type of Surface	Runoff Coefficient
Rooftop of Buildings	0.85
Shed	0.85
Road/Paved area	0.65
Open Land	0.20
Green Belt	0.15

b. Calculation of Quantum of Runoff

The quantum of runoff available was calculated for each surface type using the following formula:

$$\text{Quantum of Runoff (Cum/Year)} = \text{Area (m}^2\text{)} \times \text{Rainfall Intensity (m)} \times \text{Runoff Coefficient}$$

This calculation was performed separately for each surface type to determine the total potential runoff.

c. Scenario Analysis

Two scenarios were considered to assess the rainwater harvesting potential:

- *Scenario 1: Present Condition* - evaluates the RWH potential for buildings and infrastructure constructed under Phase I and Part 1 of Phase II. It determines the current requirement for RWH systems based on the existing structures.
- *Scenario 2: Master Plan* - projects the RWH potential upon the completion of all construction phases as per the University's master plan. It provides a long-term view of RWH infrastructure needs.

d. Determination of Required RWH Pits

The required volume of RWH pits was determined by considering approximately 3.5% of the volume of RWH potential for each block of connected buildings. The volume was divided by the nominal pit volume of 32 cubic meters (cu.m) (pit size: 8.0 x 2.0 x 2.0 meters) to determine the number of pits required. The guideline considered for pit-size as shown in Table 3.

Table 3. Rain Water Harvesting pit size guideline

Plot Area (SQM)	Required Volume of RWH Pit (Cu.M)	Dimensions		
		Length (m)	Width (m)	Depth (m)
200	4	2	1	2
300	8	2	2	2
400	12	3	2	2
500	16	4	2	2
600	20	5	2	2
700	24	4	3	2
800	28	7	2	2
900	32	4	4	2
1000	36	6	3	2

3. Results

The results of the rainwater harvesting (RWH) potential assessment for Delhi Technological University (DTU) are presented in two scenarios: the present condition and the master plan scenario. These scenarios help in understanding the current and future requirements for RWH systems to optimize water conservation on the campus.

Scenario 1: Present Condition

This scenario evaluates the requirement of Rooftop Rainwater Harvesting System (RTRWHS) considering the RWH potential based on the buildings and infrastructure currently in place, focusing on structures completed under Phase I and Part 1 of Phase II construction. Refer to Table A.1. of the annexure for the calculation sheet of this scenario. The building-wise summary of Rain-water Harvesting System requirements as per the Master Plan of the university is presented in Table 5 below.

Summary of Present Condition:

Total Area Evaluated:	663,154.03 sqm
Total Quantum of Available Runoff:	266,874.38 cubic meters (cum) per year
Total Number of Pits Required:	73

Detailed Results:

Table 4. Present Roof-top Rainwater Harvesting System Requirements

<i>Sr. No.</i>	<i>Block</i>	<i>No. of Connected Buildings</i>	<i>No. of Pits required</i>
1	Admin Block	1	1
2	Auditorium	1	1
3	Library	1	1
4	Computer Centre	1	1
5	Science Block	1	1
6	Inclined Wing Sc. Block	1	1
7	Workshop	6	2
8	Mechanical Engineering	1	2
9	Canteen	1	1
10	Civil to Electrical Block	1	2
11	Delhi School of Management	1	1
12	Substations	8	8
13	Boys Hostel	6	6
14	Director's Sports Office & Toi	1	1
15	Indoor Hall	1	1
16	Wind Tunnel	2	2
17	SPS	5	5
18	Pragya Bhavan	1	1
19	Type 4 Residences	8	8
20	Type 5 Residences	4	4
21	Guest House	1	1
22	Transit Hostel	1	1
23	VC Residence	2	1
24	KC Hostel	1	1
25	SN Hostel	1	1
26	Health Centre	1	1
27	Type 2 & 3 Residences	10	10
28	Type 1 Residences	4	4
29	Aryabhata Mess	1	1

30	Raj Soin Hall	1	1
31	Design Centre	1	1
Total		76	73

Scenario 2. - Master Plan

This scenario determines the requirement of Rooftop Rainwater Harvesting System (RTRWHS) considering the RWH potential upon completion of all construction phases of the University as per the Master Plan. Refer to Table A.2. of the annexure for the calculation sheet of this scenario. The building-wise summary of Rain-water Harvesting System requirements as per the Master Plan of the university is presented in Table 5 below.

Summary as per Master Plan:

Total Roof-top Area Evaluated: 663,154.03 sqm
 Total Quantum of Available Runoff: 266,874.38 cubic meters (cum) per year
 Total Number of Pits Required: 120

Detailed Results:

Sr. No.	Particulars	Area (Sq.m)	Rainfall (m)	Runoff Coefficient*	Quantum of Runoff available (Cum/Year)
	1	2	3	4	5 (2*3*4)
1	Rooftop of building/Shed	461006.78	0.6215	0.85	243,538.36
2	Road/Paved area	4572.92	0.6215	0.65	1,847.35
3	Open Land	98787.165	0.6215	0.20	12,279.24
4	Green Belt	98787.165	0.6215	0.15	9,209.43
Total Area (sqm) =		663154.03	Total Quantum of available runoff (cum/y) =		266,874.38

Table 5. Details of RTRWHS for RWH Potential at DTU as per Master Plan

Sr. No.	Blocks	Description	Quantum of Runoff available (Cum/Year)	Estimated Pit Volume (Cu.m)	No. of 32 Cu.m Pits	No. of 22 Cu.m Pits	No. of 20 Cu.m Pits	No. of 12 Cu.m Pits
1	AB-1	ACADEMIC BUILDING	2,669.43	131.34	3			
2	AB-3A	SEMINAR HALL	233.50	11.49				1

Sr. No.	Blocks	Description	Quantum of Runoff available (Cmm/Year)	Estimated Pit Volume (C.m)	No. of 32 C.m Pits	No. of 22 C.m Pits	No. of 20 C.m Pits	No. of 12 C.m Pits
3	AB-6	ACADEMIC BUILDING	834.10	41.04			1	
4	AB-7	ACADEMIC BUILDING	826.16	40.65			1	
5	AB-8	ACADEMIC BUILDING	1,106.79	54.45	1	1		
6	AB-9	MULTIPURPOSE HALL	528.28	25.99				1
7	CB-1	ACTIVITY CENTRE	756.05	37.20			1	
8	CB-3	DINING HALL (BOYS)	857.76	42.20			1	
9	CB-5	DINING HALL (GIRLS)	461.51	22.71				1
10	II-12ME 1	BOYS HOSTEL	204.13	10.04				1
11	II-12ME 2	BOYS HOSTEL	204.13	10.04				1
12	II1	BOYS HOSTEL	262.25	12.90				1
13	II10	BOYS HOSTEL	262.25	12.90				1
14	II11	BOYS HOSTEL	274.70	13.52				1
15	II12	BOYS HOSTEL	262.25	12.90				1
16	II13	BOYS HOSTEL	262.25	12.90				1
17	II14	BOYS HOSTEL	274.70	13.52				1
18	II15	BOYS HOSTEL	262.25	12.90				1
19	II16	BOYS HOSTEL	274.70	13.52				1
20	II2	BOYS HOSTEL	262.25	12.90				1
21	II3	BOYS HOSTEL	274.70	13.52				1
22	II6	BOYS HOSTEL	262.25	12.90				1
23	II7	BOYS HOSTEL	274.70	13.52				1
24	II8	BOYS HOSTEL	262.25	12.90				1
25	II9	BOYS HOSTEL	274.70	13.52				1
26	HG-1	GIRLS HOSTEL	262.25	12.90				1
27	IIIG-12ME	GIRLS HOSTEL	204.13	10.04				1
28	IIIG-2-	GIRLS HOSTEL	262.25	12.90				1
29	IIIG-3	GIRLS HOSTEL	274.70	13.52				1
30	IIIG-4	GIRLS HOSTEL	262.25	12.90				1
31	MILCP-1	Multi Level Car Parking	3,480.35	171.23	4			
32	MILCP-2	Multi Level Car Parking	1,427.28	70.22	2			

Sr. No.	Blocks	Description	Quantum of Runoff available (Cmm/Year)	Estimated Pit Volume (C.m)	No. of 32 C.m Pits	No. of 22 C.m Pits	No. of 20 C.m Pits	No. of 12 C.m Pits
33	MLCP-3	Multi Level Car Parking	1,259.60	61.97	1	1		
34	MLCP-4	Multi Level Car Parking	642.68	31.62			1	
35	MLCP-5	Multi Level Car Parking	544.66	26.80				1
36	R8-12.13.14.15. 16.17.18.19	H.O.D	756.49	37.22			1	
37	RB-1,2	TYPE-III QUARTERS	474.39	23.34				1
38	RB-10.11	TYPE-I QUARTERS	1,671.01	82.21	2			
39	RB-3.4	TYPE-IV QUARTERS	872.71	42.94			1	
40	RB-5,6,7,8	TYPE-V QUARTERS	1,745.42	85.87	2			
41	RB-9.RB-20.RB-21	TYPE-I QUARTERS	886.54	43.62			1	
42	EAB-1	ADMIN.	992.84	34.75	1	1		
43	EAB-10	CANTEEN	369.79	12.94				1
44	EAB-11	GATE COMPLEX	12.04	0.42				1
45	EAB-2	MULTIPURPOSE	1,320.69	46.22	1	1		
46	EAB-3	LIBRARY	1,056.55	36.98	1	1		
47	EAB-4	COMP. CENTRE	792.41	27.73			1	
48	EAB-5	DEPT. OF CIVIL	5,086.57	178.03	6			
49	EAB-6	DEPT. OF PROD. MECH.	2,223.42	77.82	2	1		
50	EAB-7	WORKSHOP	1,804.69	63.16	2	1		
51	EAB-8	DEPT. OF PHYS. CHEM.	1,488.38	52.09	2			
52	EAB-9	TURBINE WIND TUNNEL	1,056.55	36.98	1	1		
53	EHB-1,2,3,4,5	BOYS HOSTEL	5,148.49	180.20	6			
54	EHB-6	GIRLS HOSTEL	410.38	14.36				1
55	EHB-7	PG HOSTEL	1,124.79	39.37	1	1		
56	ERB-1,2,3,4	TYPE-I QUARTERS	424.27	14.85				1
57	ERB-12,13,14	TYPE-III QUARTERS	463.97	16.24				1
58	ERB-15,16,17,18	TYPE-IV QUARTERS	827.05	28.95				1
59	ERB-19,20,21,22	TYPE-V QUARTERS	1,576.73	55.19	2			
60	ERB-23	GUEST HOUSE	218.95	7.66				1
61	ERB-24	MARRIED SCHOLARS HOSTEL	122.14	4.27				1

Sr. No.	Blocks	Description	Quantum of Runoff available (C.m/Year)	Estimated Pit Volume (C.m)	No. of 32 C.m Pits	No. of 22 C.m Pits	No. of 20 C.m Pits	No. of 12 C.m Pits
62	ERB-25	TRANSIT HOSTEL	302.73	10.60				1
63	ERB-26	NURSERY SCHOOL	422.62	14.79				1
64	ERB-27	PRINCIPAL'S BUNGALOW	105.66	3.70				1
65	ERB-28,29,30,31	PUMP HOUSE	221.88	7.77				1
66	ERB-32	12-BED HOSPITAL	413.32	14.47				1
67	ERB-33	CHLORINATION ROOM	21.34	0.75				1
68	ERB-34	DESU METERING PANEL	95.09	3.33				1
69	ERB-35,36,37,38	TRANSFORMER ROOMS	570.54	19.97				1
70	ERB-5,6,7,8,9,10,11	TYPE-II QUARTERS	887.17	31.05			1	
71	AB-2	ACADEMIC BUILDING	1,274.17	44.60	1	1		
72	AB-3	ACADEMIC BUILDING	1,620.33	56.71	2			
73	AB-4	ACADEMIC BUILDING	1,399.93	49.00	2			
74	AB-5	ACADEMIC BUILDING	2,557.31	89.51	3			
75	CB-6	SWIMMING POOL	418.83	14.66				1
76	CB-7	INDOOR SPORTS FACILITY	969.94	33.95	1	1		
77	II5	BOYS HOSTEL	274.70	9.61				1
78	II6-6	GIRLS HOSTEL	274.70	9.61				1
79	II6-5	GIRLS HOSTEL	262.25	9.18				1
80	AB-4A	ACADEMIC BUILDING RECEPTION	422.62	20.79				1
81	CB-2	DINING HALL (BOYS)	857.76	42.20			1	
82	CB-4	DINING HALL (GIRLS)	406.29	19.99				1
83	II4	BOYS HOSTEL	262.25	12.90				1
Totals					49	11	12	48

Comparison of Rainwater Harvesting Potential in Both Scenarios

Table 6 provides a comparative analysis of the rainwater harvesting (RWH) potential in two scenarios: the present condition (Scenario 1) and the future condition as per the master plan (Scenario 2). The comparison is based on the potential run-off available for each phase.

Table 6 Phase-wise RTRWHS Potential compared based on various scenarios.

Sr. No.	Phase	Coverage Area (sqm)	Scenario 1: Present Potential Run-off available (Cum/Year)	Scenario 2: Potential Run-off available (Cum/Year)
1	Future Phases	51,970.49	7,859.02	27,454.71
2	Phase I	590,359.02	220,748.26	228,418.59
3	Phase IIA	17,135.31	9,052.16	9,052.16
4	Phase IIB	3,689.21	682.31	1,948.92
Total			238,341.75	266,874.38




Fig. 2. Comparison of RTRWHS Potential of the considered scenarios.

The comparison highlights the significant increase in rainwater harvesting potential in Scenario 2 compared to Scenario 1. The total potential run-off available increases from 238,341.75 cubic meters per year in the present condition to 266,874.38 cubic meters per year in the master plan scenario. This increase indicates future developments, infrastructure improvements, and better RWH practices. Implementing

RTRWHS in future constructions will enhance the university's water conservation efforts, contributing to sustainable resource management and environmental stewardship.

4. Conclusion

This report on Rainwater Harvesting Potential for Delhi Technological University has identified numerous opportunities for capturing and utilizing rainwater. The evaluation has been conducted using calculations based on ground coverage area, runoff coefficients, and annual rainfall data as per the Manual of Artificial Recharge of Ground Water. Based on the current and planned infrastructural developments, two scenarios have been evaluated to determine the necessary rainwater harvesting systems:

Scenario 1 - Present Condition:

- This scenario considers the buildings constructed under Phase I and Part 1 of Phase II.
- The analysis indicates a requirement of 73 rainwater harvesting pits to accommodate the runoff generated from these buildings.

Scenario 2 - Master Plan:

- This scenario projects the requirement for the entire university campus upon completion of all construction phases as per the master plan.
- The analysis reveals a requirement of 120 rainwater harvesting pits to manage the runoff from the fully developed campus.

The study concludes that implementing the recommended number of rainwater harvesting pits will significantly contribute to water conservation efforts on the campus, enhancing sustainability and resource management. By adopting these measures, Delhi Technological University can effectively utilize its rainwater harvesting potential and possibly reduce the dependency on external water sources, and promote environmental stewardship.



Prof. S. Anbu Kumar
Professor, Dept. of Civil Engg.



Mr. Gour Anunay Ashokkumar
Asst. Prof., Dept. of Environmental Engg.

Table A.1. Present Scenario of RWH Potential at Delhi Technological University

Sr. No.	Blocks	Description	Type of Surface (Present Condition)	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cum/Year)
1	AB-1	ACADEMIC BUILDING	Open Land	Future Phases	5,053.11	0.20	628.10
2	AB-3A	SEMINAR HALL	Road/Paved area	Future Phases	442.00	0.65	178.56
3	AB-6	ACADEMIC BUILDING	Green Belt	Future Phases	1,578.92	0.15	147.19
4	AB-7	ACADEMIC BUILDING	Open Land	Future Phases	1,563.88	0.20	194.59
5	AB-8	ACADEMIC BUILDING	Open Land	Future Phases	2,095.10	0.20	260.42
6	AB-9	MULTIPURPOSE HALL	Open Land	Future Phases	1,000.00	0.20	124.30
7	CB-1	ACTIVITY CENTRE	Open Land	Future Phases	1,431.16	0.20	177.89
8	CB-3	DINING HALL (BOYS)	Open Land	Future Phases	1,623.70	0.20	201.83
9	CB-5	DINING HALL (GIRLS)	Open Land	Future Phases	873.61	0.20	108.59
10	H-12ME-1	BOYS HOSTEL	Open Land	Future Phases	386.40	0.20	48.03
11	H-12ME-2	BOYS HOSTEL	Open Land	Future Phases	386.40	0.20	48.03
12	H1	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
13	H10	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
14	H11	BOYS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
15	H12	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
16	H13	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
17	H14	BOYS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
18	H15	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
19	H16	BOYS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
20	H2	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71

Sr. No	Blocks	Description	Type of Surface (Present Condition)	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cum) Year
21	113	BOYS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
22	116	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
23	117	BOYS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
24	118	BOYS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
25	119	BOYS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
26	11G-1	GIRLS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
27	11G-12M15	GIRLS HOSTEL	Open Land	Future Phases	386.40	0.20	48.05
28	11G-2-	GIRLS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
29	11G-3	GIRLS HOSTEL	Open Land	Future Phases	520.00	0.20	64.64
30	11G-4	GIRLS HOSTEL	Open Land	Future Phases	496.42	0.20	61.71
31	M.L.C.P-1	Multi Level Car Parking	Open Land	Future Phases	6,588.15	0.20	818.91
32	M.L.C.P-2	Multi Level Car Parking	Open Land	Future Phases	2,701.78	0.20	335.85
33	M.L.C.P-3	Multi Level Car Parking	Open Land	Future Phases	2,384.37	0.20	296.38
34	M.L.C.P-4	Multi Level Car Parking	Open Land	Future Phases	1,216.57	0.20	151.22
35	M.L.C.P-5	Multi Level Car Parking	Open Land	Future Phases	1,031.01	0.20	128.15
36	RB-12,13,14,15,16,17,18,19	FLOOD	Road/Paved area	Future Phases	1,432.00	0.65	578.49
37	RB-1,2	TYPE-III QUARTERS	Open Land	Future Phases	898.00	0.20	111.62
38	RB-10,11	TYPE-I QUARTERS	Open Land	Future Phases	3,163.14	0.20	393.18
39	RB-3,4	TYPE-IV QUARTERS	Open Land	Future Phases	1,652.00	0.20	205.34
40	RB-5,6,7,8	TYPE-V QUARTERS	Road/Paved area	Future Phases	3,304.00	0.65	1,334.75
41	RB-9, RB-20, RB-21	TYPE-I QUARTERS	Open Land	Future Phases	1,678.17	0.20	208.60
42	LEAB-1	ADMIN.	Rooftop of building	Phase I	1,879.40	0.85	992.84

Sr. No.	Block	Description	Type of Surface (Present Condition)	Stage	Ground Coverage Area (sqm)	Rainoff Coefficient	Quantum of Rainoff available (Cum/Year)
43	EAB-10	CANTINE	Rooftop of building	Phase I	700.00	0.85	369.79
44	EAB-11	GATE COMPLEX	Shed	Phase I	22.80	0.85	12.04
45	EAB-2	MULTIPURPOSE	Rooftop of building	Phase I	2,500.00	0.85	1,320.69
46	EAB-3	LIBRARY	Rooftop of building	Phase I	2,000.00	0.85	1,056.55
47	EAB-4	COMP. CENTRE	Rooftop of building	Phase I	1,500.00	0.85	792.41
48	EAB-5	DEPT. OF CIVIL	Rooftop of building	Phase I	9,628.64	0.85	5,086.57
49	EAB-6	DEPT. OF PROD. MECH.	Rooftop of building	Phase I	4,208.83	0.85	2,223.42
50	EAB-7	WORKSHOP	Shed	Phase I	3,416.20	0.85	1,804.69
51	EAB-8	DEPT. OF PHYS. CHEM.	Rooftop of building	Phase I	2,817.43	0.85	1,488.38
52	EAB-9	TURBINE WIND TUNNEL	Shed	Phase I	2,000.00	0.85	1,056.55
53	EBB-1,2,3,4,5	BOYS HOSTEL	Rooftop of building	Phase I	9,745.85	0.85	5,148.49
54	EBB-6	GIRLS HOSTEL	Rooftop of building	Phase I	776.83	0.85	410.38
55	EBB-7	PG HOSTEL	Rooftop of building	Phase I	2,129.17	0.85	1,124.79
56	ERB-1,2,3,4	TYPE-I QUARTERS	Rooftop of building	Phase I	803.12	0.85	424.27
57	ERB-12,13,14	TYPE-III QUARTERS	Rooftop of building	Phase I	878.28	0.85	463.97
58	ERB-15,16,17,18	TYPE-IV QUARTERS	Rooftop of building	Phase I	1,565.56	0.85	827.05
59	ERB-19,20,21,22	TYPE-V QUARTERS	Rooftop of building	Phase I	2,984.68	0.85	1,576.73
60	ERB-23	GUEST HOUSE	Rooftop of building	Phase I	414.46	0.85	218.95
61	ERB-24	MARRIED SCHOLARS HOSTEL	Rooftop of building	Phase I	231.20	0.85	122.14
62	ERB-25	TRANSF. HOSTEL	Rooftop of building	Phase I	573.05	0.85	302.73
63	ERB-26	NURSERY SCHOOL	Rooftop of building	Phase I	800.00	0.85	422.62
64	ERB-27	PRINCIPALS BUNGLOW	Rooftop of building	Phase I	200.00	0.85	105.66
65	ERB-28,29,30,31	PUMP HOUSE	Rooftop of building	Phase I	420.00	0.85	221.88

Sr. No.	Blocks	Description	Type of Surface (Present Condition)	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cum/Year)
66	IRB-32	12-BED HOSPITAL	Rooftop of building	Phase I	782.40	0.85	413.32
67	IRB-33	CHLORINATION ROOM	Rooftop of building	Phase I	40.39	0.85	21.34
68	IRB-34	DISU METERING PANEL	Rooftop of building	Phase I	180.00	0.85	95.09
69	IRB-35,36,37,38	TRANSFORMER ROOMS	Rooftop of building	Phase I	1,080.00	0.85	570.54
70	IRB-5,6,7,8,9,10,11	TYPE-II QUARTERS	Rooftop of building	Phase I	1,679.37	0.85	887.17
71	P1	Parking	Road/Paved area	Phase I	1,844.74	0.65	745.23
72	P10	Parking	Road/Paved area	Phase I	1,869.28	0.65	755.14
73	P11	Parking	Road/Paved area	Phase I	1,665.75	0.65	672.32
74	P12	Parking	Road/Paved area	Phase I	667.91	0.65	269.82
75	P13	Parking	Road/Paved area	Phase I	1,788.37	0.65	722.46
76	P14	Parking	Road/Paved area	Phase I	2,259.93	0.65	912.96
77	P15	Parking	Road/Paved area	Phase I	1,101.17	0.65	444.85
78	P16	Parking	Road/Paved area	Phase I	1,869.07	0.65	735.06
79	P17	Parking	Road/Paved area	Phase I	1,463.75	0.65	591.32
80	P18	Parking	Road/Paved area	Phase I	1,416.71	0.65	572.32
81	P18A	Parking	Road/Paved area	Phase I	4,081.53	0.65	1,648.84
82	P19	Parking	Road/Paved area	Phase I	3,629.13	0.65	1,466.08
83	P2	Parking	Road/Paved area	Phase I	2,167.78	0.65	875.73
84	P20	Parking	Shed	Phase I	2,790.02	0.85	1,473.90
85	P21	Parking	Shed	Phase I	1,367.14	0.85	722.23
86	P22	Parking	Open Land	Phase I	1,339.90	0.20	166.55
87	P23	Parking	Open Land	Phase I	843.36	0.20	104.83
88	P24	Parking	Road/Paved area	Phase I	5,952.61	0.65	2,404.71

Sr. No	Blocks	Description	Type of Surface (Present Condition)	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cumf Year)
89	P25	Parking	Road/Paved area	Phase I	4,257.73	0.65	1,720.02
90	P26	Parking	Shed	Phase I	2,990.32	0.85	1,579.71
91	P26A	Parking	Shed	Phase I	11,765.50	0.85	6,215.42
92	P27	Parking	Open Land	Phase I	2,212.90	0.20	275.06
93	P28	Parking	Open Land	Phase I	441.08	0.20	54.85
94	P29	Parking	Shed	Phase I	12,549.80	0.85	6,629.75
95	P3	Parking	Open Land	Phase I	181.61	0.20	22.57
96	P30	Parking	Road/Paved area	Phase I	1,693.17	0.65	684.00
97	P31	Parking	Road/Paved area	Phase I	1,924.48	0.65	777.44
98	P32	Parking	Road/Paved area	Phase I	792.45	0.65	320.15
99	P33	Parking	Open Land	Phase I	1,606.00	0.20	199.65
100	P34	Parking	Open Land	Phase I	5,127.96	0.20	637.41
101	P35	Parking	Green Belt	Phase I	2,133.37	0.15	198.88
102	P36	Parking	Open Land	Phase I	439.52	0.20	54.63
103	P37	Parking	Road/Paved area	Phase I	3,096.83	0.65	1,251.04
104	P38	Parking	Road/Paved area	Phase I	12,120.04	0.65	4,896.19
105	P39	Parking	Road/Paved area	Phase I	5,314.06	0.65	2,146.75
106	P4	Parking	Open Land	Phase I	1,899.54	0.20	236.11
107	P40	Parking	Open Land	Phase I	1,123.56	0.20	139.66
108	P41	Parking	Open Land	Phase I	1,175.72	0.20	146.14
109	P42	Parking	Road/Paved area	Phase I	669.69	0.65	270.54
110	P43	Parking	Green Belt	Phase I	1,587.52	0.15	148.00
111	P44	Parking	Green Belt	Phase I	2,731.63	0.15	254.66

Sr. No.	Blocks	Description	Type of Surface (Present Condition)	Stage	Ground Coverage Area (sqm)	Rainoff Coefficient	Quantity of Rainoff available (Cumul. Year)
112	P45	Parking	Road/Paved area	Phase I	2,058.24	0.65	823.40
113	P46	Parking	Open Land	Phase I	419.85	0.20	52.19
114	P5	Parking	Road/Paved area	Phase I	561.60	0.65	226.87
115	P6	Parking	Open Land	Phase I	7,279.95	0.20	904.90
116	P7	Parking	Road/Paved area	Phase I	915.42	0.65	369.81
117	P8	Parking	Green Belt	Phase I	9,444.59	0.15	880.47
118	P9	Parking	Open Land	Phase I	3,974.27	0.20	494.00
119	R	Roads	Road/Paved area	Phase I	4,572.92	0.65	1,847.35
120	AB-2	ACADEMIC BUILDING	Shed	Phase IIA	2,411.95	0.85	1,274.17
121	AB-3	ACADEMIC BUILDING	Rooftop of building	Phase IIA	3,067.20	0.85	1,620.33
122	AB-4	ACADEMIC BUILDING	Rooftop of building	Phase IIA	2,650.00	0.85	1,399.93
123	AB-5	ACADEMIC BUILDING	Shed	Phase IIA	4,840.87	0.85	2,557.31
124	CB-6	SWIMMING POOL	Shed	Phase IIA	792.82	0.85	418.85
125	CB-7	INDOOR SPORTS FACILITY	Rooftop of building	Phase IIA	1,836.05	0.85	969.94
126	I15	BOYS HOSTEL	Rooftop of building	Phase IIA	520.00	0.85	274.70
127	I1B-6	GIRLS HOSTEL	Rooftop of building	Phase IIA	520.00	0.85	274.70
128	I1C-5	GIRLS HOSTEL	Rooftop of building	Phase IIA	496.42	0.85	262.25
129	AB-4A	ACADEMIC BUILDING RECEPTION	Road/Paved area	Phase IIB	800.00	0.65	323.18
130	CB-2	DINING HALL (BOYS)	Open Land	Phase IIB	1,623.70	0.20	201.85
131	CB-4	DINING HALL (GIRLS)	Open Land	Phase IIB	769.09	0.20	95.60
132	I14	BOYS HOSTEL	Open Land	Phase IIB	496.42	0.20	61.71
133	Rest of the area		Open Land	Phase I	392,232.21	0.58	141,424.78
Totals					666,144.35	461006.78	238,341.75

Table A.2. RWH Potential at Delhi Technological University as per Master Plan

Sr. No.	Blocks	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cum/Year)
1	AB-1	ACADEMIC BUILDING	Rooftop of building	Future Phases	5,053.11	0.85	2,669.43
2	AB-3A	SEMINAR HALL	Rooftop of building	Future Phases	442.00	0.85	233.50
3	AB-6	ACADEMIC BUILDING	Rooftop of building	Future Phases	1,578.92	0.85	834.10
4	AB-7	ACADEMIC BUILDING	Rooftop of building	Future Phases	1,563.88	0.85	826.16
5	AB-8	ACADEMIC BUILDING	Rooftop of building	Future Phases	2,095.10	0.85	1,106.79
6	AB-9	MULTIPURPOSE HALL	Rooftop of building	Future Phases	1,000.00	0.85	528.28
7	CB-1	ACTIVITY CENTRE	Rooftop of building	Future Phases	1,431.16	0.85	756.05
8	CB-3	DINING HALL (BOYS)	Rooftop of building	Future Phases	1,623.70	0.85	857.76
9	CB-5	DINING HALL (GIRLS)	Rooftop of building	Future Phases	873.61	0.85	461.51
10	H-12ME 1	BOYS HOSTEL	Rooftop of building	Future Phases	386.40	0.85	204.13
11	H-12ME 2	BOYS HOSTEL	Rooftop of building	Future Phases	386.40	0.85	204.13
12	H1	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
13	H10	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
14	H11	BOYS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
15	H12	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
16	H13	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
17	H14	BOYS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
18	H15	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
19	H16	BOYS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
20	I12	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25

Sr. No.	Blocks	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantum of Runoff available (Cumul Year)
21	H3	BOYS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
22	H6	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
23	H7	BOYS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
24	H8	BOYS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
25	H9	BOYS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
26	HG-1	GIRLS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
27	HG-12ME	GIRLS HOSTEL	Rooftop of building	Future Phases	386.40	0.85	204.13
28	HG-2	GIRLS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
29	HG-3	GIRLS HOSTEL	Rooftop of building	Future Phases	520.00	0.85	274.70
30	HG-4	GIRLS HOSTEL	Rooftop of building	Future Phases	496.42	0.85	262.25
31	MLCP-1	Multi Level Car Parking	Rooftop of building	Future Phases	6,588.15	0.85	3,480.35
32	MLCP-2	Multi Level Car Parking	Rooftop of building	Future Phases	2,701.78	0.85	1,427.28
33	MLCP-3	Multi Level Car Parking	Rooftop of building	Future Phases	2,384.37	0.85	1,259.60
34	MLCP-4	Multi Level Car Parking	Rooftop of building	Future Phases	1,216.57	0.85	642.68
35	MLCP-5	Multi Level Car Parking	Rooftop of building	Future Phases	1,031.01	0.85	544.66
36	R8-12,13,14,15,16,17,18,19	H.O.D	Rooftop of building	Future Phases	1,432.00	0.85	756.49
37	RB-1,2	TYPE-III QUARTERS	Rooftop of building	Future Phases	898.00	0.85	474.39
38	RB-10,11	TYPE-I QUARTERS	Rooftop of building	Future Phases	3,163.14	0.85	1,671.01
39	RB-3,4	TYPE-IV QUARTERS	Rooftop of building	Future Phases	1,652.00	0.85	872.71
40	RB-5,6,7,8	TYPE-V QUARTERS	Rooftop of building	Future Phases	3,304.00	0.85	1,745.42
41	RB-9, RB-20, RB-21	TYPE-I QUARTERS	Rooftop of building	Future Phases	1,678.17	0.85	886.54
42	EAB-1	ADMIN.	Rooftop of building	Phase I	1,879.40	0.85	992.84

Sr. No.	Blocks	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cum/Year)
43	EAB-10	CANTINE	Rooftop of building	Phase I	700.00	0.85	369.79
44	EAB-11	GATE COMPLEX	Shed	Phase I	22.80	0.85	12.04
45	EAB-2	MULTIPURPOSE	Rooftop of building	Phase I	2,500.00	0.85	1,320.69
46	EAB-3	LIBRARY	Rooftop of building	Phase I	2,000.00	0.85	1,056.55
47	EAB-4	COMP. CENTRE	Rooftop of building	Phase I	1,500.00	0.85	792.41
48	EAB-5	DEPT. OF CIVIL	Rooftop of building	Phase I	9,628.64	0.85	5,086.57
49	EAB-6	DEPT OF PROD. MACHI	Rooftop of building	Phase I	4,208.83	0.85	2,223.42
50	EAB-7	WORKSHOP	Shed	Phase I	3,416.20	0.85	1,804.69
51	EAB-8	DEPT. OF PHYS. CHEM.	Rooftop of building	Phase I	2,817.43	0.85	1,488.38
52	EAB-9	TURBINE WIND TUNNEL	Shed	Phase I	2,000.00	0.85	1,056.55
53	EIB-1,2,3,4,5	BOYS HOSTEL	Rooftop of building	Phase I	9,745.85	0.85	5,148.49
54	EIB-6	GIRLS HOSTEL	Rooftop of building	Phase I	776.83	0.85	410.38
55	EIB-7	PG HOSTEL	Rooftop of building	Phase I	2,129.17	0.85	1,124.79
56	ERB-1,2,3,4	TYPE-I QUARTERS	Rooftop of building	Phase I	803.12	0.85	424.27
57	ERB-12,13,14	TYPE-III QUARTERS	Rooftop of building	Phase I	878.28	0.85	463.97
58	ERB-15,16,17,18	TYPE-IV QUARTERS	Rooftop of building	Phase I	1,565.56	0.85	827.05
59	ERB-19,20,21,22	TYPE-V QUARTERS	Rooftop of building	Phase I	2,984.68	0.85	1,576.73
60	ERB-23	GUEST HOUSE	Rooftop of building	Phase I	414.46	0.85	218.95
61	ERB-24	MARRIED SCHOLARS HOSTEL	Rooftop of building	Phase I	231.20	0.85	122.14
62	ERB-25	TRANSIT HOSTEL	Rooftop of building	Phase I	573.05	0.85	302.73
63	ERB-26	NURSERY SCHOOL	Rooftop of building	Phase I	800.00	0.85	422.62
64	ERB-27	PRINCIPAL'S BUNGLOW	Rooftop of building	Phase I	200.00	0.85	105.66


Sr. No	Blocks	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Rainfall Coefficient	Quantity of Rainfall available (Cumul Year)
65	ERB-28,29,30,31	PUMP HOUSE	Rooftop of building	Phase I	420.00	0.85	221.88
66	ERB-32	12-BED HOSPITAL	Rooftop of building	Phase I	782.40	0.85	413.12
67	ERB-33	CHLORINATION ROOM	Rooftop of building	Phase I	41.39	0.85	21.34
68	ERB-34	DESU MITTERING PANEL	Rooftop of building	Phase I	180.00	0.85	95.09
69	ERB-35,36,37,38	TRANSFORMER ROOMS	Rooftop of building	Phase I	1,080.00	0.85	571.54
70	ERB-5,6,7,8,9,10,11	TYPE-II QUARTERS	Rooftop of building	Phase I	1,679.37	0.85	887.17
71	P1	Parking	Road/Paved area	Phase I	1,844.74	0.65	745.25
72	P10	Parking	Road/Paved area	Phase I	1,869.28	0.65	755.14
73	P11	Parking	Road/Paved area	Phase I	1,665.75	0.65	672.92
74	P12	Parking	Road/Paved area	Phase I	667.91	0.65	269.82
75	P13	Parking	Road/Paved area	Phase I	1,788.37	0.65	722.46
76	P14	Parking	Road/Paved area	Phase I	2,259.93	0.65	912.96
77	P15	Parking	Road/Paved area	Phase I	1,101.17	0.65	444.85
78	P16	Parking	Road/Paved area	Phase I	1,869.07	0.65	755.06
79	P17	Parking	Road/Paved area	Phase I	1,463.75	0.65	591.32
80	P18	Parking	Road/Paved area	Phase I	1,416.71	0.65	572.32
81	P18A	Parking	Road/Paved area	Phase I	4,081.53	0.65	1,648.84
82	P19	Parking	Road/Paved area	Phase I	3,629.13	0.65	1,466.08
83	P2	Parking	Road/Paved area	Phase I	2,167.78	0.65	873.73
84	P20	Parking	Road/Paved area	Phase I	2,790.02	0.65	1,127.10
85	P21	Parking	Road/Paved area	Phase I	1,367.14	0.65	552.29
86	P22	Parking	Road/Paved area	Phase I	1,339.90	0.65	541.29

Sr. No.	Block	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Rainfall Coefficient	Quantity of Rainfall available (Cum/Year)
87	P23	Parking	Road/Paved area	Phase I	843.36	0.65	340.70
88	P24	Parking	Road/Paved area	Phase I	5,952.61	0.65	2,404.71
89	P25	Parking	Road/Paved area	Phase I	4,257.73	0.65	1,720.02
90	P26	Parking	Road/Paved area	Phase I	11,765.50	0.65	4,732.97
91	P27	Parking	Road/Paved area	Phase I	2,212.90	0.65	893.96
92	P28	Parking	Road/Paved area	Phase I	441.08	0.65	178.19
93	P29	Parking	Road/Paved area	Phase I	12,549.80	0.65	5,069.81
94	P3	Parking	Road/Paved area	Phase I	181.61	0.65	73.37
95	P30	Parking	Road/Paved area	Phase I	1,693.17	0.65	684.00
96	P31	Parking	Road/Paved area	Phase I	1,924.48	0.65	777.44
97	P32	Parking	Road/Paved area	Phase I	792.45	0.65	320.13
98	P33	Parking	Road/Paved area	Phase I	1,606.00	0.65	648.78
99	P34	Parking	Road/Paved area	Phase I	5,127.96	0.65	2,071.57
100	P35	Parking	Road/Paved area	Phase I	2,133.37	0.65	861.85
101	P36	Parking	Road/Paved area	Phase I	439.52	0.65	177.56
102	P37	Parking	Road/Paved area	Phase I	3,096.83	0.65	1,251.04
103	P38	Parking	Road/Paved area	Phase I	12,120.04	0.65	4,896.19
104	P39	Parking	Road/Paved area	Phase I	5,314.06	0.65	2,146.75
105	P4	Parking	Road/Paved area	Phase I	1,899.54	0.65	767.37
106	P40	Parking	Road/Paved area	Phase I	1,123.56	0.65	453.89
107	P41	Parking	Road/Paved area	Phase I	1,175.72	0.65	474.96
108	P42	Parking	Road/Paved area	Phase I	669.69	0.65	270.54


Sr. No.	Blocks	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Runoff Coefficient	Quantity of Runoff available (Cumul Year)
109	P43	Parking	Road/Paved area	Phase I	1,587.52	0.65	641.32
110	P44	Parking	Road/Paved area	Phase I	2,731.63	0.65	1,103.51
111	P45	Parking	Road/Paved area	Phase I	2,038.24	0.65	823.40
112	P46	Parking	Road/Paved area	Phase I	419.85	0.65	169.61
113	P5	Parking	Road/Paved area	Phase I	561.61	0.65	226.87
114	P6	Parking	Road/Paved area	Phase I	7,279.95	0.65	2,940.92
115	P7	Parking	Road/Paved area	Phase I	915.42	0.65	369.81
116	P8	Parking	Road/Paved area	Phase I	9,444.59	0.65	3,815.38
117	P9	Parking	Road/Paved area	Phase I	3,974.27	0.65	1,605.51
118	AB-2	ACADEMIC BUILDING	Rooftop of building	Phase IIA	2,411.95	0.85	1,274.17
119	AB-3	ACADEMIC BUILDING	Rooftop of building	Phase IIA	3,067.20	0.85	1,620.33
120	AB-4	ACADEMIC BUILDING	Rooftop of building	Phase IIA	2,650.00	0.85	1,399.95
121	AB-5	ACADEMIC BUILDING	Rooftop of building	Phase IIA	4,840.87	0.85	2,557.51
122	CB-6	SWIMMING POOL	Rooftop of building	Phase IIA	792.82	0.85	418.83
123	CB-7	INDOOR SPORTS FACILITY	Rooftop of building	Phase IIA	1,836.05	0.85	969.94
124	IB-5	BOYS HOSTEL	Rooftop of building	Phase IIA	520.00	0.85	274.70
125	IB-6	GIRLS HOSTEL	Rooftop of building	Phase IIA	520.00	0.85	274.70
126	IG-5	GIRLS HOSTEL	Rooftop of building	Phase IIA	496.42	0.85	262.25
127	AB-4A	ACADEMIC BUILDING RECEPTION	Rooftop of building	Phase IIB	800.00	0.85	422.62
128	CB-2	DINING HALL (BOYS)	Rooftop of building	Phase IIB	1,623.70	0.85	857.76
129	CB-4	DINING HALL (GIRLS)	Rooftop of building	Phase IIB	769.09	0.85	406.29

Sr. No	Blocks	Description	Type of Surface	Stage	Ground Coverage Area (sqm)	Roads Coefficient	Quantity of Roads available (Cum/Year)
130	114	BOYS HOSTEL.	Rooftop of building	Phase 11B	496.42	0.85	262.25
131	R	Roads	Road/Paved area	Phase 1	4,572.92	0.65	1,847.15
132	Rest of the area		Open Land	Phase 1	392,232.21	0.58	141,424.78
Totals					663,154.03	461006.78	266,874.38


Rain Water Harvesting Pits







 **GPS Map Camera**



Delhi, Delhi, भारत

H No. A-3 Kh. No. 15/25 & 26/5 Ground floor Prakash Vihar Shahbad Ext, Ph.-2,
Bawana Rd, Delhi Technological University, Shahbad Daulatpur Village, Rohini, Delhi,
110042, भारत

Lat 28.750308°

Long 77.112422°


03/06/24 02:56 PM GMT +05:30




 GPS Map Camera



Delhi, Delhi, भारत
H_no 358, Shahabad Daulatpur, Delhi Technological University, Shahbad
Daulatpur Village, Alipur, Delhi, 110042, भारत
Lat 28.75015°
Long 77.113562°
03/06/24 02:55 PM GMT +05:30



 **GPS Map Camera**



Delhi, Delhi, भारत

H No. A-3 Kh. No. 15/25 & 26/5 Ground floor Prakash Vihar Shahbad Ext, Ph.-2, Bawana Rd, Delhi Technological University, Shahbad Daulatpur Village, Rohini, Delhi, 110042, भारत

Lat 28.750323°

Long 77.112487°

03/06/24 03:48 PM GMT +05:30



 **GPS Map Camera**



Delhi, Delhi, भारत

H_no 358, Shahabad Daulatpur, Delhi Technological University, Shahbad Daulatpur Village, Alipur, Delhi, 110042, भारत

Lat 28.750204°

Long 77.11388°

03/06/24 03:50 PM GMT +05:30




Delhi, Delhi, भारत

H_no 358, Shahabad Daulatpur, Delhi Technological University, Shahbad Daulatpur Village, Alipur, Delhi, 110042, भारत

Lat 28.750204°

Long 77.11388°

03/06/24 03:51 PM GMT +05:30

 GPS Map Camera



दिल्ली, दिल्ली, भारत

52/23, दिल्ली तेज्जोलोगिकल युनिवर्सिटी, शाहबाद दौलतपुर गाँव, बुरारी, दिल्ली, 110084, भारत


Lat 28.749357°

Long 77.113576°

03/06/24 03:53 PM GMT +05:30


 GPS Map Camera



 GPS Map Camera

दिल्ली, दिल्ली, भारत
52/23, दिल्ली तेज्जोलोगिकल युनिवर्सिटी, शाहबाद दौलतपुर गाँव, बुरारी, दिल्ली, 110084, भारत
Lat 28.749679°
Long 77.113783°
03/06/24 03:52 PM GMT +05:30



 GPS Map Camera


दिल्ली, दिल्ली, भारत
52/23, दिल्ली तेज्जोलोगिकल युनिवर्सिटी, शाहबाद दौलतपुर गाँव, बुरारी, दिल्ली, 110084, भारत
Lat 28.74968°
Long 77.11376°
03/06/24 02:51 PM GMT +05:30



Details of Roof Top Rain Water Harvesting Structures at various installations in Delhi Technological University

Sr. No.	Location of RWH Structure	Latitude	Longitude	Total Plot Area (in)	Roof Top Area (in)	Size of Pit(s) LxBxH	Total (Cum.)	Functional		Quantum of Run off available (Cum/Year)
								Yes	No	
1	Academic Block 3	28.750204	77.11388			5.5x2.0x2.0 mtr.	22.00	Yes		
2	Academic Block 3	28.750204	77.11388	1809.00	1809.00	8.0x2.0x2.0 mtr.	32.00	Yes		1620.33
3	Academic Block 4	28.749679	77.113783			5.5x2.0x2.0 mtr.	22.00	Yes		
4	Academic Block 4	28.749357	77.113576	2285.00	2285.00	8.0x2.0x2.0 mtr.	32.00	Yes		1399.93
5	APJ Hostel	28.750323	77.112487			5.5x2.0x2.0 mtr.	22.00	Yes		
6	APJ Hostel	28.750323	77.112487	491.00	491.00	8.0x2.0x2.0 mtr.	32.00	Yes		274.7
						Total	162.00	6		3294.96


Maintenance of Water Body – DTU Lake



Waste to Energy Plant






 **GPS Map Camera**

Delhi, Delhi, India

H No. A-3 Kh. No. 15/25 & 26/5 Ground floor Prakash Vihar Shahbad Ext, Ph.-2, Bawana Rd, Delhi Technological University, Shahbad Daulatpur Village, Rohini, Delhi, 110042, India
Lat 28.750263°
Long 77.112296°
12/07/24 12:03 PM GMT +05:30





 **GPS Map Camera**



Delhi, Delhi, India

H No. A-3 Kh. No. 15/25 & 26/5 Ground floor Prakash Vihar Shahbad Ext,
Ph.-2, Bawana Rd, Delhi Technological University, Shahbad Daultapur Village,
Rohini, Delhi, 110042, India
Lat 28.750343°
Long 77.112354°
12/07/24 12:02 PM GMT +05:30



मुख्य अभियंता(अन्य परियोजनाएं)
लो०नि०वि०, (रा०रा०क्षे०दि०स०),
13वां तल, एम०एस०ओ० भवन,
आई०पी० एस्टेट, नई दिल्ली-02
फोन:23490426, 23490427, 23490428
ई-मेल: cepwddelhiop@gmail.com

Mr. Akshay
(C.D.)
दिल्ली सरकार
P.W.D.
16/8


सं०: 23(53)/मु०अभि०(ओ०पी०)/लो०नि०वि०/2023-24/891/ए

दिनांक: 5-7-2023

30-11

सेवा में,

The Joint Director (Tech./Plg.)
Development of Training and Technical Education,
GNCTD, Muni Maya Ram Marg,
Pitampura, Delhi-110034



विषय: Comprehensive Consultancy for Planning and Development of Student Activity Centre and beautification of existing pond at Delhi Technological University at Bawana Road, Delhi.

महोदय,

Please find enclosed a Preliminary Estimate of the above mentioned work for the probable cost of Rs. 48,26,046/- i/c 1% contingencies and 18% GST has been framed for accord of Administrative Approval and Expenditure Sanction of the Competent Authority.

Accordingly, this Preliminary Estimate is submitted for accord of A/A & E/S from the Competent Authority.

This issues with the approval of Chief Engineer (OP).

संलग्न: प्रारंभिक प्राक्कलन

भवदीय,

कार्यपालक अभियंता (मु०)

प्रतिलिपि:-

- परियोजना प्रबन्धक (उ०शि०परि०), लो०नि०वि०, दिल्ली सरकार, भाई निहाल सिंह मार्ग, लाजपत नगर-4, नई दिल्ली-110024 को उनके पत्र सं० 23(63)/DTU/परि०प्रबं०(उ०शि०परि०)/लो०नि०वि०/2023/508 दिनांक 23.06.2023 के संदर्भ में सूचनार्थ हेतु प्रेषित।
- कार्यपालक अभियंता (सि०), शिक्षा परियोजना मंडल-4, लो०नि०वि०, (दि०स०), ए ब्लॉक, प्रथमतल, विकास भवन-4, सिविल लाईन, दिल्ली-110054 को सूचनार्थ हेतु प्रेषित।

UDC
8/12

PLP
R.K.

कार्यपालक अभियंता (मु०)
8/12/23

Email/Speed Post/By Hand



लोक निर्माण विभाग,
कार्यालय कार्यपालक अभियंता
शिक्षा परियोजना मंडल-4 लो.नि.वि.
दिल्ली सरकार, ए ब्लॉक, प्रथम तल,
विकास भवन-2, सिविल
लाइन्स दिल्ली-110054

Public Works Department
O/o Executive Engineer,
Education Project Division-4
P.W.D. Government of NCT of
Delhi, A Block, 1st Floor, Vikas
Bhawan-II,
Civil Lines, Delhi-110054



011-23813801

E-Mail : eepwddelhiedu4@gmail.com

दिनांक: 07/08/2023

सं. 23(3)/का.अभि./शिक्षा परि.मं.-4/लो.नि.वि./2023-24/455

सेवा में,

प्रो. अमित श्रीवास्तव,
मुख्य परियोजना अधिकारी,
दिल्ली टेक्नोलॉजिकल यूनिवर्सिटी,
शाहबाद दौलतपुर, बवानारोड,
दिल्ली-110042

1618

Mr. Ashish (C.O.)

विषय:-Development of existing pond including construction of student activity centre at Delhi Technological University, Bawana Road, Delhi.

संदर्भ:-आपके कार्यालय का पत्र सं.DTU/Engg.Cell/003544/2022-23/Civil/1260-66
दिनांक 27.07.2023

महोदय,

Reference to the above subject, this is to inform that Preliminary Estimate of providing consultancy services for the above mentioned work amounting to Rs. 48,26,046/- has been forwarded to Joint Director (Tech/Planning), DTTE by Chief Engineer (Other Projects) vide their letter No. 23(53)/मु.अभि.(ओ.पी.)/लो.नि.वि./2023-24/901-हि dated 05.07.2023 (Copy attached). The A/A & E/S of same is awaited.

This is for your information and necessary action please.

संलग्न:-As above

Roshini
07/08/23

कार्यपालक अभियंता
शिक्षा परि.मंडल-4, लो.नि.वि

प्रतिलिपि:-

1. मुख्य अभियंता (अन्य परियोजनायें), लो.नि.वि., दिल्ली सरकार, 13वाँ तल, एम.एस. ओ. भवन, आई. पी.एस्टेट, नई दिल्ली-110002 को सूचनार्थ।
2. परियोजना प्रबन्धक (उच्च शिक्षा परियोजनायें), लोक निर्माण विभाग, लाजपत नगर-4, नियर, केन्द्रीय विद्यालय, एन्ड्रयूज गंज, नई दिल्ली-110024 को सूचनार्थ।
3. सहायक अभियंता-1, शिक्षा परियोजना मंडल-4, लो.नि.वि, दिल्ली को सूचनार्थ एवं आवश्यक कार्यवाही हेतु।
4. गार्ड फाईल।

11971/00
9/8/23
16/8/2023

कार्यपालक अभियंता

Absolute Water Private Limited

M-58, Market
Greater Kailash-II
New Delhi-110048
Delhi

MSME NO.UDYAM -DL-08-0002045
CIN: U29190DL2016PTC289934

Delhi Technological University

Ledger Account

Delhi Technological University
Shahbad Daulatpur
Main Bawana Road
Delhi-110042

1-Apr-23 to 31-Mar-24

Page 1

Date	Particulars	Vch Type	Vch No.	Debit	Credit
1-Apr-23	Dr Opening Balance				1,63,385.34
3-May-23	Cr Sale of Services	Sales	SI/23-24/03	2,28,000.00	
8-May-23	Dr Bank of Baroda <i>Beign amt of NEFT recd</i>	Receipt	9		3,33,216.00
	Dr CGST CASH LEDGER <i>Beign amt of GST TDS on rs.347100/-</i>	Journal	152		6,942.00
	Dr TDS (R) <i>Beign amt of TDS deducted</i>	Journal	155		6,942.00
3-Jun-23	Cr Sale of Services	Sales	SI/23-24/07	2,28,000.00	
21-Jun-23	Dr Bank of Baroda <i>Beign amt of NEFT recd</i>	Receipt	18		3,33,216.00
	Dr CGST CASH LEDGER <i>Being amt of GST TDS on Rs.347100/-</i>	Journal	153		6,942.00
	Dr TDS (R) <i>Beign amt of TDS deducted</i>	Journal	154		6,942.00
1-Jul-23	Cr Sale of Services	Sales	SI/23-24/10	2,37,800.00	
18-Jul-23	Cr Sale of Services	Sales	SI/23-24/14	59,000.00	
31-Jul-23	Cr Sale of Services	Sales	SI/23-24/15	2,42,000.00	
2-Aug-23	Dr Bank of Baroda <i>Being amt of NEFT recd</i>	Receipt	30		3,42,388.00
	Dr CGST CASH LEDGER <i>Beign amt of TDS deducted</i>	Journal	156		7,134.00
	Dr TDS (R) <i>Beign amt of TDS deducted</i>	Journal	157		7,133.00
31-Aug-23	Cr Sale of Services	Sales	SI/23-24/19	2,42,000.00	
4-Oct-23	Cr Sale of Services	Sales	SI/23-24/24	2,42,000.00	
3-Nov-23	Cr Sale of Services	Sales	SI/23-24/30	2,42,000.00	
21-Nov-23	Cr Sale of Services	Sales	SI/23-24/34	59,000.00	
2-Dec-23	Cr Sale of Services	Sales	SI/23-24/36	2,42,000.00	
28-Dec-23	Dr Bank of Baroda <i>Being amt recd from</i>	Receipt	72		56,820.00
	Dr CGST CASH LEDGER <i>Being amt of GST TDS</i>	Journal	756		1,000.00
	Dr TDS (R) <i>Beign amt of TDS deducted</i>	Journal	757		1,000.00
2-Jan-24	Cr Sale of Services	Sales	SI/23-24/41	2,42,000.00	
7-Feb-24	Cr Sale of Services	Sales	SI/23-24/47	2,42,000.00	
4-Mar-24	Dr Bank of Baroda <i>Beign amt of NEFT recd UTR NO. SBIN524064906240</i>	Receipt	82		8,82,350.00
	Carried Over			25,05,800.00	21,55,410.34

continued ...

Absolute Water Private Limited

Delhi Technological University Ledger Account : 1-Apr-23 to 31-Mar-24

Page 2

Date	Particulars	Vch Type	Vch No.	Debit	Credit
	Brought Forward			25,05,800.00	21,55,410.34
4-Mar-24	Dr CGST CASH LEDGER <i>Being amt of GST TDS</i>	Journal	762		24,610.00
	Dr TDS (R) <i>Beign amt of TDS deducted</i>	Journal	843		24,610.00
5-Mar-24	Cr Sale of Services	Sales	SI/23-24/51	2,42,000.00	
30-Mar-24	Cr Sale of Services	Sales	SI/23-24/57	2,42,000.00	
				29,89,800.00	22,04,630.34
	Dr Closing Balance				7,85,169.66
				29,89,800.00	29,89,800.00

Absolute Water Private Limited

M-58, IInd Floor, Market

Greater Kailash-II

New Delhi-110048

Delhi

MSME NO.DL08D0005736

CIN: U29190DL2016PTC289934

Delhi Technological University

Ledger Account

Delhi Technological University

Shahbad Daulatpur

Main Bawana Road

Delhi-110042

1-Apr-18 to 31-Mar-19

						Page 1	
Date	Particulars	Vch Type	Vch No.	Debit		Credit	
25-Jul-18	Cr Civil Work (Income) <i>Being invoice No.SI/17-18/06 dt 25/07/18 for first running bill for vivitwork STP & WTEP</i>	Journal	86	31,86,000.00			
14-Aug-18	Cr Sale with in State	Sales	11	29,50,000.00			
23-Aug-18	Dr Dena Bank <i>Being amt of RTGS RECD</i>	Receipt	19			24,76,046.00	
	Dr TDS (R) <i>Being amt of TDS deducted agst Rs. 2526572/- from 01/07 to 30/09/18</i>	Journal	135			50,532.00	
8-Oct-18	Dr Dena Bank <i>Being amt of NEFT recd agt ino.11</i>	Receipt	27			21,79,199.00	
	Dr CGST CASH LEDGER <i>GST TDs deducted for the month of Oct -2018 on amt of Taxable Value on RS. 2293894/-</i>	Journal	178			45,878.00	
	Dr Labour Cess <i>Being amt of 1% Labour cess deducted</i>	Journal	179			22,939.00	
6-Nov-18	Cr Sale with in State	Sales	29	68,25,000.00			
21-Nov-18	Cr Civil Work (Income) <i>Invoice No.SI/18-19/15 dt 21/11/18</i>	Journal	216	40,12,000.00			
1-Dec-18	Cr Sale with in State	Sales	30	5,69,232.00			
3-Dec-18	Cr Sale with in State	Sales	31	5,16,557.00			
14-Dec-18	Cr Sale with in State	Sales	33	5,77,728.00			
17-Dec-18	Cr Sale with in State	Sales	34	10,38,778.00			
26-Dec-18	Cr Sale with in State	Sales	35	5,14,291.00			
27-Dec-18	Dr Dena Bank <i>Being amt of NEFT received</i>	Receipt	38			50,00,000.00	
	Dr Dena Bank <i>Being amt of NEFT recd</i>	Receipt	39			50,00,000.00	
	Dr Dena Bank <i>Being amt of NEFT recd</i>	Receipt	40			9,09,622.00	
28-Dec-18	Cr Sale with in State	Sales	36	1,25,174.00			
30-Dec-18	Dr Labour Cess <i>Being amt deducted</i>	Journal	251			1,14,838.00	
9-Jan-19	Dr CGST CASH LEDGER <i>amount received tds on ass. value of rs. 11483812/-</i>	Journal	270			2,29,676.00	
21-Feb-19	Dr Dena Bank <i>Being amt of NEFT recd</i>	Receipt	47			42,52,506.00	
25-Feb-19	Cr Sale with in State	Sales	38	1,68,811.00			
	Carried Over			2,04,83,571.00		2,02,81,236.00	

continued ...

Date	Particulars	Vch Type	Vch No.	Debit	Credit
	Brought Forward			2,04,83,571.00	2,02,81,236.00
28-Feb-19	Dr CGST CASH LEDGER <i>Being amt of GST TDS</i>	Journal	306		89,526.00
	Dr TDS (R) <i>Being amt of TDS deducted from 1/10 to 31 /12/2018</i>	Journal	307		2,75,554.00
	Dr Labour Cess <i>Being amt of 1% cess deducted</i>	Journal	312		44,763.00
5-Mar-19	Cr Sale with in State	Sales	39	2,78,480.00	
6-Mar-19	Cr Sale with in State	Sales	40	56,000.00	
	Cr Sale with in State	Sales	41	4,12,930.00	
	Cr Sale with in State	Sales	42	6,50,720.00	
7-Mar-19	Cr Sale with in State	Sales	43	64,670.00	
	Cr Sale with in State	Sales	44	64,890.00	
8-Mar-19	Cr Sale with in State	Sales	45	62,811.00	
	Cr Sale with in State	Sales	46	63,284.00	
	Cr Sale with in State	Sales	47	63,630.00	
11-Mar-19	Cr Sale with in State	Sales	48	63,788.00	
	Cr Sale with in State	Sales	49	45,719.00	
17-Mar-19	Cr Sale with in State	Sales	50	7,74,080.00	
18-Mar-19	Cr Sale with in State	Sales	51	66,938.00	
19-Mar-19	Cr Sale with in State	Sales	52	66,938.00	
20-Mar-19	Cr Sale with in State	Sales	53	39,375.00	
	Cr Sale with in State	Sales	54	73,185.00	
	Cr Sale with in State	Sales	55	73,185.00	
	Cr Sale with in State	Sales	56	73,185.00	
	Cr Sale with in State	Sales	57	73,185.00	
22-Mar-19	Cr Sale with in State	Sales	58	73,185.00	
30-Mar-19	Cr Civil Work (Income) <i>Being Ino.SI/18-19/24 dt 30/03/19</i>	Journal	345	40,12,000.00	
	Cr Sale with in State	Sales	61	77,880.00	
	Cr Sale with in State	Sales	62	47,200.00	
31-Mar-19	Dr CGST CASH LEDGER <i>Being amt of TDS gst on Rs.5487809/-</i>	Journal	354		1,09,756.00
	Dr TDS (R) <i>Being amt of TDS deducted</i>	Journal	369		1,99,282.00
				2,77,60,829.00	2,10,00,117.00
	Dr Closing Balance				67,60,712.00
				2,77,60,829.00	2,77,60,829.00

Absolute Water Private Limited

M-58, IInd Floor, Market

Greater Kailash-II

New Delhi-110048

Delhi

MSME NO.DL08D0005736

CIN: U29190DL2016PTC289934

Delhi Technological University

Ledger Account

Delhi Technological University

Shahbad Daulatpur

Main Bawana Road

Delhi-110042

1-Apr-19 to 31-Mar-20

Page 1

Date	Particulars	Vch Type	Vch No.	Debit	Credit
1-Apr-19	Cr Opening Balance			67,60,712.00	
5-Apr-19	Dr Dena Bank <i>Being amt of NEFT recd fromDTU , SBIN519095536522</i>	Receipt	4		50,00,000.00
	Dr Dena Bank <i>Being amt of NEFT recd UTR NO. sbin519095529868</i>	Receipt	5		2,13,419.00
9-Apr-19	Cr Sale with in State	Sales	19003	98,175.00	
10-Apr-19	Cr Sale with in State	Sales	19004	80,850.00	
	Cr Sale with in State	Sales	19005	83,738.00	
	Cr Sale with in State	Sales	19006	46,200.00	
17-Apr-19	Cr Sale with in State	Sales	19007	20,951.00	
18-Apr-19	Cr Sale with in State	Sales	19008	27,750.00	
19-Apr-19	Cr Sale with in State	Sales	19009	85,050.00	
20-Apr-19	Cr Sale with in State	Sales	19010	64,134.00	
23-Apr-19	Cr Sale with in State	Sales	19011	63,567.00	
24-Apr-19	Cr Sale with in State	Sales	19012	63,693.00	
27-Apr-19	Cr Sale with in State	Sales	19013	63,063.00	
	Cr Sale with in State	Sales	19014	15,008.00	
4-May-19	Cr Sale with in State	Sales	19015	72,813.00	
	Cr Sale with in State	Sales	19016	50,000.00	
10-May-19	Cr Sale of Services <i>Invoice No.SI/19-20/04 dt 10/05/19</i>	Journal	58	15,34,000.00	
15-May-19	Cr Sale of Services <i>Being Ino.SI/19-20/05 dt 15/05/19</i>	Journal	62	5,31,000.00	
16-May-19	Cr Sale with in State	Sales	19017	29,500.00	
6-Jun-19	Cr Sale of Services <i>Beoing Invoice No.SI/19-20/09 dt 06/6/19</i>	Journal	89	1,32,870.00	
	Cr Sale of Services <i>Being Invoice No.SI/19-20/10 dt 06/06/2019</i>	Journal	90	8,37,800.00	
	Cr Sale of Services <i>Invoice No.SI/19-20/11 dt 6/6/19 for Hiring od Super Sucker Machine with Dump Tank for cleaning of Sewer</i>	Journal	91	4,79,564.00	
8-Aug-19	Cr Sale of Services <i>Being alno.SI/119-20/17 dt 08/08/2019-Vivil Work with material</i>	Journal	175	1,85,260.00	
27-Aug-19	Dr Labour Cess <i>Beign amt of Labour cess 21% deducted</i>	Journal	192		65,250.00
29-Aug-19	Dr Dena Bank <i>Being amt of RTGS recd</i>	Receipt	36		50,00,000.00

Carried Over


1,13,25,698.00 1,02,78,669.00


continued ...


Date	Particulars	Vch Type	Vch No.	Debit	Credit
	Brought Forward			1,13,25,698.00	1,02,78,669.00
29-Aug-19	Dr Dena Bank <i>Being amt of NEFT recd</i>	Receipt	37		11,98,703.00
31-Aug-19	Dr CGST CASH LEDGER <i>Being amt of GST TDS on Rs.6524952/-</i>	Journal	202		1,30,500.00
12-Oct-19	Cr Sale of Services <i>Being Invoice No.SI/19-20/22 dt 12/10/2019</i>	Journal	285	2,02,960.00	
4-Nov-19	Cr Sale of Services <i>Invoice No.SI/19-20/25 dt 4/11/2019</i>	Journal	315	1,44,037.00	
	Cr Sale of Services <i>Invoice No.SI/19-20/26 dt 04/11/2019</i>	Journal	316	3,21,836.00	
3-Dec-19	Cr Sale of Services <i>Invoice No.SI/19-20/29 DT 03/12/2019</i>	Journal	368	2,02,960.00	
10-Dec-19	Dr Labour Cess <i>Being amt of 10% CESS deducted</i>	Journal	378		6,519.00
11-Dec-19	Dr Dena Bank <i>Being amt of NEFT recd</i>	Receipt	67		6,21,278.00
31-Dec-19	Dr CGST CASH LEDGER <i>Being amt of GST TDS deducted</i>	Journal	394		11,048.86
6-Jan-20	Cr Sale of Services <i>Invoice No.SI/19-20/31 dt 06/01/20</i>	Journal	414	2,02,960.00	
6-Feb-20	Cr Sale of Services <i>Invoice No.SI/19-20/35 dt 6/2/20</i>	Journal	452	2,02,960.00	
14-Feb-20	Dr Dena Bank <i>Being amt of NEFT recd</i>	Receipt	81		3,90,922.00
	Dr CGST CASH LEDGER <i>Being amt of GST tax deducted</i>	Journal	457		6,880.00
2-Mar-20	Cr Sale of Services <i>Invoice No.SI/19-20/38 dt 02/3/20</i>	Journal	481	2,02,960.00	
31-Mar-20	Cr Sale of Services <i>Invoice No.si/19-20/41 dt 31/03/20 for the Month of March'20</i>	Journal	498	2,02,960.00	
	Dr TDS (R) <i>Being amt of TDS educted for 2019-20</i>	Journal	528		1,51,655.00
	Dr Closing Balance			1,30,09,331.00	1,27,96,174.86
					2,13,156.14
				1,30,09,331.00	1,30,09,331.00

Sewage Treatment Plant
Log Book

Certified that this register contains Pages
from 01 to 139 (One to One hundred thirty
nine only).


JECW
09/01/2023


02/01/2023
A.E. (Civil)


21/1/23
C PO (ATU)

Jan. 2023

Date

Date

Date	Inlet Water Flow M ³ /hr						PH Testing						TDS Testing						Remarks	Checked by Supervisor	Approved by JE
	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M			
01/01/23	47	48	46	45	44	47	7.5	7.5	7.6	7.5	7.5	7.5	687	698	693	688	701	700		Patrol	
02/01/23	47	48	46	46	45	48	7.5	7.5	7.6	7.5	7.4	7.5	698	691	687	694	698	690		Patrol	Sunday
03/01/23	48	46	48	47	46	47	7.5	7.5	7.6	7.5	7.4	7.5	692	700	701	687	698	701		Patrol	
04/01/23	48	44	46	45	45	48	7.6	7.8	7.6	7.6	7.4	7.5	710	707	698	694	696	685		Patrol	
05/01/23	47	48	46	45	48	47	7.6	7.5	7.6	7.5	7.6	7.4	720	710	704	698	700	715		Patrol	
06/01/23	47	48	46	47	46	45	7.6	7.4	7.5	7.5	7.6	7.5	726	696	710	694	690	691		Patrol	
07/01/23	48	48	46	47	46	47	7.6	7.4	7.5	7.5	7.6	7.5	710	691	697	693	690	685		Patrol	
08/01/23	46	46	45	46	47	47	7.5	7.4	7.5	7.5	7.5	7.4	726	690	685	686	681	688		Patrol	
09/01/23	48	44	47	45	45	47	7.5	7.4	7.5	7.5	7.5	7.5	726	690	697	694	682	681		Patrol	
10/01/23	48	46	47	45	45	47	7.5	7.5	7.6	7.5	7.4	7.5	689	692	687	685	680	695		Patrol	
11/01/23	47	45	48	46	45	47	7.5	7.5	7.6	7.5	7.5	7.4	689	679	700	695	695	688		Patrol	
12/01/23	48	46	46	46	48	48	7.5	7.4	7.5	7.5	7.5	7.4	688	696	688	690	688	685		Patrol	
13/01/23	44	46	47	46	45	44	7.6	7.5	7.6	7.5	7.4	7.5	690	689	678	689	676	680		Patrol	
14/01/23	46	44	47	44	48	46	7.6	7.5	7.6	7.4	7.5	7.4	690	688	700	690	678	696		Patrol	
15/01/23	46	45	47	46	47	44	7.6	7.5	7.6	7.5	7.5	7.4	690	679	683	688	690	685		Patrol	
16/01/23	46	44	47	46	45	46	7.6	7.4	7.5	7.5	7.5	7.5	689	690	681	690	688	685		Patrol	
17/01/23	44	46	47	47	46	45	7.5	7.4	7.5	7.5	7.4	7.5	700	690	715	720	715	710		Patrol	
18/01/23	46	45	46	47	46	45	7.5	7.6	7.5	7.6	7.5	7.5	695	690	681	695	696	688		Patrol	
19/01/23	47	48	46	47	48	46	7.4	7.5	7.5	7.6	7.4	7.3	740	730	700	690	689	696		Patrol	
20/01/23	48	44	47	48	47	46	7.6	7.5	7.6	7.5	7.5	7.4	726	690	698	700	695	690		Patrol	
21/01/23	46	48	47	46	46	48	7.6	7.4	7.5	7.5	7.4	7.5	676	680	685	688	685	687		Patrol	
22/01/23	47	46	47	46	48	47	7.4	7.3	7.4	7.5	7.5	7.4	676	680	685	688	685	687		Patrol	
23/01/23	48	44	47	46	48	47	7.6	7.4	7.5	7.6	7.5	7.6	726	710	691	695	690	688		Patrol	
24/01/23	46	44	47	46	46	47	7.5	7.4	7.4	7.4	7.4	7.5	679	690	684	691	688	684		Patrol	
25/01/23	48	46	48	47	46	48	7.6	7.5	7.5	7.5	7.6	7.4	710	720	705	711	714	710		Patrol	
26/01/23	44	46	48	47	46	45	7.5	7.4	7.5	7.6	7.5	7.5	720	715	706	703	701	700		Patrol	
27/01/23	48	47	46	48	47	46	7.5	7.5	7.6	7.6	7.5	7.5	710	700	711	705	700	703		Patrol	
28/01/23	44	46	48	47	46	45	7.5	7.6	7.5	7.6	7.5	7.5	720	726	710	705	703	700		Patrol	
29/01/23	44	46	48	47	46	45	7.5	7.6	7.5	7.6	7.4	7.5	720	718	715	710	705	701		Patrol	
30/01/23	48	47	46	45	46	46	7.6	7.5	7.5	7.6	7.4	7.5	700	701	703	697	699	696		Patrol	
31/01/23	47	48	46	47	45	46	7.5	7.5	7.6	7.4	7.4	7.5	714	717	706	705	701	702		Patrol	

Date	Inlet Water Flow M ³ /Hr.						PH Testing						TDS Testing						checked by Supervisor	Approved by JE	Remarks
	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M			
	01/02/23	48	48	46	48	47	46	7.4	7.5	7.5	7.4	7.5	7.6	710	717	709	710	708			
02/02/23	48	46	45	47	48	46	7.5	7.5	7.6	7.5	7.6	7.5	710	709	711	704	701	700	Jaba	Jaba	do
03/02/23	48	46	47	45	46	48	7.6	7.5	7.6	7.5	7.4	7.6	714	709	706	703	700	703	Jaba	Jaba	do
04/02/23	48	46	47	48	46	45	7.6	7.6	7.5	7.6	7.4	7.5	714	706	705	703	700	698	Jaba	Jaba	do
05/02/23	46	47	45	48	46	47	7.5	7.5	7.6	7.6	7.5	7.5	691	711	706	703	717	713	Jaba	Jaba	Sunday
06/02/23	46	47	45	48	46	47	7.4	7.3	7.5	7.6	7.4	7.5	727	719	717	716	712	708	Jaba	Jaba	do
07/02/23	47	46	48	47	46	45	7.4	7.3	7.4	7.5	7.4	7.5	734	730	721	718	729	732	Jaba	Jaba	do
08/02/23	46	48	45	47	46	47	7.3	7.5	7.4	7.5	7.4	7.5	718	724	722	727	710	714	Jaba	Jaba	Please clean the site
09/02/23	45	48	46	47	47	46	7.4	7.5	7.6	7.5	7.5	7.5	708	711	714	721	728	731	Jaba	Jaba	do
10/02/23	48	47	46	45	46	47	7.5	7.6	7.5	7.4	7.5	7.4	728	731	724	729	730	726	Jaba	Jaba	do
11/02/23	46	47	45	46	46	47	7.4	7.5	7.5	7.5	7.4	7.5	728	731	724	729	730	726	Nitesh	Nitesh	do
12/02/23	47	46	45	46	48	47	6.7	6.8	7.1	7.1	7.5	7.4	735	726	719	721	715	710	Nitesh	Nitesh	do
13/02/23	47	46	45	46	48	47	7.0	6.9	7.0	7.5	7.5	7.4	725	732	730	726	722	715	Nitesh	Nitesh	Sunday
14/02/23	46	46	48	47	46	45	6.9	6.8	7.0	7.1	7.2	7.3	723	718	727	724	732	729	Nitesh	Nitesh	Please clean
15/02/23	46	47	45	46	48	47	6.9	6.9	7.1	7.0	7.0	7.2	732	728	723	718	721	724	Nitesh	Nitesh	do
16/02/23	46	44	45	45	46	45	7.1	7.1	7.0	7.1	7.2	7.0	731	734	729	725	722	715	Nitesh	Nitesh	Risky in the unit
17/02/23	46	45	45	48	47	45	7.2	7.1	7.1	7.2	7.0	7.1	735	731	728	726	722	719	Nitesh	Nitesh	do
18/02/23	46	44	44	45	45	44	7.2	7.1	7.1	7.0	7.2	7.0	724	727	722	719	725	731	Nitesh	Nitesh	do
19/02/23	46	44	44	45	45	44	7.1	7.2	7.0	7.2	7.0	7.1	729	734	724	732	735	729	Nitesh	Nitesh	do
20/02/23	46	46	42	44	45	45	7.1	7.0	7.2	7.2	7.1	7.1	727	724	733	741	739	737	Nitesh	Nitesh	do
21/02/23	45	46	44	44	42	45	7.1	7.0	7.2	7.2	7.1	7.1	727	724	733	741	739	737	Nitesh	Nitesh	do
22/02/23	45	46	44	44	42	45	7.3	7.5	7.6	7.4	7.3	7.6	758	753	749	745	742	755	Nitesh	Nitesh	do
23/02/23	46	48	45	47	48	46	7.3	7.5	7.6	7.4	7.3	7.6	758	753	749	745	742	755	Nitesh	Nitesh	Sunday
24/02/23	46	48	45	47	48	46	7.5	7.3	7.6	7.5	7.6	7.4	751	760	748	752	748	740	Nitesh	Nitesh	do
25/02/23	47	46	48	47	48	46	7.5	7.3	7.6	7.5	7.6	7.4	751	760	748	752	748	740	Nitesh	Nitesh	Risky Clean the clean
26/02/23	47	46	48	47	48	46	7.3	7.4	7.2	7.3	7.4	7.5	760	761	758	755	751	748	Nitesh	Nitesh	do
27/02/23	48	47	46	47	45	48	7.3	7.4	7.2	7.3	7.4	7.5	760	761	758	755	751	748	Nitesh	Nitesh	Risky by clean the site
28/02/23	48	47	46	47	45	48	7.3	7.4	7.2	7.3	7.4	7.5	760	761	758	755	751	748	Nitesh	Nitesh	do
29/02/23	47	48	46	48	46	47	7.5	7.4	7.5	7.4	7.6	7.5	758	765	754	748	750	753	Nitesh	Nitesh	do

Under maintenance

Ready

Risky Clean the clean
Risky by clean the site

Date	Inlet Water Flow M ³ /Hr.						PH Testing						TDS Testing						checked by Supervisor	Approved by JE	Remarks
	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 A.M	6:00 A.M	10:00 A.M	2:00 PM	6:00 P.M	10:00 PM	2:00 A.M	6:00 A.M	10:00 A.M	2:00 PM	6:00 P.M	10:00 PM	2:00 A.M	6:00 A.M			
01/03/23	48	47	46	45	44	48	7.5	7.4	7.4	7.3	7.4	7.5	760	748	739	737	741	738	Fabra	[Signature]	
02/03/23	46	47	45	46	46	45	7.5	7.4	7.3	7.5	7.5	7.4	729	740	738	726	731	728	Fabra	[Signature]	
03/03/23	45	44	46	47	46	45	7.3	7.6	7.5	7.4	7.4	7.4	741	744	759	763	760	739	Fabra	[Signature]	
04/03/23	45	47	46	45	44	45	7.2	7.1	7.2	7.3	7.4	7.3	728	725	730	728	726	722	Fabra	[Signature]	
05/03/23	45	46	47	48	46	45	7.2	7.3	7.4	7.2	7.1	7.2	719	716	720	721	716	719	Fabra	[Signature]	Sunday.
06/03/23	48	46	45	45	44	45	7.3	7.3	7.2	7.3	7.3	7.4	728	730	736	729	724	727	Fabra	[Signature]	
07/03/23	45	47	49	48	47	48	7.4	7.5	7.4	7.3	7.4	7.4	724	720	727	728	731	723	Fabra	[Signature]	
08/03/23	47	46	46	48	47	46	7.5	7.4	7.3	7.4	7.4	7.3	729	724	730	731	734	728	Fabra	[Signature]	-Holi-
09/03/23	47	45	46	44	45	47	7.4	7.3	7.3	7.4	7.3	7.3	726	721	724	727	722	728	Fabra	[Signature]	
10/03/23	48	46	47	46	45	45	7.4	7.3	7.3	7.2	7.2	7.2	720	719	724	726	730	734	Fabra	[Signature]	
11/03/23	48	46	47	45	45	47	7.1	7.2	7.1	7.1	7.2	7.2	740	737	734	729	732	735	Fabra	[Signature]	
12/03/23	46	46	45	47	45	45	7.3	7.3	7.2	7.2	7.2	7.1	728	726	723	721	724	727	Fabra	[Signature]	Sunday.
13/03/23	47	45	46	47	47	48	7.2	7.1	7.2	7.3	7.3	7.2	730	726	733	741	729	735	Fabra	[Signature]	
14/03/23	47	45	46	46	47	47	7.1	7.1	7.2	7.1	7.3	7.2	730	734	729	727	732	736	Fabra	[Signature]	
15/03/23	48	46	47	45	45	47	7.1	7.2	7.2	7.2	7.1	7.1	740	736	733	737	739	735	Fabra	[Signature]	
16/03/23	47	45	46	45	45	46	7.2	7.2	7.4	7.5	7.2	7.3	731	734	737	733	735	738	Fabra	[Signature]	
17/03/23	48	46	45	47	45	45	7.1	7.1	7.2	7.2	7.0	7.1	730	733	737	740	738	736	Fabra	[Signature]	
18/03/23	46	47	45	45	46	45	7.1	7.1	7.2	7.0	7.1	7.0	726	739	746	737	741	738	Fabra	[Signature]	
19/03/23	46	45	46	47	47	46	7.1	7.1	7.2	7.3	7.3	7.2	726	731	734	719	742	754	Fabra	[Signature]	Sunday.
20/03/23	48	46	44	46	47	48	7.2	7.1	7.2	7.3	7.3	7.4	731	720	726	736	740	720	Fabra	[Signature]	
21/03/23	48	46	46	45	44	46	7.3	7.2	7.1	7.2	7.1	7.2	736	730	732	729	734	728	Fabra	[Signature]	
22/03/23	45	46	48	46	47	45	7.2	7.3	7.3	7.4	7.2	7.1	731	732	740	748	742	749	Fabra	[Signature]	
23/03/23	46	45	47	48	46	46	7.2	7.1	7.2	7.3	7.3	7.2	744	746	740	750	748	752	Fabra	[Signature]	
24/03/23	47	45	48	46	44	47	7.2	7.1	7.3	7.3	7.4	7.2	747	744	748	741	720	744	Fabra	[Signature]	
25/03/23	46	45	46	46	48	46	7.2	7.1	7.1	7.0	7.0	7.0	747	742	739	743	739	744	Fabra	[Signature]	
26/03/23	48	45	44	46	46	45	7.3	7.3	7.2	7.2	7.2	7.1	748	745	742	739	741	744	Fabra	[Signature]	Sunday.
27/03/23	48	46	45	47	45	46	7.2	7.3	7.3	7.2	7.2	7.1	730	737	740	739	736	734	Fabra	[Signature]	
28/03/23	46	48	45	46	45	45	7.2	7.1	7.3	7.2	7.2	7.1	731	740	743	739	737	738	Fabra	[Signature]	
29/03/23	47	45	46	45	46	46	7.1	7.2	7.2	7.2	7.3	7.3	744	739	742	745	768	752	Fabra	[Signature]	
30/03/23	46	47	46	46	48	45	7.3	7.4	7.4	7.3	7.2	7.3	761	724	731	742	736	747	Fabra	[Signature]	
31/03/23	48	46	45	47	45	46	7.4	7.3	7.2	7.2	7.1	7.2	685	679	681	683	687	692	Fabra	[Signature]	

Date	Inlet Water Flow m ³ /Hr.						PH Testing					
	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M
01/04/23	47	46	47	46	46	45	7.3	7.2	7.3	7.3	7.3	7.2
02/04/23	47	46	48	46	46	47	7.2	7.2	7.3	7.3	7.4	7.2
03/04/23	45	47	46	48	46	44	7.2	7.2	7.3	7.3	7.4	7.3
04/04/23	48	47	46	48	47	46	7.4	7.4	7.5	7.3	7.4	7.3
05/04/23	47	46	48	47	46	46	7.1	7.1	6.9	6.9	6.7	6.7
06/04/23	45	47	46	45	46	46	6.5	6.4	6.7	6.7	6.6	6.6
07/04/23	45	46	47	45	45	46	6.9	6.5	6.6	6.7	6.7	6.8
08/04/23	47	46	48	45	46	47	6.9	6.7	6.6	6.8	6.7	6.7
09/04/23	46	46	47	46	48	46	6.7	6.8	6.6	6.8	6.9	6.9
10/04/23	48	46	47	46	45	47	6.6	6.7	6.8	6.8	8.6	6.6
11/04/23	46	45	46	47	46	45	6.7	6.8	6.7	6.6	6.8	6.8
12/04/23	47	46	46	45	46	45	6.8	6.8	6.9	6.9	7.0	7.0
13/04/23	46	47	46	45	44	45	6.9	6.7	6.7	6.7	6.9	6.8
14/04/23	46	46	45	46	44	45	6.9	7.0	7.0	7.1	7.0	7.1
15/04/23	46	45	46	46	45	45	7.0	7.0	7.0	7.0	7.0	7.1
16/04/23	45	46	46	47	45	45	7.1	7.1	7.2	7.2	7.1	7.0
17/04/23	47	46	46	45	45	47	7.0	7.1	7.1	7.2	7.0	7.1
18/04/23	46	45	47	45	45	46	7.1	7.1	7.2	7.2	7.1	7.0
19/04/23	47	46	45	45	46	47	7.0	7.1	7.1	7.2	7.2	7.2
20/04/23	46	45	46	47	46	48	7.1	7.1	7.1	7.0	7.1	7.1
21/04/23	47	46	48	47	47	46	7.0	6.8	6.9	6.9	7.1	7.1
22/04/23	46	47	46	48	47	48	7.9	7.1	7.0	7.1	7.0	7.0
23/04/23	46	47	45	46	48	47	7.1	7.2	7.1	7.1	7.1	7.0
24/04/23	48	47	46	45	45	47	7.1	7.1	6.8	6.8	6.9	6.9
25/04/23	46	46	47	46	46	48	7.0	7.0	7.1	6.9	7.0	6.9
26/04/23	47	48	47	47	45	46	6.8	6.7	6.8	6.9	6.9	7.0
27/04/23	47	45	46	46	47	48	7.0	7.0	7.1	7.0	7.1	6.9
28/04/23	46	45	47	47	46	45	6.9	7.0	6.9	7.1	7.0	7.1
29/04/23	47	46	47	48	47	46	6.8	6.9	7.1	7.0	6.9	7.0
30/04/23	48	47	45	46	46	45	7.1	6.9	6.9	6.8	7.0	7.0

TDS Testing						Checked by	Approved	Remarks
10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	Supervisor	by JE	
701	708	717	720	723	719	Jabra	201/23	lightly clean the tank
727	691	699	705	712	721	Jabra	Sunday.	
728	709	714	690	689	678	Jabra	203/23	
696	790	789	769	760	755	Jabra	204/23	clean the site and tank
680	648	646	635	652	663	Jabra		
671	669	638	642	649	654	Jabra	201/23	
670	673	648	652	658	663	Jabra	201/23	check the oil
671	668	645	652	656	653	Jabra	201/23	
655	661	649	667	684	659	Jabra	Sunday	
719	637	642	660	656	651	Jabra	201/23	clean the site
649	657	641	637	655	649	Jabra	201/23	
653	660	664	670	675	682	Jabra	201/23	
689	667	659	652	657	660	Jabra	201/23	
663	665	670	668	664	672	Jabra	201/23	
670	676	678	675	671	681	Jabra	201/23	
684	679	674	669	672	676	Jabra	Sunday.	
678	680	677	675	682	686	Jabra	201/23	
691	684	679	688	685	683	Jabra	201/23	
677	674	671	668	670	676	Jabra	201/23	
669	672	681	686	679	648	Jabra	201/23	
641	629	634	628	624	627	Jabra	201/23	
633	639	642	626	629	628	Jabra	201/23	
631	627	634	626	631	621	Jabra	Sunday.	
659	671	661	667	670	665	Jabra	201/23	
661	667	672	688	740	733	Jabra	201/23	
763	767	759	738	729	724	Jabra	201/23	
718	714	724	718	732	724	Jabra	201/23	
719	742	735	741	753	748	Jabra	201/23	
741	745	752	739	746	740	Jabra	201/23	
734	741	729	732	736	727	Jabra	Sunday.	

May, 2023

Date	Inlet water Flow M ³ /hr.						PH Testing						TDS Testing						checked by Supervisor	Approved by JE	Remarks
	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M	10:00 A.M	2:00 P.M	6:00 P.M	10:00 P.M	2:00 A.M	6:00 A.M			
01/05/23	47	46	45	46	46	47	6.9	7.0	7.0	6.9	6.9	7.0	765	773	764	760	753	751	Jabra	J 0115	
02/05/23	46	47	47	46	45	46	6.9	7.0	6.9	6.9	6.9	7.0	742	738	732	728	736	741	Jabra	J 0115	
03/05/23	45	46	46	45	45	47	7.0	6.9	7.0	7.0	7.1	7.0	744	750	754	749	743	739	Jabra	J 0115	
04/05/23	47	46	45	47	46	46	6.9	7.0	7.0	6.9	7.0	7.1	746	738	741	734	729	734	Jabra	J 0115	
05/05/23	47	46	45	46	45	47	6.9	7.0	7.0	7.1	7.0	6.9	729	726	730	735	742	739	Jabra	—	
06/05/23	46	46	47	48	46	47	7.1	7.1	7.1	7.0	7.1	6.9	744	750	747	740	739	734	Jabra	—	
07/05/23	48	47	46	48	47	47	7.0	6.9	7.1	7.0	7.1	7.0	732	735	738	740	733	741	Jabra	Sunday.	
08/05/23	46	45	46	46	47	48	6.9	6.9	7.0	7.1	7.0	7.1	743	740	732	730	735	739	Jabra	J 0115	
09/05/23	47	46	45	46	45	47	7.0	7.1	7.0	7.0	6.9	6.9	736	742	750	739	733	728	Jabra	J 0115	
10/05/23	46	48	46	45	45	47	7.1	7.1	7.0	7.0	7.1	7.1	731	726	730	722	727	720	Jabra	J 0115	
11/05/23	46	47	46	47	47	46	7.1	7.1	7.0	7.2	7.1	7.1	726	730	742	739	736	732	Jabra	J 0115	
12/05/23	47	48	47	46	46	47	7.0	6.9	7.0	7.1	7.2	7.2	729	730	726	731	727	738	Jabra	J 0115	
13/05/23	46	47	48	46	47	48	7.1	7.2	7.2	7.1	7.0	7.2	731	742	740	738	735	741	Jabra	J 1515	
14/05/23	48	46	47	48	47	48	7.2	7.1	7.2	7.3	7.1	7.0	730	729	734	741	728	729	Jabra	Sunday	
15/05/23	47	46	44	48	46	47	7.0	7.1	7.2	7.1	7.2	7.1	734	736	740	736	731	726	Jabra	J 1515	
16/05/23	47	46	48	46	48	47	7.1	7.1	7.1	7.1	7.2	7.0	739	735	730	740	738	734	Jabra	J 1615	
17/05/23	47	46	48	46	47	46	7.1	7.0	7.1	7.0	7.1	7.2	733	728	730	739	742	738	Jabra	J 1615	
18/05/23	47	46	44	46	47	46	7.1	7.0	7.1	7.0	7.1	7.2	741	737	740	736	742	738	Jabra	J 1815	
19/05/23	47	45	48	49	46	47	7.1	7.1	7.1	7.0	7.1	7.0	735	737	740	739	748	742	Jabra	J 1915	
20/05/23	48	46	44	47	49	46	7.0	7.1	7.2	7.1	7.1	7.2	746	745	739	741	742	740	Jabra	J 2015	
21/05/23	47	48	46	46	47	48	7.1	7.1	7.0	7.1	7.1	7.2	730	737	739	741	736	731	Jabra	Sunday.	
22/05/23	48	46	47	46	48	46	7.1	7.1	7.0	7.1	7.1	7.0	740	735	738	734	740	734	Jabra	J 2215	
23/05/23	46	48	48	45	46	45	7.1	7.1	7.0	7.0	7.1	7.3	735	740	744	738	741	732	Jabra	J 2315	
24/5/23	48	47	46	47	46	47	7.1	7.0	7.1	7.1	7.2	7.2	740	733	742	739	744	736	Jabra	J 2415	
25/5/23	46	47	48	47	46	47	7.1	7.0	7.2	7.1	7.2	7.1	742	736	743	738	745	737	Jabra	J 2515	
26/5/23	47	46	47	48	47	46	7.0	7.0	7.2	7.0	7.1	7.0	744	738	741	734	742	733	Jabra	J 2615	
27/5/23	47	46	48	49	47	48	7.1	7.1	7.1	7.1	7.0	7.2	746	739	740	748	741	738	Jabra	J 2715	
28/5/23	46	47	48	46	44	46	7.0	7.1	7.0	7.1	7.1	7.2	736	742	740	748	742	745	Jabra	Sunday.	
29/5/23	47	46	48	46	47	48	7.1	7.0	7.1	7.0	7.2	7.1	731	734	739	730	740	742	Jabra	J 2915	
30/5/23	47	48	46	47	49	47	7.1	7.2	7.1	7.1	7.0	7.1	730	740	735	740	735	730	Jabra	J 3015	
31/5/23	48	46	47	46	48	47	7.2	7.2	7.1	7.2	7.1	7.1	712	736	726	720	690	689	Jabra	J 3115	

TOILET

June, 2023

Date	Inlet water Flow M ³ /hr.				Outlet PH Testing						Outlet TDS Testing						Checked by Supervisor	Approved by JE	Remarks			
	10:00 A.M.	2:00 P.M.	6:00 P.M.	10:00 P.M.	6:00 A.M.	8:00 A.M.	10:00 A.M.	12:00 P.M.	2:00 P.M.	4:00 P.M.	6:00 P.M.	8:00 P.M.	10:00 P.M.	12:00 P.M.	2:00 P.M.	4:00 P.M.				6:00 P.M.		
01/06/23	48	46	47	47	48	47	46	7.0	7.1	7.2	7.1	7.1	7.0	688	685	680	697	692	678	Jaha	Jaha	
02/06/23	48	47	47	48	47	46	44	7.2	7.1	7.2	7.1	7.2	7.1	714	696	676	680	686	679	Jaha	Jaha	
03/06/23	48	46	47	48	46	44	44	7.1	7.1	7.2	7.1	7.1	7.0	670	680	678	680	671	680	Jaha	Jaha	Sunday
04/06/23	48	46	47	48	49	44	44	7.2	7.3	7.2	7.1	7.1	7.0	689	680	685	670	669	685	Jaha	Jaha	
05/06/23	48	46	47	46	48	46	46	7.2	7.1	7.2	7.1	7.2	7.1	690	685	680	685	671	669	Jaha	Jaha	
06/06/23	44	47	48	47	46	47	47	7.2	7.1	7.2	7.0	7.2	7.1	680	670	672	685	680	688	Jaha	Jaha	
07/06/23	47	46	48	47	46	47	47	7.0	7.1	7.2	7.1	7.2	7.0	676	679	690	688	681	679	Jaha	Jaha	
08/06/23	48	46	47	48	46	45	45	7.1	7.0	7.2	7.1	7.0	7.1	691	689	680	679	688	685	Jaha	Jaha	
09/06/23	48	46	48	46	47	47	47	7.2	7.1	7.2	7.1	7.2	7.0	690	689	686	681	676	671	Jaha	Jaha	
10/06/23	46	44	48	46	44	43	43	7.1	7.0	7.1	7.3	7.1	7.0	680	679	669	690	689	678	Jaha	Jaha	
11/06/23	44	48	47	48	46	45	45	7.3	7.1	7.2	7.1	7.0	7.1	679	691	690	688	677	685	Jaha	Jaha	Sunday
12/06/23	46	48	46	48	47	46	46	7.2	7.1	7.2	7.1	7.2	7.1	690	691	688	685	690	688	Jaha	Jaha	
13/06/23	48	46	48	47	46	47	47	7.2	7.1	7.0	7.2	7.1	7.0	689	694	681	691	698	688	Jaha	Jaha	
14/06/23	48	46	47	48	45	46	46	7.2	7.0	7.2	7.1	7.0	7.2	680	682	691	688	690	689	Jaha	Jaha	
15/06/23	48	44	47	48	46	45	45	7.2	7.3	7.2	7.1	7.2	7.0	691	689	691	689	690	688	Jaha	Jaha	
16/06/23	46	48	47	46	48	47	47	7.1	7.0	6.9	7.0	7.2	7.1	681	688	700	705	679	690	Jaha	Jaha	
17/06/23	48	46	47	48	46	47	47	7.1	7.0	7.1	7.2	7.1	7.0	688	691	708	688	694	693	Jaha	Jaha	
18/06/23	48	44	47	46	48	46	46	7.1	7.2	7.2	7.1	7.2	7.0	680	670	691	688	693	689	Jaha	Jaha	Sunday
19/06/23	44	48	46	48	47	46	46	7.1	7.2	7.1	7.1	7.0	7.2	695	689	687	689	690	692	Jaha	Jaha	
20/06/23	48	46	47	46	44	46	46	7.2	7.1	7.0	7.2	7.0	7.1	689	671	700	702	708	698	Jaha	Jaha	
21/06/23	48	46	47	45	48	47	47	7.2	7.1	7.1	7.2	7.2	7.1	671	676	680	688	690	689	Jaha	Jaha	
22/06/23	48	46	48	47	45	46	46	7.2	7.0	7.1	7.2	7.1	7.0	691	700	698	691	688	690	Jaha	Jaha	
23/06/23	47	46	45	47	46	47	47	7.2	7.0	7.0	7.1	7.0	7.1	676	708	687	694	691	686	Jaha	Jaha	
24/06/23	48	44	46	45	46	47	47	7.2	7.1	7.1	7.0	7.1	7.2	689	691	684	679	677	681	Jaha	Jaha	
25/06/23	47	48	46	48	47	46	47	7.2	7.2	7.3	7.2	7.0	7.1	680	676	686	691	698	693	Jaha	Jaha	
26/06/23	48	47	47	45	48	46	46	7.1	7.1	7.2	7.0	7.2	7.0	689	688	698	700	699	694	Jaha	Jaha	
27/06/23	48	44	45	46	47	48	46	7.1	7.2	7.2	7.1	7.0	7.2	684	670	677	668	658	652	Jaha	Jaha	
28/06/23	47	45	46	47	48	46	46	7.2	7.2	7.1	7.1	7.2	7.1	685	624	609	601	595	585	Jaha	Jaha	
29/06/23	46	47	45	46	48	47	47	7.1	7.1	7.0	7.1	7.2	7.0	574	591	587	589	572	568	D	D	
30/06/23	48	46	47	46	48	48	48	7.1	7.1	7.1	7.2	7.0	7.0	595	600	599	600	602	608	D	D	

WALTER
Sawyer Singh V.
Territory Manager
CPO

Itender Singh
Manager - Sales
+91 9999790004
Email: sales@ganpatifurniture.com

Ganpati Furniture Systems Pvt. Ltd.
20/61/1, Kirti Nagar Industrial Area
New Delhi - 110015. Mob. : +91 9910163239
Email: sales@waterindia.com, Web: www.waterindia.com

STAR CONS
- IN - C/P

hindwari

kd
KUMAR DESIGNS INDIA
D-51 3rd Floor Gop Metro P
Delhi - 110007
Ph: 0170-4248448 9810033
e-mail: dinesh@kumardesigns
kumar@kumardesigns@gmail.com
www.kumardesigns.com

ANIRUPES PVT. LTD.
Interior

GovtTech Services
Government e Marketplace

Md Farhan
Project Relations

July 2023

Date	Inlet water Flow m ³ /hr						outlet PH Testing						outlet TDS Testing						checked by SUPERVISOR	APPROVED by J.E.	REMARKS
	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 AM	6:00 AM	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 AM	6:00 AM	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 AM	6:00 AM			
	01/07/23	46	44	46	48	46	47	7.2	7.1	7.0	7.1	7.0	7.2	612	620	615	621	618			
02/07/23	48	46	45	47	48	47	7.1	7.2	7.0	7.1	7.1	7.2	603	601	611	617	604	600	Nitesh	[Signature]	
03/07/23	47	48	46	48	46	47	7.0	7.1	7.0	7.0	7.2	7.1	610	608	590	600	603	595	Nitesh	[Signature]	
4-07/23	48	47	46	47	48	46	7.1	7.0	7.1	7.2	7.1	7.0	625	630	626	640	633	625	Nitesh	[Signature]	
05/07/23	47	46	47	44	45	46	7.0	7.1	7.0	7.2	7.0	7.1	634	629	610	640	632	619	Nitesh	[Signature]	
6/07/23	48	47	46	45	44	46	7.2	7.2	7.1	7.2	7.1	7.0	640	630	626	629	633	621	Nitesh	[Signature]	
07/07/23	47	48	48	46	45	46	7.0	7.1	7.2	7.0	7.2	7.1	635	631	629	621	632	601	Nitesh	[Signature]	
08/07/23	47	48	48	46	44	45	7.1	7.2	7.0	7.2	7.3	7.2	630	640	638	630	626	636	Nitesh	[Signature]	
09/07/23	47	48	47	46	48	47	7.2	7.1	7.2	7.2	7.1	7.0	600	612	610	602	609	608	Nitesh	[Signature]	
10/07/23	46	48	47	46	47	45	7.1	7.2	7.1	7.0	7.1	7.2	605	610	618	611	621	626	Nitesh	[Signature]	
11/07/23	47	48	46	47	46	45	7.3	7.2	7.1	7.2	7.1	7.0	630	618	626	620	613	606	Nitesh	[Signature]	
12/07/23	46	47	46	47	48	46	7.1	7.2	7.0	7.2	7.1	7.0	616	618	622	631	621	609	Nitesh	[Signature]	
13/07/23	47	45	48	47	45	46	7.0	7.2	7.3	7.2	7.1	7.0	600	608	620	611	618	600	Nitesh	[Signature]	
14/07/23	46	48	45	44	46	47	7.3	7.2	7.3	7.0	7.2	7.1	619	591	596	590	595	600	Nitesh	[Signature]	
15/07/23	46	48	47	45	44	46	7.2	7.1	7.1	7.2	7.3	7.2	590	585	588	589	576	589	Nitesh	[Signature]	
16/07/23	47	46	44	47	48	46	7.3	7.2	7.2	7.3	7.3	7.1	567	589	590	588	579	571	Nitesh	[Signature]	
17/07/23	48	47	45	44	46	47	7.2	7.1	7.1	7.2	7.1	7.0	571	589	572	575	570	565	Nitesh	[Signature]	
18/07/23	47	45	48	46	45	46	7.3	7.0	7.2	7.1	7.2	7.1	681	665	671	661	665	609	Nitesh	[Signature]	
19/07/23	46	47	48	46	45	47	7.2	7.0	7.1	7.2	7.0	7.1	577	570	565	550	548	566	Nitesh	[Signature]	
20/07/23	45	48	47	48	46	45	7.1	7.2	7.1	7.0	7.2	7.0	588	561	556	560	559	578	Nitesh	[Signature]	
21/07/23	47	48	47	48	46	47	7.1	7.2	7.1	7.0	7.1	7.0	591	610	605	610	619	615	Nitesh	[Signature]	
22/07/23	46	48	47	44	46	45	7.2	7.1	7.2	7.1	7.2	7.0	602	600	610	619	623	614	Nitesh	[Signature]	
23/07/23	46	48	46	48	45	47	7.2	7.0	7.1	7.0	7.2	7.1	603	614	600	616	618	611	Nitesh	[Signature]	
24/07/23	45	47	48	48	47	46	7.1	7.0	7.1	7.0	7.2	7.1	621	591	600	606	609	611	Nitesh	[Signature]	
25/07/23	48	46	48	44	47	46	7.2	7.0	7.1	7.1	7.0	7.2	605	610	600	610	621	617	Nitesh	[Signature]	
26/07/23	47	48	46	47	45	47	7.1	7.0	7.1	7.0	7.1	7.2	608	613	620	626	621	618	Nitesh	[Signature]	
27/07/23	46	47	48	44	47	46	7.1	7.0	7.1	7.2	7.1	7.0	614	623	626	630	614	611	Nitesh	[Signature]	
28/07/23	48	46	48	47	46	48	7.2	7.1	7.1	7.2	7.3	7.3	619	605	610	626	620	626	Nitesh	[Signature]	
29/07/23	46	47	48	44	46	47	7.1	7.0	7.2	7.1	7.2	7.2	622	636	626	630	634	628	Nitesh	[Signature]	
30/07/23	46	45	46	48	47	48	7.1	7.0	7.1	7.2	7.2	7.1	618	610	620	626	629	633	Nitesh	[Signature]	
31/07/23	47	46	48	44	45	46	7.3	7.2	7.2	7.1	7.0	7.2	619	630	626	620	623	617	Nitesh	[Signature]	

Date

Date

Date	Inlet water Flow M ³ /HR						Outlet PH Testing						Outlet TDS Testing						Checked by Supervisor	Approved by JE	Remarks
	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 AM	6:00 AM	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 AM	6:00 AM	10:00 AM	2:00 PM	6:00 PM	10:00 PM	2:00 AM	6:00 AM			
	01-08-23	47	45	46	48	47	46	7.2	7.1	7.2	7.1	7.0	7.1	622	611	616	623	610			
02-08-23	45	47	46	47	45	46	7.0	7.2	7.1	7.2	7.2	7.0	628	610	618	619	614	621	Nitesh	02/08/23	
03-08-23	48	46	47	46	45	47	7.1	7.2	7.2	7.1	7.2	7.0	608	618	621	612	611	602	Nitesh	03/08/23	
04-08-23	48	46	47	46	48	45	7.1	7.2	7.1	7.2	7.0	7.1	595	598	600	609	613	616	Nitesh	04/08/23	
05-08-23	47	48	46	45	47	48	7.0	7.1	7.2	7.2	7.1	7.0	602	611	613	616	602	618	Nitesh		
06-08-23	46	48	47	46	47	48	7.2	7.0	7.1	7.1	7.2	7.1	621	614	619	609	611	628	Nitesh		
07-08-23	46	48	46	47	45	46	7.2	7.2	7.1	7.0	7.2	7.1	618	622	617	613	600	608	Nitesh		
08-08-23	47	46	48	47	48	45	7.2	7.0	7.0	7.2	7.1	7.0	616	602	612	610	619	608	Nitesh		
09-08-23	46	48	47	45	46	48	7.1	7.0	7.2	7.1	7.2	7.1	602	614	610	600	618	621	Nitesh		
10-08-23	46	48	47	46	47	48	7.0	7.2	7.2	7.1	7.2	7.2	600	619	628	622	619	613	Nitesh	10/08/23	
11-08-23	48	46	46	47	45	44	7.1	7.2	7.1	7.2	7.0	7.1	615	617	621	627	630	628	Nitesh	11/08/23	
12-08-23	46	48	47	48	46	47	7.0	7.1	7.2	7.1	7.2	7.1	626	631	629	632	631	624	Nitesh	12/08/23	
13-08-23	47	48	47	46	45	46	7.1	7.2	7.1	7.2	7.1	7.0	619	641	638	635	640	632	Nitesh		
14-08-23	47	48	46	47	46	45	7.2	7.1	7.2	7.1	7.0	7.1	624	620	628	633	636	634	Nitesh	14/08/23	
15-08-23	46	47	48	46	47	46	7.1	7.2	7.1	7.2	7.1	7.0	628	627	624	626	634	630	Nitesh	15/08/23	
16-08-23	47	48	46	45	47	48	7.2	7.1	7.0	7.1	7.2	7.2	637	641	638	630	625	618	Nitesh	16/08/23	
17-08-23	48	46	47	46	46	46	7.3	7.2	7.1	7.2	7.1	7.0	630	640	635	638	641	632	Nitesh	17/08/23	
18-08-23	46	47	45	48	48	47	7.2	7.1	7.0	7.1	7.2	7.1	620	623	628	630	624	621	Nitesh	18/08/23	
19-08-23	47	48	46	46	47	46	7.3	7.2	7.1	7.2	7.1	7.0	644	639	637	631	625	630	Nitesh	19/08/23	
20-08-23	48	47	46	45	46	48	7.1	7.0	7.1	7.1	7.2	7.1	636	630	625	620	640	631	Nitesh	20/08/23	
21-08-23	46	45	47	46	47	46	7.2	7.1	7.2	7.1	7.1	7.0	600	621	609	602	618	621	Nitesh	21/08/23	
22-08-23	47	46	48	47	46	45	7.3	7.2	7.1	7.2	7.2	7.1	632	640	637	630	600	609	Nitesh	22/08/23	
23-08-23	48	47	46	48	48	48	7.2	7.1	7.0	7.1	7.0	7.1	617	674	668	671	659	661	Nitesh	23/08/23	
24-08-23	47	48	46	47	45	46	7.2	7.3	7.1	7.0	7.2	7.0	672	663	670	657	660	655	Nitesh	24/08/23	
25-08-23	45	47	48	47	48	45	7.2	7.1	7.0	7.1	7.3	7.2	659	653	651	670	665	620	Nitesh	25/08/23	
26-08-23	47	45	48	46	47	45	7.1	7.2	7.3	7.2	7.2	7.1	681	663	649	654	650	660	Nitesh		
27-08-23	47	45	46	48	47	47	7.1	7.3	7.2	7.3	7.2	7.2	671	669	659	664	656	652	Nitesh	27/08/23	
28-08-23	45	47	45	47	46	48	7.0	7.2	7.1	7.0	7.1	7.2	638	670	648	651	660	665	Nitesh	28/08/23	
29-08-23	47	48	46	45	47	46	7.2	7.1	7.0	7.1	7.2	7.1	659	641	654	644	638	632	Nitesh	29/08/23	
30-08-23	48	47	45	48	46	47	7.1	7.0	7.2	7.0	7.1	7.2	635	629	632	627	639	635	Nitesh	30/08/23	
31-08-23	47	46	48	47	45	46	7.2	7.1	7.1	7.2	7.0	7.1	644	649	655	660	665	657	Nitesh	31/08/23	

September 2023

Date

Date

Date	Inlet Water Flow M ³ /hr						Outlet PA Testing						Outlet TDS Testing						Checked by	Approved/Remarks
	10:00Am	2:00Pm	6:00Pm	10:00Pm	2:00Am	6:00Am	10:00Am	2:00Pm	6:00Pm	10:00Pm	2:00Am	6:00Am	10:00Am	2:00Pm	6:00Pm	10:00Pm	2:00Am	6:00Am		
11-09-2023	46	45	46	47	45	46	7.1	7.0	7.1	7.2	7.1	7.0	671	663	659	652	617	614	M/tegh	by JE
12-09-2023	47	46	45	47	44	45	7.0	7.1	7.2	7.3	7.2	7.2	674	660	652	640	637	641	M/tegh	by JE
13-09-2023	48	46	45	46	48	47	7.2	7.0	7.1	7.2	7.1	7.2	678	681	677	669	659	663	M/tegh	by JE
14-09-2023	46	45	46	47	45	46	7.1	7.2	7.1	7.1	7.0	7.0	659	653	642	638	651	657	M/tegh	Sunday
15-09-2023	45	46	47	46	45	46	7.2	7.1	7.2	7.2	7.2	7.2	657	649	638	613	651	656	M/tegh	by JE
16-09-2023	46	45	47	45	46	47	7.1	7.2	7.1	7.0	7.1	7.2	659	649	638	643	650	652	M/tegh	by JE
17-09-2023	48	46	45	46	48	46	7.2	7.1	7.0	7.1	7.0	7.1	685	642	636	629	648	655	M/tegh	by JE
18-09-2023	45	47	46	45	46	47	7.0	7.1	7.0	7.1	7.0	7.1	683	674	685	677	661	670	M/tegh	by JE
19-09-2023	47	48	45	46	45	47	7.2	7.0	7.1	7.1	7.0	7.1	676	678	668	658	654	661	M/tegh	by JE
20-09-2023	47	48	45	46	47	48	7.1	7.2	7.1	7.2	7.2	7.1	645	655	651	660	663	665	M/tegh	by JE
21-09-2023	45	46	47	48	44	46	7.0	7.1	7.0	7.2	7.0	7.2	690	685	692	698	670	660	M/tegh	by JE
22-09-2023	47	45	46	48	47	48	7.1	7.2	7.0	7.2	7.0	7.1	671	659	663	648	651	654	M/tegh	by JE
23-09-2023	45	46	47	45	44	46	7.0	7.1	7.0	7.1	7.0	7.1	660	679	683	668	641	648	M/tegh	by JE
24-09-2023	46	45	47	46	47	48	7.2	7.1	7.1	7.2	7.2	7.1	691	683	674	682	661	633	M/tegh	by JE
25-09-2023	49	47	46	45	47	48	7.0	7.1	7.1	7.1	7.1	7.2	652	661	668	671	675	655	M/tegh	by JE
26-09-2023	46	47	48	47	46	47	7.1	7.0	7.0	7.1	7.0	7.1	651	662	668	671	675	655	M/tegh	by JE
27-09-2023	48	46	47	48	47	48	7.2	7.1	7.0	7.2	7.0	7.1	651	658	662	667	681	650	M/tegh	by JE
28-09-2023	47	45	46	47	48	46	7.1	7.2	7.1	7.0	7.0	7.1	609	618	640	649	660	670	M/tegh	by JE
29-09-2023	48	46	47	45	46	47	7.0	7.1	7.0	7.1	7.0	7.1	671	680	675	670	660	655	M/tegh	by JE
30-09-2023	47	45	47	48	46	45	7.2	7.0	7.2	7.1	7.0	7.1	660	691	681	675	681	671	M/tegh	by JE
01-10-2023	45	48	46	47	48	46	7.0	7.1	7.1	7.0	7.1	7.0	691	695	682	671	660	665	M/tegh	by JE
02-10-2023	46	47	48	46	47	45	7.1	7.0	7.1	7.1	7.0	7.1	677	681	656	649	655	661	M/tegh	by JE
03-10-2023	47	48	46	47	46	47	7.1	7.0	7.2	7.1	7.1	7.0	671	681	663	658	654	650	M/tegh	by JE
04-10-2023	47	45	46	47	46	47	7.2	7.1	7.0	7.2	7.1	7.0	629	649	654	661	655	671	M/tegh	by JE
05-10-2023	49	48	46	47	48	45	7.0	7.1	7.1	7.0	7.1	7.0	661	652	660	663	651	663	M/tegh	by JE

Date

OCTOBER 2023

Date

Date	Inlet water Flow m ³ /hr	Outlet PH Testing	Outlet TDS Testing								Checked by	APP Rtd by T.F.	Remarks		
			10:00 AM	2:00 PM	6:00 PM	10:00 AM	2:00 PM	6:00 PM	10:00 AM	2:00 PM				6:00 PM	
1-10-2023	48	7.1	638	644	653	658	641	690	657	660	671	652	Micha		
1-2-10-2023	46	7.1	668	654	653	667	662	690	662	670	670	670	Micha		
1-3-10-2023	49	7.0	659	672	661	679	689	669	669	669	669	669	Micha		
1-4-10-2023	46	7.2	650	661	631	644	630	660	660	660	660	660	Micha		
1-5-10-2023	49	7.2	671	653	642	630	651	657	657	657	657	657	Micha		
1-6-10-2023	46	7.1	661	651	671	688	633	645	645	645	645	645	Micha		
1-7-10-2023	45	7.0	691	649	662	674	655	671	671	671	671	671	Micha		
1-8-10-2023	45	7.2	691	649	654	651	677	695	695	695	695	695	Micha		
1-9-10-2023	46	7.0	661	640	637	632	671	657	657	657	657	657	Micha		
1-10-10-2023	48	7.1	661	642	631	641	691	661	661	661	661	661	Micha		
1-11-10-2023	46	7.2	651	642	631	645	691	661	661	661	661	661	Micha		
1-12-10-2023	46	7.0	734	718	708	714	731	729	729	729	729	729	Micha		
1-13-10-2023	47	7.1	725	731	716	721	738	722	722	722	722	722	Micha		
1-14-10-2023	48	7.2	700	706	706	730	721	718	718	718	718	718	Micha		
1-15-10-2023	46	7.0	705	698	695	690	693	691	691	691	691	691	Micha		
1-16-10-2023	45	7.1	670	665	667	659	670	668	668	668	668	668	Micha		
1-17-10-2023	47	7.2	671	649	648	641	638	631	631	631	631	631	Micha		
1-18-10-2023	46	7.1	659	671	660	689	667	660	660	660	660	660	Micha		
1-19-10-2023	48	7.0	671	653	642	635	655	647	647	647	647	647	Micha		
1-20-10-2023	49	7.2	661	649	651	658	665	667	667	667	667	667	Micha		
1-21-10-2023	47	7.2	650	662	657	651	649	650	650	650	650	650	Micha		
1-22-10-2023	46	7.1	638	641	651	657	660	671	671	671	671	671	Micha		
1-23-10-2023	47	7.3	691	680	675	660	651	652	652	652	652	652	Micha		
1-24-10-2023	47	7.1	668	651	657	661	665	670	670	670	670	670	Micha		
1-25-10-2023	48	7.0	663	660	655	650	659	671	671	671	671	671	Micha		
1-26-10-2023	46	7.2	644	649	644	661	670	653	653	653	653	653	Micha		
1-27-10-2023	47	7.3	651	659	641	653	671	651	651	651	651	651	Micha		
1-28-10-2023	47	7.0	653	671	660	644	638	640	640	640	640	640	Micha		
1-29-10-2023	45	7.2	645	659	655	651	657	661	661	661	661	661	Micha		
1-30-10-2023	47	7.3	643	651	634	641	647	655	655	655	655	655	Micha		
1-31-10-2023	46	7.1	670	675	661	653	658	650	650	650	650	650	Micha		

Date	Inlet water Flow M ³ /HR						Outlet PH Testing				
	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Am	6:00 Am	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Am
1-11-2023	48	47	49	46	48	46	7.3	7.2	7.3	7.2	7.1
2-11-2023	47	46	48	47	46	47	7.2	7.0	7.1	7.3	7.0
3-11-2023	46	47	46	48	47	48	7.4	7.2	7.2	7.1	7.3
4-11-2023	44	46	47	45	46	47	7.3	7.1	7.2	7.0	7.4
5-11-2023	46	45	46	47	46	47	7.4	7.1	7.3	7.4	7.0
6-11-2023	48	47	48	46	45	46	7.2	7.0	7.1	7.5	7.1
7-11-2023	49	48	47	46	47	48	7.4	7.3	7.2	7.4	7.1
8-11-2023	48	49	48	47	46	47	7.2	7.1	7.3	7.1	7.2
9-11-2023	47	48	46	47	47	46	7.3	7.2	7.1	7.2	7.3
10-11-2023	48	46	47	46	47	48	7.2	7.3	7.2	7.3	7.0
11-11-2023	47	45	46	48	47	46	7.5	7.4	7.1	7.1	7.1
12-11-2023	48	48	47	48	47	46	7.4	7.3	7.2	7.0	7.4
13-11-2023	46	47	48	47	48	49	7.2	7.0	7.3	7.0	7.5
14-11-2023	48	47	48	46	47	48	7.3	7.1	7.2	7.2	7.4
15-11-2023	47	48	47	45	46	47	7.4	7.1	7.0	7.2	7.2
16-11-2023	46	48	47	46	47	44	7.2	7.2	7.4	7.3	7.1
17-11-2023	45	46	48	47	48	46	7.4	7.3	7.0	7.1	7.2
18-11-2023	47	47	46	47	46	45	7.5	7.1	7.2	7.3	7.1
19-11-2023	46	48	47	48	46	47	7.3	7.4	7.1	7.3	7.0
20-11-2023	48	47	48	46	47	47	7.1	7.3	7.3	7.0	7.1
21-11-2023	47	46	49	48	48	46	7.2	7.5	7.2	7.4	7.1
22-11-2023	46	47	48	46	47	47	7.1	7.1	7.3	7.3	7.0
23-11-2023	47	45	47	46	46	48	7.2	7.4	7.1	7.1	7.2
24-11-2023	48	47	46	45	46	48	7.0	7.2	7.0	7.2	7.3
25-11-2023	48	47	45	44	45	47	7.3	7.4	7.2	7.0	7.2
26-11-2023	47	47	46	45	48	46	7.1	7.2	7.1	7.1	7.0
27-11-2023	47	48	47	46	48	47	7.2	7.3	7.2	7.3	7.4
28-11-2023	46	48	46	47	47	46	7.4	7.4	7.3	7.4	7.2
29-11-2023	46	47	47	48	46	46	7.3	7.4	7.2	7.3	7.1
30-11-2023	47	48	46	47	45	48	7.2	7.1	7.1	7.5	7.0

Date	Outlet TDS Testing						Checked By	Approved	Remarks
	6:00 Am	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Am			
1-11-2023	7.4	682	675	671	665	660	655	Nitesh	By JE
2-11-2023	7.2	690	682	675	671	667	661	Nitesh	
3-11-2023	7.1	678	670	660	655	645	640	Nitesh	
4-11-2023	7.2	665	660	656	651	648	641	Nitesh	
5-11-2023	7.3	671	660	655	651	644	640	Nitesh	Sunday
6-11-2023	7.5	661	655	651	645	641	638	Nitesh	
7-11-2023	7.1	678	661	650	644	638	639	Nitesh	
8-11-2023	7.3	691	683	675	670	660	655	Nitesh	
9-11-2023	7.2	682	670	661	657	651	645	Nitesh	
10-11-2023	7.1	659	651	657	650	644	640	Nitesh	
11-11-2023	7.2	688	680	670	665	661	657	Nitesh	
12-11-2023	7.3	691	683	688	678	671	667	Nitesh	Sunday
13-11-2023	7.2	714	719	725	731	738	744	Nitesh	
14-11-2023	7.1	719	702	708	713	720	727	Nitesh	
15-11-2023	7.4	690	680	674	671	666	660	Nitesh	
16-11-2023	7.2	699	693	687	675	670	661	Nitesh	
17-11-2023	7.2	695	691	685	681	680	670	Nitesh	
18-11-2023	7.5	705	713	720	728	735	739	Nitesh	
19-11-2023	7.5	689	694	699	704	711	716	Nitesh	Sunday
20-11-2023	7.2	707	715	719	724	740	738	Nitesh	
21-11-2023	7.1	718	713	706	711	719	723	Nitesh	
22-11-2023	7.3	681	670	662	669	680	688	Nitesh	
23-11-2023	7.3	667	661	657	651	644	660	Nitesh	
24-11-2023	7.0	699	690	681	675	671	660	Nitesh	
25-11-2023	7.2	690	681	674	670	666	660	Nitesh	
26-11-2023	7.1	695	690	688	680	675	678	Nitesh	Sunday
27-11-2023	7.3	710	713	702	706	715	718	Nitesh	HED
28-11-2023	7.0	705	700	695	690	703	710	Nitesh	
29-11-2023	7.2	690	694	699	701	709	700	Nitesh	
30-11-2023	7.1	696	690	695	688	684	680	Nitesh	

Date

Date

Date	inlet water Flow m ³ /hr						Outlet PH Testing					Outlet TDS Testing						Checked By Subenish	Approved BY JE	Remarks		
	10:00 Am	12:00 Pm	16:00 Pm	10:00 Pm	2:00 Am	6:00 Am	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Pm	6:00 Am	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Pm				6:00 Am	
1-12-23	46	48	47	49	46	47	7.1	7.2	7.0	7.1	7.3	7.2	7.10	7.02	7.11	7.20	9.28	7.33	Nitesh			
2-12-23	48	46	48	47	46	46	7.2	7.1	7.2	7.0	7.2	7.1	7.18	7.06	7.16	7.23	7.19	7.23	Nitesh			
3-12-23	47	45	46	45	47	45	7.3	7.2	7.3	7.1	7.0	7.3	6.90	6.99	7.05	7.15	7.03	7.08	Nitesh		Sunday	
4-12-23	45	47	47	46	46	47	7.1	7.3	7.1	7.2	7.1	7.0	6.99	7.11	7.00	6.90	6.83	6.78	Nitesh			
5-12-23	49	46	48	47	47	46	7.2	7.1	7.2	7.1	7.2	7.1	6.67	6.80	6.72	6.78	6.83	6.89	Nitesh			
6-12-23	48	46	47	48	46	47	7.0	7.2	7.0	7.2	7.1	7.1	6.57	6.60	6.57	6.51	6.45	6.41	Nitesh			
7-12-23	46	48	45	46	45	46	7.1	7.0	7.1	7.0	7.3	7.1	6.80	6.71	6.66	6.59	6.51	6.44	Nitesh			
8-12-23	45	47	46	47	46	47	7.3	7.1	7.2	7.1	7.2	7.3	6.95	6.88	6.80	6.77	6.71	6.67	Nitesh			
9-12-23	47	46	47	48	45	48	7.2	7.3	7.1	7.0	7.4	7.2	6.71	6.77	6.70	6.65	6.60	6.53	Nitesh			
10-12-23	46	48	48	49	47	46	7.3	7.1	7.3	7.2	7.3	7.1	6.60	6.66	6.60	6.61	6.52	6.48	Nitesh		Sunday	
11-12-23	46	45	46	47	46	47	7.2	7.0	7.1	7.0	7.1	7.0	6.55	6.65	6.59	6.51	6.44	6.41	Nitesh			
12-12-23	47	47	49	47	48	46	7.1	7.1	7.0	7.1	7.0	7.3	6.70	6.77	6.70	6.63	6.55	6.49	Nitesh			
13-12-23	48	48	46	48	49	48	7.0	7.2	7.2	7.3	7.2	7.1	6.78	6.81	6.72	6.79	6.81	6.87	Nitesh			
14-12-23	49	44	47	46	48	47	7.4	7.3	7.1	7.4	7.1	7.2	6.60	6.68	6.61	6.52	6.47	6.40	Nitesh			
15-12-23	45	47	48	46	47	46	7.3	7.2	7.0	7.2	7.0	7.3	6.98	6.91	6.83	6.77	6.70	6.66	Nitesh			
16-12-23	46	47	49	45	46	47	7.2	7.1	7.2	7.3	7.1	7.1	6.85	6.80	6.88	6.93	6.96	7.01	Nitesh			
17-12-23	47	46	46	47	46	45	7.1	7.2	7.3	7.4	7.2	7.3	6.70	6.70	6.77	6.71	6.63	6.58	Nitesh		Sunday	
18-12-23	48	46	45	48	45	46	7.2	7.0	7.2	7.1	7.3	7.1	6.59	6.63	6.55	6.49	6.41	6.35	Nitesh			
19-12-23	49	47	46	48	45	47	7.3	7.4	7.1	7.2	7.1	7.0	6.81	6.88	6.93	7.00	7.11	7.16	Nitesh			
20-12-23	47	45	47	48	49	46	7.2	7.3	7.1	7.0	7.2	7.1	6.94	6.91	6.81	6.74	6.62	6.54	Nitesh			
21-12-23	45	46	48	46	47	48	7.4	7.2	7.0	7.1	7.1	7.2	6.78	6.71	6.64	6.58	6.48	6.40	Nitesh			
22-12-23	47	47	48	46	47	46	7.1	7.1	7.3	7.2	7.3	7.3	6.70	6.80	6.71	6.62	6.55	6.50	Nitesh			
23-12-23	44	45	46	47	48	47	7.2	7.2	7.1	7.0	7.2	7.2	6.61	6.71	6.80	6.88	6.89	7.00	Nitesh			
24-12-23	47	46	45	47	46	45	7.4	7.4	7.0	7.1	7.4	7.0	6.53	6.58	6.51	6.44	6.39	6.35	Nitesh		Sunday	
25-12-23	46	47	46	49	48	46	7.3	7.0	7.1	7.2	7.3	7.1	6.58	6.51	6.58	6.64	6.71	6.80	Nitesh		H-D	
26-12-23	48	48	47	48	47	48	7.0	7.2	7.2	7.1	7.2	7.3	6.74	6.79	6.90	6.99	7.10	7.18	Nitesh			
27-12-23	49	48	46	47	46	47	7.1	7.1	7.4	7.0	7.1	7.2	6.83	6.89	7.00	7.13	7.20	7.29	Nitesh			
28-12-23	47	46	48	46	47	46	7.2	7.0	7.3	7.2	7.0	7.0	6.90	6.96	7.05	7.14	7.26	7.33	Nitesh			
29-12-23	47	45	46	45	46	47	7.1	7.2	7.1	7.1	7.2	7.1	7.00	7.11	7.19	7.25	7.21	7.30	Nitesh			
30-12-23	48	46	47	46	48	45	7.0	7.1	7.2	7.0	7.1	7.1	7.3	7.15	7.19	7.26	7.31	7.38	7.42	Nitesh		
31-12-23	46	47	45	48	47	46	7.0	7.0	7.1	7.2	7.3	7.1	7.10	7.00	7.16	7.11	7.19	7.24	Nitesh		Sunday	

Date

January 2024

Date

Date	Inlet water Flow M ³ /HY						Outlet PH Testing						Checked & Supervisor	Approved By JE	Remarks						
	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Am	6:00 Am	10:00 Am	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Am	6:00 Am									
							Outlet TDS Testing														
1-1-2024	48	47	48	46	47	46	7.3	7.2	7.1	7.2	7.3	7.0	661	667	671	673	680	685	Nitesh		
2-1-2024	47	46	47	48	46	47	7.2	7.3	7.0	7.1	7.1	7.2	667	669	684	673	671	662	Nitesh		
3-1-2024	47	45	46	47	47	46	7.0	7.1	7.2	7.2	7.0	7.1	695	681	680	668	690	688	Nitesh		
4-1-2024	46	47	45	46	48	47	7.2	7.1	7.1	7.3	7.2	7.3	672	677	682	685	693	679	Nitesh		
5-1-2024	45	48	47	45	46	48	7.1	7.0	7.3	7.4	7.1	7.1	684	680	677	670	666	660	Nitesh		
6-1-2024	47	47	48	49	48	46	7.3	7.2	7.1	7.3	7.1	7.2	669	661	657	651	647	640	Nitesh		
7-1-2024	46	48	46	47	46	47	7.2	7.0	7.4	7.4	7.2	7.1	682	677	670	662	655	650	Nitesh	Sunday	
8-1-2024	48	47	45	46	47	48	7.1	7.3	7.2	7.1	7.1	7.0	664	660	653	659	667	671	Nitesh		
9-1-2024	49	46	47	48	48	46	7.2	7.4	7.9	7.2	7.2	7.2	659	651	646	661	671	675	Nitesh		
10-1-2024	46	45	46	47	45	47	7.1	7.4	7.1	7.3	7.3	7.1	669	677	681	688	690	696	Nitesh		
11-1-2024	45	46	47	46	47	46	7.0	7.3	7.0	7.0	7.1	7.0	681	687	690	695	699	701	Nitesh		
12-1-2024	46	47	46	47	48	45	7.3	7.2	7.1	7.1	7.2	7.2	664	658	661	665	671	678	Nitesh		
13-1-2024	47	45	47	46	46	47	7.2	7.1	7.4	7.1	7.1	7.3	684	678	682	687	691	698	Nitesh	Sunday	
14-1-2024	48	44	46	48	47	48	7.3	7.0	7.4	7.2	7.2	7.0	690	688	692	696	700	705	Nitesh	Sunday	
15-1-2024	46	45	47	46	48	46	7.0	7.0	7.3	7.2	7.3	7.1	718	705	711	703	709	714	Nitesh		
16-1-2024	48	46	48	47	46	47	7.1	7.1	7.2	7.3	7.1	7.2	699	696	703	709	713	718	Nitesh		
17-1-2024	47	48	49	47	45	48	7.2	7.2	7.1	7.4	7.2	7.0	731	721	715	721	727	733	Nitesh		
18-1-2024	46	47	49	48	47	46	7.3	7.3	7.2	7.4	7.3	7.3	700	710	715	726	731	736	Nitesh		
19-1-2024	45	46	47	46	45	48	7.1	7.1	7.3	7.3	7.1	7.1	690	700	706	712	719	725	Nitesh		
20-1-2024	48	49	48	47	46	47	7.0	7.4	7.1	7.2	7.0	7.2	677	685	691	700	708	716	Nitesh	Sunday	
21-1-2024	47	48	46	44	47	45	7.0	7.3	7.2	7.1	7.1	7.3	651	680	682	690	701	707	Nitesh	Sunday	
22-1-2024	46	47	46	45	47	48	7.2	7.1	7.1	7.1	7.2	7.1	658	665	672	680	689	696	Nitesh		
23-1-2024	46	45	47	46	48	46	7.3	7.0	7.2	7.2	7.2	7.0	650	657	661	670	678	684	Nitesh		
24-1-2024	48	47	46	46	48	45	7.3	7.0	7.4	7.3	7.3	7.2	665	671	678	685	689	693	Nitesh		
25-1-2024	45	46	45	47	46	45	7.1	7.1	7.2	7.1	7.0	7.1	670	677	683	689	695	702	Nitesh		
26-1-2024	49	45	46	46	47	48	7.1	7.2	7.3	7.2	7.0	7.0	682	687	693	700	709	717	Nitesh		
27-1-2024	48	47	45	46	48	47	7.4	7.3	7.1	7.4	7.1	7.3	695	690	698	710	719	729	Nitesh	Sunday	
28-1-2024	47	48	47	48	47	46	7.3	7.1	7.2	7.3	7.2	7.4	700	710	716	722	730	738	Nitesh	Sunday	
29-1-2024	46	47	48	49	46	48	7.2	7.0	7.1	7.2	7.1	7.1	715	721	718	725	731	739	Nitesh		
30-1-2024	48	48	46	47	49	46	7.1	7.3	7.2	7.2	7.4	7.2	711	716	719	729	738	740	Nitesh		
31-1-2024	45	47	45	47	45	48	7.0	7.2	7.1	7.1	7.2	7.0	700	705	709	718	711	719	Nitesh		

Date	Inlet Water Flow M ³ /Hr					Outlet PH Testing					Outlet TDS Testing					Checked By	Approved By J.E	Remarks				
	10:00 Pm	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Pm	6:00 Pm	10:00 Pm	2:00 Pm	6:00 Pm							
1-2-2024	47	46	47	46	45	46	7.2	7.3	7.1	7.3	7.2	7.1	691	685	696	670	689	677	Mitesh	Pran		
2-2-2024	47	46	47	48	47	46	7.3	7.1	7.0	7.2	7.1	7.0	679	681	680	688	679	690	Mitesh	Pran		
3-2-2024	48	49	48	47	45	47	7.4	7.3	7.2	7.1	7.2	7.3	689	678	690	687	670	678	Mitesh	Pran		
4-2-2024	46	48	46	48	46	47	6.9	7.0	7.1	7.2	7.2	7.1	691	699	705	711	716	722	Mitesh	Sundar		
5-2-2024	45	47	45	46	47	48	6.9	7.1	7.0	7.1	7.3	7.2	698	691	700	708	714	720	Mitesh	Pran		
6-2-2024	46	47	47	46	48	46	7.0	7.2	7.1	7.0	7.2	7.1	670	680	690	700	705	711	Mitesh	Pran		
7-2-2024	47	46	47	48	47	45	7.0	7.1	7.2	7.4	7.3	7.2	655	659	665	671	678	684	Mitesh	Pran		
8-2-2024	48	47	48	47	46	47	7.1	7.0	7.3	7.2	7.1	7.2	679	680	685	690	694	699	Mitesh	Pran		
9-2-2024	48	47	49	48	46	45	7.2	7.1	7.1	7.0	7.2	7.3	670	678	685	690	694	699	Mitesh	Pran		
10-2-2024	47	46	47	46	47	46	7.3	7.1	7.3	7.3	7.1	7.2	690	699	700	706	712	719	Mitesh	Pran		
11-2-2024	46	45	46	45	47	48	7.3	7.2	7.0	7.2	7.1	7.1	660	671	677	688	692	697	Mitesh	Sundar		
12-2-2024	46	46	48	45	46	47	7.4	7.2	7.0	7.1	7.0	7.2	651	657	654	651	644	640	Mitesh	Pran		
13-2-2024	47	48	47	46	48	47	7.2	7.1	7.1	7.0	7.1	7.3	680	686	692	700	704	711	Mitesh	Pran		
14-2-2024	45	46	47	48	46	48	7.1	7.2	7.2	7.3	7.2	7.1	695	699	703	709	716	723	Mitesh	Pran		
15-2-2024	46	47	48	46	47	45	7.1	7.2	7.0	7.1	7.2	7.3	690	698	693	687	680	673	Mitesh	Pran		
16-2-2024	48	47					7.2	7.3					699	701					Mitesh			
17-2-2024	47	46					7.1	7.2					680	687					Mitesh			
18-2-2024	47	48					7.1	7.0					677	670					Mitesh			
19-2-2024																			Mitesh			
20-2-2024																			Mitesh			
21-2-2024																			Mitesh			
22-2-2024																			Mitesh			
23-2-2024	49	47	48	49	46	47	7.3	7.2	7.0	7.1	7.1	7.2	688	693	701	710	718	726	Mitesh	Pran		
24-2-2024	48	46	47	46	47	46	7.2	7.0	7.1	7.3	7.2	7.0	670	675	681	688	693	700	Mitesh	Pran		
25-2-2024	48	47	48	48	46	47	7.1	7.2	7.2	7.0	7.1	7.1	660	667	672	679	684	690	Mitesh	Sundar		
26-2-2024	47	48	46	47	45	46	7.0	7.2	7.1	7.2	7.3	7.2	651	656	659	665	671	679	Mitesh	Pran		
27-2-2024	46	48	47	46	46	47	7.4	7.3	7.0	7.1	7.2	7.3	644	641	638	634	630	626	Mitesh	Pran		
28-2-2024	47	46	47	48	45	48	7.1	7.0	7.2	7.2	7.1	7.2	640	636	631	641	647	651	Mitesh	Pran		
29-2-2024	48	47	45	46	47	46	7.0	7.1	7.3	7.1	7.0	7.1	633	637	642	648	653	659	Mitesh	Pran		
30-2-2024																						
31-2-2024																						

WATER MANGROVE

J.M.

Date	Inlet water Flow M ³ /hr						Outlet PH Testing						Outlet TDS Testing						Checked By	Approved	Remarks		
	10:00 Am	2:00 Pm	6:00 Pm	10:00 Am	2:00 Pm	6:00 Pm	10:00 Am	2:00 Pm	6:00 Pm	10:00 Am	2:00 Pm	6:00 Pm	10:00 Am	2:00 Pm	6:00 Pm	10:00 Am	2:00 Pm	6:00 Pm					
1-3-2024	48	47	46	47	48	46	7.2	7.1	7.3	7.1	7.0	7.2	7.0	7.1	688	696	671	674	686	691	Water	By J.E	
2-3-2024	47	48	47	46	47	48	7.3	7.2	7.1	7.0	7.4	7.2	7.1	7.0	675	679	684	689	694	699	Water	By J.E	
3-3-2024	46	46	48	47	46	47	7.1	7.0	7.1	7.2	7.3	7.2	7.1	7.0	661	667	673	679	684	690	Water	Sunday	
4-3-2024	47	45	46	45	47	46	7.0	7.1	7.2	7.3	7.0	7.2	7.1	7.3	657	651	647	641	639	633	Water	HLD	
5-3-2024	48	47	46	47	46	45	7.1	7.3	7.3	7.0	7.1	7.2	7.1	7.2	641	645	649	653	658	664	Water	By J.E	
6-3-2024	46	48	47	46	45	46	7.2	7.2	7.1	7.2	7.3	7.3	7.1	7.1	651	659	671	678	681	688	Water	By J.E	
7-3-2024	47	47	46	47	46	47	7.3	7.1	7.0	7.1	7.1	7.2	7.2	7.2	671	679	686	693	699	703	Water	By J.E	
8-3-2024	47	46	45	48	45	48	7.1	7.0	7.2	7.0	7.1	7.1	7.1	7.3	663	669	674	681	689	695	Water	HLD	
9-3-2024	48	47	48	47	46	47	7.0	7.2	7.3	7.2	7.0	7.0	7.1	7.1	670	667	669	677	681	688	Water	By J.E	
10-3-2024	45	48	47	46	47	46	7.2	7.1	7.1	7.0	7.2	7.2	7.0	7.0	650	656	662	671	678	682	Water	Sunday	
11-3-2024	46	47	46	47	46	47	7.3	7.3	7.3	7.0	7.1	7.3	7.3	7.3	700	710	715	721	728	733	Water	By J.E	
12-3-2024	47	46	47	46	47	46	7.1	7.0	7.2	7.3	7.2	7.2	7.2	7.2	710	716	721	726	731	735	Water	By J.E	
13-3-2024	46	47	48	47	46	48	7.0	7.1	7.3	7.2	7.1	7.1	7.1	7.1	685	689	693	699	703	711	Water	By J.E	
14-3-2024	48	46	47	46	47	46	7.2	7.3	7.1	7.2	7.0	7.0	7.0	7.0	638	644	641	650	657	662	Water	By J.E	
15-3-2024	47	45	46	47	46	45	7.3	7.2	7.0	7.1	7.2	7.2	7.1	7.1	631	628	636	641	646	651	Water	By J.E	
16-3-2024	49	48	47	48	47	46	7.2	7.1	7.2	7.0	7.1	7.1	7.0	7.0	640	646	649	654	660	665	Water	By J.E	
17-3-2024	48	47	46	47	48	47	7.1	7.4	7.3	7.1	7.0	7.2	7.2	7.2	630	633	639	644	650	655	Water	Sunday	
18-3-2024	47	46	47	46	47	46	7.0	7.2	7.2	7.0	7.3	7.2	7.2	7.2	642	649	654	662	668	672	Water	By J.E	
19-3-2024	45	45	48	47	46	47	7.2	7.3	7.1	7.2	7.1	7.1	7.1	7.1	651	657	662	668	672	680	Water	By J.E	
20-3-2024	46	47	46	45	46	48	7.3	7.1	7.0	7.1	7.4	7.0	7.0	7.0	668	670	673	667	670	681	Water	By J.E	
21-3-2024	47	46	47	46	47	46	7.1	7.2	7.1	7.2	7.3	7.3	7.3	7.3	684	667	700	689	668	660	Water	By J.E	
22-3-2024	46	48	47	46	48	47	7.0	7.3	7.2	7.3	7.1	7.2	7.2	7.2	662	680	689	678	691	684	Water	By J.E	
23-3-2024	47	49	48	47	46	48	7.0	7.1	7.3	7.2	7.0	7.0	7.1	7.1	669	660	657	651	644	640	Water	By J.E	
24-3-2024	45	47	46	47	48	46	7.3	7.2	7.0	7.1	7.2	7.2	7.2	7.2	690	696	700	710	716	722	Water	Sunday	
25-3-2024	46	46	45	46	46	47	7.2	7.4	7.1	7.2	7.3	7.0	7.0	7.0	698	700	706	709	714	719	Water	HLD	
26-3-2024	47	48	47	46	45	46	7.1	7.0	7.2	7.3	7.2	7.2	7.1	7.1	673	660	710	700	671	678	Water	By J.E	
27-3-2024	48	45	44	47	46	48	7.2	7.3	7.4	7.1	7.2	7.3	7.3	7.3	681	671	672	678	668	660	Water	By J.E	
28-3-2024	47	46	48	45	47	46	7.0	7.1	7.2	7.3	7.1	7.1	7.0	7.0	691	694	699	703	710	715	Water	By J.E	
29-3-2024	48	47	46	44	46	45	7.1	7.2	7.1	7.0	7.2	7.1	7.1	7.1	700	710	690	683	678	670	Water	By J.E	
30-3-2024	47	45	46	43	45	44	7.2	7.1	7.0	7.2	7.1	7.2	7.1	7.2	665	661	687	691	672	659	Water	By J.E	
31-3-2024	45	46	45	47	44	45	7.0	7.1	7.1	7.0	7.2	7.1	7.1	7.1	672	654	661	670	663	669	Water	Sunday	

Waste to Energy plant

Log Book

Certified that this register contains Pages from 01 to 139 (one to One hundred thirty nine only).

[Signature]
AE(CV)
02/01/2023

[Signature]
02/01/2023
AE(Civil)

[Signature]
2/1/23
(Po(DTU))

4

Date	PH	PH 4.4	Food Received (kg)	Feed (kg)	Feed PH	Temp (°C)	Actual Feeding			Generator Running		Time (Hr)	Power Generated		Disposal (kg)	Remarks	Checked by Supervisor	Approved by JE	
							Food	Sbc	ES	Water	Initial		Final	Initial					Final
01/01/23	8.37	35.9	171	1	5.69	35.6	160	0	0	15.1	1779.8	1782.2	2.40	4137.2	4140.6	3.40			
02/01/23	8.45	36.3	174	1	6.17	35.6	160	0	0	15.1	1782.2	1784.7	2.50	4140.6	4144.1	3.50			
03/01/23	8.46	36.2	155	1	6.55	35.6	170	0	0	15.1	1787.2	1789.6	2.40	4147.6	4151.0	3.40			
04/01/23	8.39	36.0	147	1	5.81	35.6	170	0	0	20.1	1789.6	1792.0	2.40	4151.0	4154.6	3.60			
05/01/23	8.60	36.2	188	1	6.57	35.6	180	0	0	20.1	1792.0	1794.5	2.50	4154.6	4158.2	3.60			
06/01/23	8.54	36.1	192	2	6.19	35.6	180	0	0	20.1	1794.5	1797.1	2.60	4158.2	4161.9	3.70			
07/01/23	8.71	36.2	207	2	5.58	35.6	200	0	0	20.1	1797.1	1799.7	2.60	4161.9	4165.6	3.70			
08/01/23	8.75	36.2	215	2	6.60	34.2	200	0	0	15.1	1799.7	1802.3	2.60	4165.6	4169.4	3.80			
09/01/23	8.64	36.1	180	1	6.24	34.2	220	0	0	20.1	1802.3	1804.8	2.50	4169.4	4173.2	3.80			
10/01/23	8.69	36.3	254	2	6.09	34.2	220	0	0	20.1	1804.8	1807.5	2.70	4173.2	4176.9	3.70			
11/01/23	8.77	36.1	240	1	5.81	34.2	220	0	0	20.1	1807.5	1810.4	2.90	4176.9	4180.7	3.80			
12/01/23	8.72	36.2	251	4	5.69	35.6	240	0	0	30.1	1810.4	1813.3	2.90	4180.7	4184.6	3.90			
13/01/23	8.81	36.2	415	3	5.27	35.6	260	0	0	20.1	1813.3	1816.4	3.10	4184.6	4188.7	4.10			
14/01/23	8.74	36.0	280	1	6.12	34.2	280	0	0	20.1	1816.4	1819.4	3.00	4188.7	4192.7	4.00			
15/01/23	8.66	36.1	340	2	5.71	35.6	300	0	0	30.1	1819.4	1822.5	3.10	4192.7	4196.4	3.70			
16/01/23	8.87	36.2	365	3	5.34	35.6	300	0	0	30.1	1822.5	1825.7	3.20	4196.4	4200.1	3.70			
17/01/23	8.80	36.3	341	3	5.44	35.6	320	0	0	30.1	1825.7	1828.8	3.20	4200.1	4204.0	3.90			
18/01/23	8.93	36.3	377	1	6.27	34.2	320	0	0	20.1	1828.8	1832.1	3.30	4204.0	4208.1	4.10			
19/01/23	8.92	36.2	316	1	5.59	34.2	340	0	0	20.1	1832.1	1835.2	3.10	4208.1	4211.9	3.80			
20/01/23	8.88	36.1	310	1	6.10	34.2	340	0	0	30.1	1835.2	1838.1	2.90	4211.9	4215.8	3.90			
21/01/23	9.04	36.4	424	2	6.35	35.6	350	0	0	30.1	1838.1	1841.2	3.10	4215.8	4219.9	4.10			
22/01/23	8.97	36.2	320	1	5.78	34.2	350	0	0	30.1	1841.2	1844.4	3.10	4219.9	4223.9	4.00			
23/01/23	9.07	36.3	458	2	5.59	35.6	380	0	0	30.1	1844.4	1847.5	3.20	4223.9	4227.8	3.90			
24/01/23	9.14	36.3	440	2	5.81	36.6	400	0	0	30.1	1847.5	1850.7	3.20	4227.8	4231.9	4.10			
25/01/23	9.10	36.4	465	3	6.24	36.6	400	0	0	30.1	1850.7	1854.0	3.30	4231.9	4235.9	4.00			
26/01/23	8.98	36.2	420	3	5.96	36.6	400	0	0	30.1	1854.0	1857.4	3.30	4235.9	4239.8	3.90			
27/01/23	9.11	36.4	530	2	5.64	38.6	440	0	0	30.1	1857.4	1860.8	3.40	4239.8	4243.9	4.10			
28/01/23	9.07	36.5	517	2	6.37	39.6	440	0	0	30.1	1860.8	1864.1	3.40	4243.9	4247.8	3.90			
29/01/23	8.89	36.3	545	3	6.19	39.6	450	0	0	30.1	1864.1	1867.5	3.40	4247.8	4252.0	4.20			
30/01/23	9.04	36.4	560	2	5.81	39.6	450	0	0	40.1	1867.5	1870.9	3.40	4252.0	4256.3	4.30			
31/01/23	8.40	36.0	520	3	5.96	39.6	480	0	0	40.1	1870.9								

Date	PH	PH 4.4	Food Received (kg)	Food Rejected (kg)	Food PH	Temp (°C)	Actual Sbc	Feeding CS	Water	Generator Initial	Generator Final	Time (Hr)	Power Initial	Power Final	Unit (kwh)	Disposed (kg)	Checked by	Approved by	Remarks
01/02/23	8.19	36.1	520	2	5.37	39°C	450 0.30	0	40 L	1870.9	1874.4	3.50	4256.3	4260.6	4.30	500 kg	Supervisor	By JTE	
02/02/23	8.27	36.2	541	2	5.78	39°C	450 0.30	0	40 L	1874.4	1876.8	2.40	4260.6	4264.1	3.50	500 kg	Patrol	Patrol	Washroom for disposal
03/02/23	8.21	36.2	446	2	5.65	39°C	400 0.30	0	40 L	1876.8	1878.9	2.10	4264.1	4267.4	3.30	500 kg	Patrol	Patrol	
04/02/23	7.89	35.8	427	1	5.74	39°C	400 0.30	0	40 L	1878.9	1881.1	2.20	4267.4	4270.7	3.30	500 kg	Patrol	Patrol	Washroom for disposal
05/02/23	7.93	35.7	464	3	6.22	39°C	420 0.20	0	40 L	1881.1	1883.2	2.10	4270.7	4273.9	3.20	600 kg	Patrol	Patrol	
06/02/23	7.69	35.8	410	2	5.91	39°C	420 0.20	0	40 L	1883.2	1885.4	2.20	4273.9	4277.2	3.30	600 kg	Patrol	Patrol	
07/02/23	7.73	35.9	370	2	5.68	39°C	400 0	0	30 L	1885.4	1887.6	2.20	4277.2	4280.3	3.10	550 kg	Patrol	Patrol	
08/02/23	7.54	35.7	420	2	6.07	39°C	400 0	0	30 L	1887.6	1890.0	2.40	4280.3	4283.7	3.40	550 kg	Patrol	Patrol	Washroom for disposal
09/02/23	7.44	35.8	396	2	6.28	39°C	380 0	0	30 L	1890.0	1892.5	2.50	4283.7	4287.1	3.40	600 kg	Patrol	Patrol	
10/02/23	7.51	35.6	370	3	5.96	39°C	380 0	0	30 L	1892.5	1895.4	2.90	4287.1	4290.9	3.80	600 kg	Patrol	Patrol	
11/02/23	7.62	35.7	410	2	6.11	38°C	400 0	0	30 L	1895.4	1898.1	2.70	4290.9	4294.6	3.70	500 kg	Patrol	Patrol	
12/02/23	7.58	35.7	420	2	6.19	39°C	400 0	0	30 L	1898.1	1900.9	2.80	4294.6	4298.5	3.90	500 kg	Patrol	Patrol	Washroom for disposal
13/02/23	7.74	35.8	405	1	5.59	39°C	400 0	0	30 L	1900.9	1903.8	2.90	4298.5	4302.1	3.60	500 kg	Patrol	Patrol	
14/02/23	7.71	35.9	385	3	5.85	38°C	400 0	0	30 L	1903.8	1906.9	3.10	4302.1	4306.00	3.90	500 kg	Patrol	Patrol	
15/02/23	7.76	35.6	430	3	5.44	38°C	400 0	0	30 L	1906.9	1910.1	3.20	4306.00	4310.0	4.0	600 kg	Patrol	Patrol	
16/02/23	7.82	35.6	460	2	6.08	38°C	420 0	0	30 L	1910.1	1913.3	3.20	4310.0	4313.9	3.90	600 kg	Patrol	Patrol	
17/02/23	7.80	35.7	425	1	6.17	39°C	420 0	0	20 L	1913.3	1916.6	3.30	4313.9	4317.7	3.80	550 kg	Patrol	Patrol	
18/02/23	7.85	35.8	435	2	5.77	39°C	420 0	0	30 L	1916.6	1919.8	3.20	4317.7	4321.8	4.10	550 kg	Patrol	Patrol	
19/02/23	7.78	35.7	451	2	5.95	39°C	430 0	0	30 L	1919.8	1923.2	3.40	4321.8	4325.7	3.90	500 kg	Patrol	Patrol	
20/02/23	7.79	35.7	445	3	6.33	38°C	430 0	0	30 L	1923.2	1926.2	3.00	4325.7	4329.9	4.20	500 kg	Patrol	Patrol	
21/02/23	7.67	35.6	421	3	6.12	39°C	430 0	0	20 L	1926.2	1929.4	3.20	4329.9	4334.0	4.10	600 kg	Patrol	Patrol	
22/02/23	7.65	35.9	430	2	5.64	38°C	420 0	0	30 L	1929.4	1932.6	3.20	4334.0	4338.3	4.30	600 kg	Patrol	Patrol	
23/02/23	7.63	35.8	455	2	5.91	38°C	430 0	0	30 L	1932.6	1935.9	3.30	4338.3	4342.6	4.30	600 kg	Patrol	Patrol	
24/02/23	7.73	35.9	442	3	6.07	39°C	430 0	0	30 L	1935.9	1939.3	3.40	4342.6	4346.8	4.20	550 kg	Patrol	Patrol	
25/02/23	7.88	36.1	410	1	5.57	39°C	430 0	0	20 L	1939.3	1942.7	3.40	4346.8	4350.9	4.10	500 kg	Patrol	Patrol	
26/02/23	7.82	36.1	407	2	5.76	38°C	430 0	0	30 L	1942.7	1946.2	3.50	4350.9	4355.4	4.50	500 kg	Patrol	Patrol	
27/02/23	7.75	36.2	405	1	5.80	39°C	420 0	0	20 L	1946.2	1949.6	3.40	4355.4	4359.9	4.50	550 kg	Patrol	Patrol	
28/02/23	7.61	36.0	424	2	6.07	39°C	420 0.20	0	40 L	1949.6	1952.9	3.36	4359.9	4364.1	4.20	550 kg	Patrol	Patrol	

Date	PH		Food Received (kg)	Food Reject (kg)	Food PH	Temp (°C)	Actual Feeding				Generator Running		Time (Hr)	Power Generated			Disposal (kg)	Checked by Supervisor	Approved by JE	Remarks
	PH	PH 4					Food	SBE	CS	Water	Initial	Final		Initial	Final	Unit (kwh)				
01/03/23	7.19	36.1	427	2	5.33	38°C	400	0.200	0	40L	1952.9	1956.2	3.30	4364.1	4368.4	4.30	300 kg.	Jabra	P 1013	clean the
02/03/23	7.27	35.7	385	3	5.58	38°C	400	0.200	0	40L	1956.2	1959.6	3.40	4368.4	4372.6	4.20		Jabra	P 1013	-
03/03/23	7.49	35.9	391	2	5.41	39°C	380	0.200	0	40L	1959.6	1963.0	3.40	4372.6	4376.6	4.00	550 kg.	Jabra	P 1013	-
04/03/23	7.51	35.8	445	2	6.24	39°C	380	0.200	0	40L	1963.0	1966.0	3.30	4376.6	4380.5	3.90		Jabra	P 1013	clean the
05/03/23	7.46	36.2	360	3	5.95	39°C	360	0.200	0	40L	1966.0	1969.5	3.50	4380.5	4384.4	3.90	600 kg.	Jabra	Sunday	-
06/03/23	7.24	35.9	290	2	5.40	38°C	330	0.200	0	30L	1969.5	1972.9	3.40	4384.4	4388.5	4.10		Jabra	P 1013	-
07/03/23	7.14	35.8	230	1	5.19	38°C	250	0.200	0	30L	1972.9	1976.3	3.40	4388.5	4392.7	4.20	500 kg.	Jabra	P 1013	cooker may not in use
08/03/23	7.18	35.7	190	1	6.08	39°C	220	0.200	0	30L	1976.3	1979.8	3.50	4392.7	4396.7	4.00		Jabra	P 1013	-
09/03/23	7.31	35.7	180	1	5.98	38°C	200	0.200	0	20L	1979.8	1983.0	3.20	4396.7	4400.5	3.80	300 kg.	Jabra	P 1013	-
10/03/23	7.50	36.0	220	2	6.11	39°C	200	0	0	20L	1983.0	1986.4	3.40	4400.5	4404.6	4.10		Jabra	P 1013	-
11/03/23	7.44	35.8	210	1	6.24	40°C	200	0	0	20L	1986.4	1989.7	3.30	4404.6	4408.8	4.20		Jabra	P 1013	clean the site
12/03/23	7.61	35.9	230	2	5.76	40°C	220	0	0	30L	1989.7	1992.8	3.10	4408.8	4412.6	3.80	450 kg.	Jabra	Sunday	-
13/03/23	7.58	35.8	220	1	6.21	40°C	220	0.200	0	40L	1992.8	1996.2	3.40	4412.6	4416.7	4.10		Jabra	P 1013	-
14/03/23	7.81	36.0	285	2	5.78	39°C	240	0.200	0	40L	1996.2	1999.4	3.20	4416.7	4420.7	4.00		Jabra	P 1013	-
15/03/23	7.92	36.1	320	1	5.59	39°C	240	0	0	30L	1999.4	2002.9	3.50	4420.7	4425.0	4.30	500 kg.	Jabra	P 1013	-
16/03/23	7.66	35.7	338	1	5.87	38°C	260	0	0	30L	2002.9	2006.3	3.40	4425.0	4429.1	4.10		Jabra	P 1013	clean the
17/03/23	7.88	36.0	365	2	6.24	38°C	300	0	0	30L	2006.3	2009.7	3.40	4429.1	4433.3	4.20	600 kg.	Jabra	P 1013	-
18/03/23	7.79	35.8	340	2	6.39	38°C	300	0	0	30L	2009.7	2013.2	3.50	4433.3	4437.7	4.40		Jabra	P 1013	-
19/03/23	7.74	36.1	380	1	5.77	38°C	340	0	0	30L	2013.2	2016.6	3.40	4437.7	4441.9	4.20	550 kg.	Jabra	Sunday	-
20/03/23	7.86	36.2	370	1	6.11	38°C	340	0	0	30L	2016.6	2020.0	3.40	4441.9	4446.2	4.30		Jabra	P 1013	clean the site
21/03/23	7.91	36.2	360	1	6.24	39°C	340	0	0	30L	2020.0	2023.6	3.60	4446.2	4450.6	4.40		Jabra	P 1013	-
22/03/23	7.88	36.0	380	1	5.95	39°C	350	0	0	30L	2023.6	2027.1	3.50	4450.6	4455.0	4.40	600 kg.	Jabra	P 1013	-
23/03/23	7.94	36.1	360	2	5.44	39°C	350	0	0	30L	2027.1	2030.6	3.50	4455.0	4459.3	4.30		Jabra	P 1013	-
24/03/23	7.83	35.9	365	2	5.38	39°C	350	0	0	30L	2030.6	2034.2	3.60	4459.3	4463.8	4.50	550 kg.	Jabra	P 1013	-
25/03/23	7.90	36.0	371	1	5.87	39°C	350	0	0	30L	2034.2	2037.6	3.40	4463.8	4468.2	4.40		Jabra	P 1013	-
26/03/23	7.78	36.1	344	1	5.45	39°C	350	0	0	30L	2037.6	2040.4	2.80	4468.2	4471.8	3.60	700 kg.	Jabra	Sunday	-
27/03/23	7.61	36.1	310	1	5.81	39°C	320	0	0	20L								Jabra	P 2013	-
28/03/23	7.66	36.0	246	1	6.13	39°C	300	0	0	30L							400 kg	Jabra	P 2013	clean the site
29/03/23	7.72	36.2	280	0	5.49	39°C	300	0	0	20L								Jabra	P 2013	-
30/03/23	7.70	36.1	295	0	6.08	39°C	300	0	0	20L								Jabra	P 2013	-
31/03/23	7.61	35.9	265	0	5.88	38°C	280	0	0	20L							600 kg.	Jabra	P 2013	-

from site under maintenance

Date

April, 2023

Date

Date	PH		Food Received (kg)	Food Reject (kg)	Food PH	Temp (°C)	Actual Feeding				Generator Running		Time (Hr)	Power Generated			Disposal (kg)	Checked by Supervisor	Approved by JE	Remarks		
	PH	PH 4.4					Food	SBC	CS	Water	Initial	Final		Initial	Final	Unit (kwh)						
01/04/23	7.67	36.1	140	0	5.44	38°C	200	0.200	0	20 l.												
02/04/23	7.50	36.2	120	1	5.37	38°C	200	0.200	0	20 l.												
03/04/23	7.58	36.0	80	0	5.87	38°C	150	0	0	20 l.						300 kg.						
04/04/23	7.72	35.9	110	0	5.66	39°C	150	0	0	20 l.												
05/04/23	7.44	36.1	40	0	5.78	38°C	80	0	0	20 l.												
06/04/23	7.57	36.3	30	0	6.18	38°C	80	0	0	20 l.						100 kg.						
07/04/23	7.51	36.2	35	0	5.81	38°C	80	0	0	20 l.												
08/04/23	7.64	36.2	25	0	5.94	38°C	50	0	0	20 l.												
09/04/23	7.67	36.0	27	0	5.77	38°C	50	0	0	10 l.												
10/04/23	7.48	36.1	23	0	5.57	38°C	40	0	0	10 l.												
11/04/23	7.12	35.8	41	0	6.07	39°C	50	0	0	10 l.												
12/04/23	6.90	35.7	45	0	5.78	39°C	50	0	0	10 l.												
13/04/23	7.10	35.9	148	1	5.54	39°C	100	0	0	10 l.												
14/04/23	7.14	35.7	55	0	6.24	39°C	100	0	0	10 l.												
15/04/23	7.27	35.8	140	0	6.47	39°C	100	0	0	10 l.						200 kg.						
16/04/23	7.30	35.8	200	1	6.19	39°C	120	0	0	15 l.	2040.4	2041.0	0.6	4471.8	4472.8	1.0						
17/04/23	7.26	35.7	205	1	6.20	38°C	130	0	0	10 l.	2041.0	2041.6	0.6	4472.8	4473.6	0.8						
18/04/23	7.19	35.9	196	0	6.26	38°C	120	0	0	10 l.	2041.6	2042.4	0.8	4473.6	4474.7	1.1	250 kg					
19/04/23	7.10	35.7	210	1	6.49	38°C	120	0	0	15 l.	2042.4	2043.5	1.1	4474.7	4475.9	1.2						
20/04/23	7.24	35.8	220	0	5.88	39°C	150	0	0	15 l.	2043.5	2044.5	1.0	4475.9	4477.2	1.3						
21/04/23	7.31	35.9	235	1	5.74	39°C	150	0	0	15 l.	2044.5	2045.5	1.0	4477.2	4478.4	1.2						
22/04/23	7.14	36.1	227	0	6.11	38°C	200	0	0	20 l.	2045.5	2046.7	1.2	4478.4	4479.6	1.2	300 kg.					
23/04/23	7.21	36.2	214	0	5.69	39°C	200	0	0	20 l.	2046.7	2047.9	1.2	4479.6	4481.0	1.4						
24/04/23	7.34	36.2	231	0	5.57	39°C	200	0	0	20 l.	2047.9	2049.3	1.4	4481.0	4482.8	1.8						
25/04/23	7.17	36.2	222	0	5.66	39°C	220	0	0	20 l.	2049.3	2050.5	1.2	4482.8	4484.2	1.4						
26/04/23	7.29	36.1	251	1	6.04	39°C	220	0	0	20 l.	2050.5	2051.7	1.2	4484.2	4485.5	1.3						
27/04/23	7.25	36.3	210	0	5.31	40°C	220	0	0	20 l.	2051.7	2053.0	1.3	4485.5	4487.0	1.5	400 kg.					
28/04/23	7.24	35.8	230	0	5.59	40°C	220	0	0	20 l.	2053.0	2054.5	1.5	4487.0	4488.8	1.8						
29/04/23	7.33	35.9	208	1	6.23	39°C	230	0	0	20 l.	2054.5	2056.0	1.5	4488.8	4490.5	1.7						
30/04/23	7.18	35.9	224	0	5.87	39°C	230	0	0	20 l.	2056.0	2057.4	1.4	4490.5	4492.2	1.7						

Generator Running Initial Final

Time (Hr)

Power Generated Initial Final Unit (kwh)

Disposal (kg)

Checked by Supervisor

Approved by JE

Remarks

Under

Maintenance

Food

not received

Food not received

Sunday

Sunday

Sunday

Date	PH		Food Received (kg)	Food Rejected (kg)	Food PH	Temp (°C)	Actual Feeding				Generator Running		Time (Hr)	Power Generated			Disposal (kg)	Checked by Supervisor	Approved by JE	Remarks
	PH	PH 4.4					Food	SBC	CS	Water	Initial	Final		Initial	Final	Unit (Kwh)				
01/05/23	7.44	36.1	237	0	5.55	39°C	230	0	0	20L	2057.4	2059.0	1.6	4492.2	4494.0	1.8	400 kg.	Jabra	J 01/5	
02/05/23	7.39	36.3	264	1	5.61	38°C	240	0	0	20L	2059.0	2060.4	1.4	4494.0	4495.7	1.7	-	Jabra	J 02/5	
03/05/23	7.51	36.1	250	1	5.37	38°C	240	0	0	20L	2060.4	2061.8	1.4	4495.7	4497.5	1.8	250 kg.	Jabra	J 03/5	
04/05/23	7.47	36.2	258	1	6.10	38°C	240	0	0	20L	2061.8	2063.3	1.5	4497.5	4499.3	1.8	-	Jabra	J 04/5	
05/05/23	7.21	35.9	237	1	5.78	38°C	240	0	0	20L	2063.3	2064.9	1.6	4499.3	4501.4	2.1	-	Jabra	-	
06/05/23	7.33	36.0	219	1	6.08	38°C	240	0	0	20L	2064.9	2066.5	1.6	4501.4	4503.4	2.0	300 kg.	Jabra	-	
07/05/23	7.24	35.8	244	1	6.17	38°C	240	0	0	20L	2066.5	2068.2	1.7	4503.4	4505.3	1.9	-	Jabra	-	
08/05/23	7.23	36.0	231	1	5.66	39°C	240	0	0	20L	2068.2	2069.7	1.5	4505.3	4507.1	1.8	-	Jabra	J 08/5	
09/05/23	7.18	35.8	217	1	5.70	39°C	220	0	0	20L	2069.7	2071.5	1.8	4507.1	4509.3	2.2	400 kg.	Jabra	J 09/5	
10/05/23	7.09	35.7	214	1	6.19	39°C	220	0.250	0	20L	2071.5	2073.0	1.5	4509.3	4511.4	2.1	-	Jabra	J 10/5	
11/05/23	7.11	35.8	241	2	6.39	40°C	220	0.300	0	20L	2073.0	2073.8	0.8	4511.4	4512.9	1.5	-	Jabra	J 11/5	
12/05/23	6.57	36.9	267	2	5.97	40°C	220	0.300	0	20L	2073.8	2074.8	1.0	4512.9	4514.3	1.4	-	Jabra	J 12/5	
13/05/23	6.44	37.5	144	0	6.14	39°C	150	0.300	0	15L	2074.8	2075.3	0.5	4514.3	4515.2	-0.9	500 kg.	Jabra	J 13/5	
14/05/23	5.59	38.7	120	0	6.45	39°C	120	0.300	0	15L	2075.3	2075.7	0.4	4515.2	4516.0	0.8	-	Jabra	Sunday	
15/05/23	5.38	-	131	0	5.88	39°C	120	0.300	0	15L	2075.7	2076.1	0.4	4516.0	4516.6	0.6	-	Jabra	J 15/5	
16/05/23																				
17/05/23																				
18/05/23																				
19/05/23																				
20/5																				
21/5																				
22/5																				
23/5																				
24/5																				
25/5																				
26/5																				
27/5																				
28/5																				
29/5																				
30/5																				
31/5																				

Under Maintenance
 from 16/5/23 to 31/5/23

Date	PH	PH 4.4	Food Received (kg)	Food Reject (kg)	Food PH	Temp (°C)	Actual Feeding				Generator Running		Time (Hr)	Power Generated			Disposal (kg)	Checked by Supervisor	Approved by JE	Remarks
							Food	SBC	CS	Water	Initial	Final		Initial	Final	Unit (kwh)				
01/06/23											Under Mg									
02/06/23	6.20	34.2	10	0	5.89	38°C	10	0	0	5L	2076.1	2076.3	0.20	4516.6	4516.9	0.30	-	Jabra	J. J. J.	
03/06/23	6.20	34.4	10	0	5.44	38°C	10	0	0	5L	2076.3	2076.5	0.20	4516.9	4517.2	0.30	-	Jabra	J. J. J.	
04/06/23	6.30	34.3	10	0	6.19	38°C	10	0	0	5L	2076.5	2076.8	0.30	4517.2	4517.7	0.50	-	Jabra	J. J. J.	
05/06/23	6.30	34.7	10	0	5.58	39°C	10	0	0	5L	2076.8	2077.1	0.30	4517.7	4518.2	0.50	-	Jabra	J. J. J.	
06/06/23	6.40	35.2	15	0	6.11	39°C	15	0	0	5L	2077.1	2077.4	0.30	4518.2	4518.6	0.40	-	Jabra	J. J. J.	
07/06/23	6.50	35.1	15	0	5.78	39°C	15	0	0	5L	2077.4	2077.7	0.30	4518.6	4519.1	0.50	-	Jabra	J. J. J.	
08/06/23	6.50	35.1	15	0	6.23	39°C	15	0	0	5L	2077.7	2078.1	0.40	4519.1	4519.6	0.50	-	Jabra	J. J. J.	
09/06/23	6.60	34.8	15	0	5.44	39°C	15	0	0	5L	2078.1	2078.4	0.30	4519.6	4520.0	0.40	-	Jabra	J. J. J.	
10/06/23	6.60	34.7	20	0	5.35	40°C	20	0	0	5L	2078.4	2078.7	0.30	4520.0	4520.5	0.50	-	Jabra	J. J. J.	
11/06/23	6.60	35.2	20	0	5.28	39°C	20	0	0	5L	2078.7	2079.1	0.40	4520.5	4521.1	0.60	-	Jabra	J. J. J.	
12/06/23	6.50	35.1	20	0	6.10	39°C	20	0	0	5L	2079.1	2079.5	0.40	4521.1	4521.6	0.50	-	Jabra	J. J. J.	
13/06/23	6.60	35.5	20	0	6.33	39°C	20	0	0	5L	2079.5	2080.0	0.50	4521.6	4522.3	0.70	-	Jabra	J. J. J.	
14/06/23	6.70	34.6	25	0	5.60	40°C	25	0	0	5L	2080.0	2080.4	0.40	4522.3	4522.8	0.50	50 kg.	Jabra	J. J. J.	
15/06/23	6.70	34.8	25	0	5.31	40°C	25	0	0	5L	2080.4	2080.9	0.50	4522.8	4523.4	0.60	-	Jabra	J. J. J.	
16/06/23	6.70	34.7	25	0	5.64	39°C	25	0	0	5L	2080.9	2081.4	0.50	4523.4	4524.1	0.70	-	Jabra	J. J. J.	
17/06/23	6.80	35.1	25	0	6.24	39°C	25	0	0	5L	2081.4	2082.0	0.60	4524.1	4524.8	0.70	-	Jabra	J. J. J.	
18/06/23	6.70	35.3	30	0	5.77	40°C	25	0	0	5L	2082.0	2082.6	0.60	4524.8	4525.6	0.80	-	Jabra	J. J. J.	
19/06/23	6.80	35.0	30	0	5.69	40°C	30	0	0	5L	2082.6	2083.3	0.70	4525.6	4526.4	0.80	-	Jabra	J. J. J.	
20/06/23	6.80	35.1	30	0	6.51	40°C	30	0	0	5L	2083.3	2083.9	0.60	4526.4	4527.1	0.70	-	Jabra	J. J. J.	
21/06/23	6.80	34.9	34	0	5.81	40°C	34	0	0	5L	2083.9	2084.5	0.60	4527.1	4527.8	0.70	50 kg.	Jabra	J. J. J.	
22/06/23	6.80	35.0	21	0	6.22	39°C	21	0	0	5L	2084.5	2085.0	0.50	4527.8	4528.4	0.60	-	Jabra	J. J. J.	
23/06/23	6.90	34.9	14	0	5.38	39°C	14	0	0	5L	2085.0	2085.6	0.60	4528.4	4529.1	0.70	-	Jabra	J. J. J.	
24/06/23	6.90	34.8	15	0	5.17	39°C	15	0	0	5L	2085.6	2086.2	0.60	4529.1	4529.8	0.70	-	Jabra	J. J. J.	
25/06/23	6.80	35.4	17	0	5.88	39°C	17	0	0	5L	2086.2	2086.7	0.50	4529.8	4530.5	0.70	-	Jabra	J. J. J.	
26/06/23	6.90	35.5	15	0	6.42	40°C	15	0	0	5L	2086.7	2087.1	0.40	4530.5	4531.1	0.60	-	Jabra	J. J. J.	
27/06/23	7.0	35.2	11	0	6.24	40°C	11	0	0	5L	2087.1	2087.6	0.50	4531.1	4531.7	0.60	-	Jabra	J. J. J.	
28/06/23	7.0	34.8	12	0	5.71	39°C	12	0	0	5L	2087.6	2087.9	0.30	4531.7	4532.2	0.50	-	Jabra	J. J. J.	
29/06/23	7.0	34.9	17	0	5.54	39°C	17	0	0	5L	2087.9	2088.2	0.50	4532.2	4532.7	0.50	-	Jabra	J. J. J.	
30/06/23	7.0	35.1	25	0	5.89	39°C	25	0	0	5L	2088.2	2088.7	0.40	4532.7	4533.2	0.60	-	Jabra	J. J. J.	

July 2023

Date	PH	PH	Food w/4 el. (kg)	Food w/4 el. (kg)	Food w/4 el. (kg)	PH	Temp	Actual Food	SBK	CS	Feeding water	Individual	General Run	in the (H.Y)	Power Initial	Generated Final	Generated Unit (kwh)	DISP (kg)	Checked by super w/4	Approved by S.E.	Remarks
11/3/23	7.0	34.8	17	0	5.64	40.2	17	0	0	5.1	2088.7	2089.1	0.40	4533.2	4533.8	0.50	—	Dryers	—	—	—
2/3/23	7.0	35.4	20	0	5.90	40.2	20	0	0	5.1	2089.4	2089.5	0.50	4533.8	4534.3	0.60	—	Dryers	—	—	—
3/7/23	7.0	36.2	18	0	5.92	40.2	18	0	0	5.1	2089.5	2089.9	0.40	4534.3	4534.9	0.60	—	Dryers	—	—	—
4/7/23	7.0	36.9	16	0	5.82	39.6	16	0	0	5.1	2089.9	2090.4	0.50	4534.9	4535.4	0.50	—	Dryers	—	—	—
5/7/23	7.1	35.8	20	0	5.88	40.2	20	0	0	5.1	2090.4	2090.9	0.50	4535.4	4535.9	0.50	—	Dryers	—	—	—
6/7/23	7.2	36.7	14	0	5.91	40.2	14	0	0	5.1	2090.9	2091.3	0.40	4535.9	4536.5	0.60	—	Dryers	—	—	—
7/7/23	7.4	39.9	18	1	5.89	39.6	18	0	0	5.1	2091.3	2091.8	0.50	4536.5	4537.0	0.50	—	Dryers	—	—	—
8/7/23	7.2	35.7	13	1	5.70	40.2	12	0	0	5.1	2091.8	2092.2	0.40	4537.0	4537.5	0.50	—	Dryers	—	—	—
9/7/23	7.4	38.7	15	1	5.41	40.2	14	0	0	5.1	2092.2	2092.6	0.40	4537.5	4538.0	0.50	—	Dryers	—	—	—
10/7/23	7.1	37.4	30	2	5.88	39.6	28	0	0	5.1	2092.6	2093.1	0.50	4538.0	4538.6	0.60	—	Dryers	—	—	—
11/7/23	7.1	38.2	20	1	5.72	40.2	19	0	0	5.1	2093.1	2093.5	0.40	4538.6	4539.1	0.50	—	Dryers	—	—	—
12/7/23	7.0	38.6	18	1	5.88	40.2	17	0	0	5.1	2093.5	2093.9	0.40	4539.1	4539.7	0.60	—	Dryers	—	—	—
13/7/23	7.3	36.2	25	1	5.77	39.6	24	0	0	5.1	2093.9	2094.4	0.50	4539.7	4540.3	0.60	—	Dryers	—	—	—
14/7/23	7.4	36.4	30	2	5.60	40.2	28	0	0	5.1	2094.4	2094.8	0.40	4540.3	4540.9	0.60	—	Dryers	—	—	—
15/7/23	7.6	35.7	30	1	5.32	39.6	29	0	0	7.0	2094.8	2095.4	0.60	4540.9	4541.4	0.50	—	Dryers	—	—	—
16/7/23	7.2	35.6	40	1	5.38	40.2	39	0	0	8.0	2095.4	2095.9	0.50	4541.4	4541.9	0.50	—	Dryers	—	—	—
17/7/23	7.2	35.4	40	2	5.35	40.2	38	0	0	8.0	2095.9	2096.3	0.40	4541.9	4542.5	0.60	—	Dryers	—	—	—
18/7/23	7.3	36.4	45	2	5.39	40.2	43	0	0	10.0	2096.3	2096.9	0.60	4542.5	4543.0	0.50	—	Dryers	—	—	—
19/7/23	7.4	36.2	50	1	5.32	40.2	49	0	0	10.0	2096.9	2097.4	0.50	4543.0	4543.6	0.60	—	Dryers	—	—	—
20/7/23	7.3	36.3	50	1	5.38	39.6	49	0	0	10.0	2097.4	2097.8	0.40	4543.6	4544.2	0.60	—	Dryers	—	—	—
21/7/23	7.4	35.4	50	1	5.36	39.6	49	0	0	10.0	2097.8	2098.3	0.50	4544.2	4544.7	0.50	—	Dryers	—	—	—
22/7/23	7.2	35.4	60	1	5.39	40.2	59	0	0	10.0	2098.3	2098.9	0.60	4544.7	4545.3	0.60	—	Dryers	—	—	—
23/7/23	7.1	36.5	60	2	5.36	40.2	58	0	0	10.0	2098.9	2099.4	0.50	4545.3	4545.8	0.50	—	Dryers	—	—	—
24/7/23	7.2	36.4	50	1	5.38	39.6	49	0	0	7.0	2099.4	2099.8	0.40	4545.8	4546.3	0.50	—	Dryers	—	—	—
25/7/23	7.0	35.3	50	0	5.41	39.6	50	0	0	7.0	2099.8	2100.3	0.50	4546.3	4546.9	0.60	—	Dryers	—	—	—
26/7/23	7.1	36.1	40	0	5.39	39.6	40	0	0	7.0	2100.3	2100.8	0.50	4546.9	4547.5	0.60	—	Dryers	—	—	—
27/7/23	7.2	35.2	40	1	5.32	39.6	39	0	0	8.0	2100.8	2101.2	0.40	4547.5	4548.0	0.50	—	Dryers	—	—	—
28/7/23	7.4	36.4	30	0	5.48	40.2	30	0	0	5.0	2101.2	2101.6	0.40	4548.0	4548.5	0.50	—	Dryers	—	—	—
29/7/23	7.3	36.2	40	0	5.40	40.2	40	0	0	5.0	2101.6	2102.0	0.40	4548.5	4549.0	0.50	—	Dryers	—	—	—
30/7/23	7.2	36.4	45	0	5.45	39.6	45	0	0	5.0	2102.0	2102.5	0.50	4549.0	4550.1	0.60	—	Dryers	—	—	—
31/7/23	7.4	35.4	40	0	5.40	39.6	40	0	0	5.0	2102.5	2103.0	0.50	4550.1	4550.7	0.60	—	Dryers	—	—	—

Date	PH	PH 4.4	Food Received (kg)	Food Retort (kg)	Food PH	Temp (°C)	Actual			Feeding			Generator Running		Time (Hr)	Power Generated			Disposal (kg)	Checked by Supervisor	Approved by JE	Remarks	
							Food	Spc	CS	Water	Initial	Final	Initial	Final		Unit (kwh)							
1-08-23	7.0	34.8	40	0	5.88	40c	40	0	0	50	2103.0	2103.3	0.30	4550.7	4551.1	0.40	—	Nitesh					
2-08-23	7.0	35.4	40	0	5.87	40c	40	0	0	50	2103.3	2103.6	0.30	4551.1	4551.5	0.40	—	Nitesh					
3-08-23	7.1	36.2	40	0	5.90	40c	40	0	0	50	2103.6	2104.0	0.40	4551.5	4552.0	0.50	—	Nitesh					
4-08-23	7.0	34.4	50	0	5.71	39c	50	0	0	100	2104.0	2104.4	0.40	4552.0	4552.5	0.50	—	Nitesh					
5-08-23	7.1	35.2	50	0	5.77	40c	50	0	0	100	2104.4	2104.8	0.40	4552.5	4553.0	0.50	—	Nitesh					
6-08-23	7.2	35.6	50	0	5.88	39c	50	0	0	100	2104.8	2105.3	0.50	4553.0	4553.6	0.60	—	Nitesh				Sunday	
7-08-23	7.1	34.2	50	0	5.71	40c	50	0	0	100	2105.3	2105.8	0.50	4553.6	4554.2	0.60	—	Nitesh					
8-08-23	7.2	35.7	50	0	5.91	39c	50	0	0	100	2105.8	2106.2	0.40	4554.2	4554.7	0.50	—	Nitesh					
9-08-23	7.4	36.2	60	1	5.88	39c	60	0	0	100	2106.2	2106.7	0.50	4554.7	4555.4	0.70	—	Nitesh					
10-08-23	7.2	35.8	60	1	5.60	40c	60	0	0	100	2106.7	2107.1	0.40	4555.4	4555.9	0.50	—	Nitesh					
11-08-23	7.4	35.2	60	0	5.77	40c	60	0	0	100	2107.1	2107.5	0.40	4555.9	4556.4	0.50	—	Nitesh					
12-08-23	7.4	36.2	60	0	5.70	40c	60	0	0	100	2107.5	2108.0	0.50	4556.4	4557.0	0.60	—	Nitesh					
13-08-23	7.2	36.4	60	1	5.66	40c	60	0	0	100	2108.0	2108.5	0.50	4557.0	4557.6	0.60	—	Nitesh				Sunday	
14-08-23	7.2	35.8	60	0	5.60	40c	60	0	0	100	2108.5	2109.0	0.50	4557.6	4558.2	0.60	—	Nitesh					
15-08-23	7.4	36.4	60	0	5.70	40c	60	0	0	100	2109.0	2110.04	0.50	4558.2	4558.8	0.60	—	Nitesh					
16-08-23	7.4	36.2	60	0	5.77	39c	60	0	0	100	2110.04	2111.0	0.60	4558.8	4559.3	0.50	—	Nitesh					
17-08-23	7.2	36.4	50	0	5.71	39c	50	0	0	100	2111.0	2111.5	0.50	4559.3	4559.9	0.60	—	Nitesh					
18-08-23	7.6	38.4	60	0	5.90	39c	60	0	0	100	2111.5	2112.0	0.50	4559.9	4560.5	0.60	—	Nitesh					
19-08-23	7.5	36.2	70	0	5.70	39c	70	0	0	100	2112.0	2112.4	0.40	4560.5	4561.0	0.50	—	Nitesh					
20-08-23	7.1	35.1	70	1	5.80	40c	70	0	0	100	2112.4	2112.9	0.50	4561.0	4561.5	0.50	—	Nitesh					
21-08-23	7.2	35.7	70	0	5.81	40c	70	0	0	100	2112.9	2113.4	0.50	4561.5	4562.1	0.60	—	Nitesh					
22-08-23	7.2	38.2	70	1	5.91	40c	70	0	0	100	2113.4	2113.8	0.40	4562.1	4562.6	0.50	—	Nitesh					
23-08-23	7.4	36.2	70	0	5.75	40c	70	0	0	100	2113.8	2114.3	0.50	4562.6	4563.2	0.60	—	Nitesh					
24-08-23	7.1	38.2	70	0	5.77	40c	70	0	0	100	2114.3	2114.8	0.50	4563.2	4563.8	0.60	—	Nitesh					
25-08-23	7.2	38.1	80	0	5.85	40c	80	0	0	100	2114.8	2115.3	0.50	4563.8	4564.4	0.60	—	Nitesh					
26-08-23	7.4	36.6	70	2	5.90	40c	70	0	0	150	2115.3	2115.9	0.60	4564.4	4565.1	0.70	—	Nitesh					
27-08-23	7.2	36.2	80	1	5.95	40c	80	0	0	120	2115.9	2116.4	0.50	4565.1	4565.7	0.60	—	Nitesh				Sunday	
28-08-23	7.2	35.4	70	0	5.77	40c	70	0	0	100	2116.4	2116.9	0.50	4565.7	4566.3	0.60	—	Nitesh					
29-08-23	7.4	36.2	70	1	5.80	40c	70	0	0	100	2116.9	2117.4	0.50	4566.3	4566.9	0.60	—	Nitesh					
30-08-23	7.3	36.6	70	1	5.92	40c	70	0	0	100	2117.4	2117.9	0.50	4566.9	4567.4	0.50	—	Nitesh					
31-08-23	7.6	35.4	70	0	5.71	40c	70	0	0	100	2117.9	2118.4	0.50	4567.4	4567.9	0.50	—	Nitesh					

September 2023

Date	PH	PH 4.4	Food Received (Kg)	Food Reject (Kg)	Food PH	Temp (°C)	Actual		Feeding		Generator		Time Hr	Power Generated			Disposal (Kg)	Checked Supervisor	Approved by JF	Remarks
							Food	Spk	CS	water	Initial	Final		Initial	Final	unit(kwh)				
1-09-23	7.4	36.4	70	0	5.92	40°C	70	0	0	100	2118.4	2119.0	0.60	4567.9	4568.4	0.50	—	Nitesh	JF 21/9	
2-09-23	7.4	36.6	70	0	5.70	40°C	70	0	0	100	2119.0	2119.6	0.60	4568.4	4568.9	0.50	—	Nitesh	JF 21/9	
3-09-23	7.9	36.9	80	0	5.44	40°C	80	0	0	100	2119.6	2120.2	0.60	4568.9	4569.4	0.50	—	Nitesh	JF 21/9	
4-09-23	7.0	35.5	70	0	5.40	40°C	70	0	0	100	2120.2	2120.8	0.60	4569.4	4569.9	0.50	—	Nitesh	Sunday	
5-09-23	7.1	36.1	75	1	5.50	40°C	75	0	0	100	2120.8	2121.5	0.70	4569.4	4570.5	0.60	—	Nitesh	JF 21/9	
6-09-23	7.6	36.3	75	0	5.41	40°C	75	0	0	100	2121.5	2122.2	0.70	4570.5	4571.1	0.60	—	Nitesh	JF 21/9	
7-09-23	7.2	36.0	80	0	5.80	40°C	80	0	0	150	2122.2	2122.9	0.70	4571.1	4571.7	0.60	—	Nitesh	holiday	
8-09-23	7.4	35.8	80	1	5.80	40°C	80	0	0	150	2122.9	2123.5	0.60	4571.7	4572.2	0.50	—	Nitesh	- 920 -	
9-09-23	7.2	35.5	80	1	5.70	39°C	80	0	0	150	2123.5	2124.1	0.60	4572.2	4572.7	0.50	—	Nitesh	- 920 -	
10-09-23	7.0	36.2	85	0	5.71	39°C	85	0	0	150	2124.1	2124.8	0.70	4572.7	4573.3	0.60	—	Nitesh	Sunday	
11-09-23	7.0	36.0	90	0	5.52	40°C	90	0	0	150	2124.8	2125.5	0.70	4573.3	4573.9	0.60	—	Nitesh	JF 21/9	
12-09-23	7.8	36.7	90	0	5.60	40°C	90	0	0	150	2125.5	2126.2	0.70	4573.9	4574.6	0.70	—	Nitesh	JF 21/9	
13-09-23	7.6	35.9	90	0	5.77	40°C	90	0	0	150	2126.2	2126.8	0.60	4574.6	4575.2	0.60	—	Nitesh	JF 21/9	
14-09-23	7.4	35.8	90	0	5.71	39°C	90	0	0	150	2126.8	2127.4	0.60	4575.2	4575.8	0.60	—	Nitesh	JF 21/9	
15-09-23	7.4	35.7	80	0	5.66	39°C	80	0	0	120	2127.4	2128.0	0.60	4575.8	4576.5	0.70	—	Nitesh	JF 21/9	
16-09-23	7.2	36.2	80	0	5.71	40°C	80	0	0	120	2128.0	2128.7	0.70	4576.5	4577.1	0.60	—	Nitesh	JF 21/9	
17-09-23	7.4	36.4	90	0	5.80	40°C	80	0	0	150	2128.7	2129.4	0.70	4577.1	4577.7	0.60	—	Nitesh	Sunday	
18-09-23	7.2	36.8	90	0	5.74	40°C	90	0	0	150	2129.4	2130.0	0.60	4577.7	4578.2	0.50	—	Nitesh	JF 21/9	
19-09-23	7.6	36.9	90	2	5.88	40°C	90	0	0	150	2130.0	2130.5	0.50	4578.2	4578.7	0.50	—	Nitesh	JF 21/9	
20-09-23	7.4	36.5	90	1	6.11	40°C	90	0	0	150	2130.5	2131.0	0.50	4578.7	4579.3	0.60	—	Nitesh	JF 21/9	
21-09-23	7.4	35.9	100	1	5.69	40°C	100	0	0	200	2131.0	2131.6	0.60	4579.3	4579.9	0.60	—	Nitesh	JF 21/9	
22-09-23	7.2	35.9	100	1	5.80	40°C	100	0	0	200	2131.6	2132.1	0.50	4579.9	4580.6	0.70	—	Nitesh	JF 21/9	
23-09-23	7.4	35.9	100	0	5.60	40°C	100	0	0	200	2132.1	2132.7	0.60	4580.6	4581.3	0.70	—	Nitesh	JF 21/9	
24-09-23	7.2	35.7	100	0	5.70	40°C	100	0	0	200	2132.7	2133.2	0.50	4581.3	4582.0	0.70	—	Nitesh	Sunday	
25-09-23	7.6	38.1	100	0	5.92	40°C	100	0	0	200	2133.2	2133.8	0.60	4582.0	4582.6	0.60	—	Nitesh	JF 21/9	
26-09-23	7.4	36.7	110	0	5.81	40°C	110	0	0	200	2133.8	2134.3	0.50	4582.6	4583.2	0.60	—	Nitesh	JF 21/9	
27-09-23	7.2	35.4	110	0	5.77	40°C	110	0	0	200	2134.3	2134.8	0.50	4583.2	4583.8	0.60	—	Nitesh	JF 21/9	
28-09-23	7.2	35.6	100	0	5.70	40°C	100	0	0	200	2134.8	2135.3	0.50	4583.8	4584.4	0.60	—	Nitesh	JF 21/9	
29-09-23	7.0	35.1	110	0	5.40	39°C	110	0	0	200	2135.3	2135.8	0.55	4584.4	4585.0	0.70	—	Nitesh	JF 21/9	
30-09-23	7.1	35.5	110	0	5.60	39°C	110	0	0	200	2135.8	2136.35	1	4585.0	4585.7	1.1	—	Nitesh	JF 21/9	

Date

Date

Date	Liquid		Food Received (KWh)	Food Accum (KWh)	Food PH (C)	TEMP (C)	Actual Food (KWh)	Feeding SOLCS	Water Water	Circulation Initial	Water Final	Run Time (HR)	Power generated			Disposal KWh	Checked Supervisor	Approved by J.E	Remarks	
	PH	PH											Initial	Final	Unit (KWh)					
1-10-23	7.1	34.4	110	0	5.1	40°C	110	0	0	20L	2136.35	2137.35	1.00	4585.8	4586.8	1.00	—	Nitesh	—	
2-10-23	7.3	36.3	100	0	5.9	40°C	100	0	0	20L	2137.35	2138.35	0.55	4586.8	4587.8	0.60	—	Nitesh	—	
3-10-23	7.4	35.9	100	0	5.6	39°C	100	0	0	20L	2138.35	2138.9	0.60	4587.8	4588.40	0.80	—	Nitesh	—	Do not
4-10-23	7.2	36.4	100	0	5.4	39°C	100	0	0	15L	2138.9	2139.5	1.10	4588.40	4589.2	0.70	—	Nitesh	—	Do not
5-10-23	7.1	35.6	100	0	5.7	40°C	100	0	0	10L	2139.5	2140.6	1.00	4589.2	4590.3	1.10	110	Nitesh	—	Do not
6-10-23	7.53	35.4	150	0	5.6	40°C	350	0	0	30L	2140.6	2142.6	2.00	4590.3	4594.8	4.5	—	Nitesh	—	
7-10-23	7.62	35.6	145	1	5.7	40°C	320	0	0	30L	2142.6	2145.1	2.5	4594.8	4600.3	5.5	120	Nitesh	—	
8-10-23	7.60	36.2	200	0	5.5	40°C	325	0	0	35L	2145.1	2148.1	3.0	4600.3	4608.5	8.2	—	Nitesh	—	
9-10-23	7.39	34.6	250	1	5.7	40°C	325	0	0	35L	2148.1	2151.3	3.2	4608.5	4618.6	10.1	150	Nitesh	—	
11-10-23	7.44	34.2	300	0	5.7	40°C	330	0	0	32L	2151.3	2154.7	3.4	4618.6	4630.0	11.4	—	Nitesh	—	
12-10-23	7.50	34.2	300	2	5.7	40°C	330	0	0	35L	2154.7	2158.2	3.5	4630.0	4642.5	12.5	200	Nitesh	—	
13-10-23	7.56	34.6	330	1	5.6	40°C	350	0	0	38L	2158.2	2161.9	3.7	4642.5	4657.0	14.5	—	Nitesh	—	
14-10-23	7.62	34.7	365	1	5.6	40°C	350	0	0	35L	2161.9	2165.9	4.0	4657.0	4673.1	16.1	300	Nitesh	—	
15-10-23	7.60	35.2	370	1	5.7	40°C	360	0	0	35L	2165.9	2169.8	3.9	4673.1	4689.0	15.9	—	Nitesh	—	
16-10-23	7.58	35.4	375	0	5.7	40°C	360	0	0	40L	2169.8	2173.6	3.8	4689.0	4704.2	15.2	—	Nitesh	—	
17-10-23	7.49	35.6	390	1	5.7	40°C	370	0	0	35L	2173.6	2177.5	3.9	4704.2	4720.2	16.0	350	Nitesh	—	
18-10-23	7.50	35.7	400	1	5.5	40°C	390	0	0	30L	2177.5	2181.5	4.0	4720.2	4736.7	16.5	—	Nitesh	—	
19-10-23	7.55	36.1	400	1	5.5	40°C	400	0	0	35L	2181.5	2185.7	4.2	4736.7	4754.2	17.5	—	Nitesh	—	
20-10-23	7.62	36.2	390	0	5.4	40°C	380	0	0	35L	2185.7	2189.7	4.0	4754.2	4771.2	17.0	—	Nitesh	—	
21-10-23	7.60	36.4	395	1	5.5	40°C	390	0	0	40L	2189.7	2193.6	3.9	4771.2	4787.2	16.0	400	Nitesh	—	
22-10-23	7.58	36.2	400	0	5.5	40°C	395	0	0	40L	2193.6	2197.5	3.9	4787.2	4803.1	15.9	—	Nitesh	—	
23-10-23	7.61	36.4	420	0	5.6	40°C	410	0	0	35L	2197.5	2204.6	4.1	4803.1	4819.5	16.4	—	Nitesh	—	
24-10-23	7.58	36.2	420	0	5.6	40°C	415	0	0	40L	2204.6	2205.7	4.1	4819.5	4836.3	16.8	—	Nitesh	—	
25-10-23	7.58	36.4	415	1	5.6	40°C	415	0	0	40L	2205.7	2210.0	4.3	4836.3	4854.8	18.5	150	Nitesh	—	
26-10-23	7.63	36.1	410	0	5.6	40°C	400	0	0	40L	2210.0	2214.0	4.0	4854.8	4871.9	17.1	—	Nitesh	—	
27-10-23	7.59	36.2	430	0	5.7	40°C	430	0	0	40L	2214.0	2218.3	4.3	4871.9	4890.4	18.5	—	Nitesh	—	
28-10-23	7.56	36.4	435	0	5.6	40°C	430	0	0	40L	2218.3	2222.7	4.4	4890.4	4909.5	19.1	—	Nitesh	—	
29-10-23	7.60	36.4	425	0	5.6	40°C	425	0	0	40L	2222.7	2227.0	4.3	4909.5	4928.0	18.5	450	Nitesh	—	
30-10-23	7.58	36.2	440	0	5.4	40°C	430	0	0	40L	2227.0	2231.4	4.4	4928.0	4948.1	20.1	—	Nitesh	—	
31-10-23	7.57	36.4	450	0	5.6	40°C	440	0	0	40L	2231.4	2235.9	4.5	4948.1	4968.6	20.5	480	Nitesh	—	

150

Date

November - 2023

Date

Date	PH		Food Received (KG)	Food Rejected (KG)	Added Cow/pts	Food PH	Temp (C)	Actual Feeding			Generator Initial	
	PH	PH 4.4						Food	SBC	CS		Water
1-11-2023	7.53	36.2	470	1		5.60	AoC	460	0	0	40l	2235.9
2-11-2023	7.62	36.1	475	2		5.57	AoC	450	0	0	40l	2238.3
3-11-2023	7.49	36.2	465	0		5.54	AoC	450	0	0	40l	2240.4
4-11-2023	7.55	35.8	475	0		5.56	AoC	460	0	0	45l	2242.6
5-11-2023	7.63	35.7	480	0		5.51	AoC	470	0	0	45l	2244.6
6-11-2023	7.58	35.8	490	0		5.62	AoC	490	0	0	45l	2246.4
7-11-2023	7.57	35.9	505	0		5.67	AoC	490	0	0	50l	2248.3
8-11-2023	7.60	35.7	565	1		5.64	AoC	500	0	0	50l	2250.4
9-11-2023	7.53	35.6	600	0		5.53	AoC	500	0	0	50l	2252.7
10-11-2023	7.49	35.8	570	1		5.48	AoC	520	0	0	40l	2254.7
11-11-2023	7.48	35.6	520	0		5.39	AoC	510	0	0	35l	2257.1
12-11-2023	7.54	35.9	410	1	150	5.51	AoC	560	0	0	30l	2259.3
13-11-2023	7.59	35.6	360	1	200	5.63	AoC	560	0	0	30l	2261.4
14-11-2023	7.48	35.4	300	1	250	5.61	AoC	550	0	0	20l	2263.3
15-11-2023	7.44	35.2	390	0	160	5.62	AoC	560	0	0	20l	2265.3
16-11-2023	7.51	35.8	365	0	180	5.71	AoC	545	0	0	20l	2267.8
17-11-2023	7.47	35.9	450	0	100	5.48	AoC	550	0	0	15l	2269.8
18-11-2023	7.50	35.8	470	0	70	5.65	AoC	540	0	0	10l	2272.2
19-11-2023	7.44	35.7	430	0	80	5.71	39C	510	0	0	10l	2274.0
20-11-2023	7.41	35.6	410	0	100	5.68	39C	540	0	0	10l	2275.9
21-11-2023	7.52	35.4	330	0	150	5.49	AoC	480	0	0	15l	2278.1
22-11-2023	7.37	38.1	360	0	120	5.64	AoC	480	0	0	10l	2280.1
23-11-2023	7.44	36.4	400	2	100	5.57	AoC	500	0	0	10l	2282.2
24-11-2023	7.49	36.2	460	3	50	5.42	AoC	510	0	0	15l	2284.3
25-11-2023	7.53	35.2	450	0	50	5.70	AoC	500	0	0	10l	2286.5
26-11-2023	7.51	35.6	400	0	100	5.67	AoC	500	0	0	10l	2288.2
27-11-2023	7.60	36.1	410	0	100	5.59	39C	510	0	0	10l	2290.1
28-11-2023	7.64	36.4	425	0	50	5.42	AoC	475	0	0	10l	2292.1
29-11-2023	7.60	34.8	430	0	50	5.61	AoC	480	0	0	10l	2294.3
30-11-2023	7.62	35.6	430	0	50	5.68	AoC	480	0	0	10l	2296.6

Running Final	Time (Hr)	Power Generated			Disposal (KG)	Checked Supervisor	Approved By J/E	Remarks
		Initial	Final	Unit (KWh)				
2238.3	2.4	4948.6	4961.0	12.4	-	Nitesh		
2240.4	2.1	4961.0	4972.8	11.8	400	Nitesh		
2242.6	2.2	4972.8	4984.7	11.9	-	Nitesh		
2244.6	2.0	4984.7	4995.7	11.0	-	Nitesh		
2246.4	1.8	4995.7	5006.2	10.5	600	Nitesh		
2248.3	1.9	5006.2	5017.0	10.8	-	Nitesh		
2250.4	2.1	5017.0	5028.1	11.1	-	Nitesh		
2252.7	2.3	5028.1	5039.5	11.4	500	Nitesh		
2254.7	2.0	5039.5	5050.5	11.0	-	Nitesh		
2257.1	2.4	5050.5	5062.5	12.0	-	Nitesh		
2259.3	2.2	5062.5	5073.8	11.3	-	Nitesh		
2261.4	2.1	5073.8	5085.1	11.3	600	Nitesh		
2263.3	1.9	5085.1	5096.0	10.9	-	Nitesh		
2265.3	2.0	5096.0	5107.0	11.0	-	Nitesh		
2267.8	2.5	5107.0	5119.4	12.4	400	Nitesh		
2269.8	2.0	5119.4	5130.4	11.0	-	Nitesh		
2272.2	2.4	5130.4	5142.4	12.0	500	Nitesh		
2274.0	1.8	5142.4	5153.0	10.6	-	Nitesh		
2275.9	1.9	5153.0	5163.7	10.7	-	Nitesh		
2278.1	2.2	5163.7	5175.5	11.8	-	Nitesh		
2280.1	2.0	5175.5	5187.2	11.7	500	Nitesh		
2282.2	2.1	5187.2	5198.8	11.6	-	Nitesh		
2284.3	2.1	5198.8	5210.5	11.7	400	Nitesh		
2286.5	2.2	5210.5	5222.1	11.6	-	Nitesh		
2288.2	1.7	5222.1	5232.2	10.1	600	Nitesh		
2290.1	1.9	5232.2	5242.8	10.6	-	Nitesh		
2292.1	2.0	5242.8	5253.8	11.0	400	Nitesh		
2294.3	2.2	5253.8	5264.8	11.0	-	Nitesh		
2296.6	2.3	5264.8	5276.2	11.4	400	Nitesh		
2298.7	2.1	5276.2	5287.8	11.6	-	Nitesh		

518

Date

December - 2023

A1

Date

Date	PH		Food Received (kg)	Food Rejected (kg)	Able to Cough	Food PH	Temp (C)	Actual Feeding				Generator Initial	Running Final	Time (hr)	Power Generated			Disposal (kg)	Checked Supervisor	Approved By P.J.E	Remarks
	PH	A.A						Food	SBC	CS	Water				Initial	Final	Unit (kwh)				
1-12-2023	7.51	35.7	743	1	0	5.58	40c	1140	0	0	10l	2298.7	2300.6	1.9	5287.8	5297.9	10.1	400	Nitesh		
2-12-2023	7.43	35.9	754	2	0	5.61	40c	1149	0	0	10l	2300.6	2303.2	2.6	5297.9	5310.5	12.6	-	Nitesh		
3-12-2023	7.54	35.8	650	1	0	5.49	40c	1100	0	0	15l	2303.2	2305.6	2.4	5310.5	5322.9	12.4	500	Nitesh	Sunday	
4-12-2023	7.49	35.4	615	2	0	5.53	40c	1160	0	0	15l	2305.6	2307.9	2.3	5322.9	5334.9	12.0	-	Nitesh		
5-12-2023	7.46	36.4	761	0	0	5.60	40c	1170	0	0	15l	2307.9	2310.0	2.1	5334.9	5346.7	11.8	600	Nitesh		
6-12-2023	7.45	36.1	752	0	0	5.63	40c	1150	0	0	15l	2310.0	2312.0	2.0	5346.7	5358.4	11.7	-	Nitesh		
7-12-2023	7.51	36.2	630	0	0	5.62	40c	1120	0	0	20l	2312.0	2313.8	1.8	5358.4	5369.2	10.8	-	Nitesh		
8-12-2023	7.42	36.0	765	1	0	5.54	40c	1160	0	0	20l	2313.8	2315.7	1.9	5369.2	5380.2	11.0	600	Nitesh		
9-12-2023	7.44	36.8	747	1	0	5.62	40c	1100	0	0	20l	2315.7	2317.8	2.1	5380.2	5391.8	11.6	-	Nitesh		
10-12-2023	7.48	35.7	750	2	0	5.71	40c	1110	0	0	25l	2317.8	2319.8	2.0	5391.8	5403.6	11.8	480	Nitesh	Sunday	
11-12-2023	7.49	35.6	712	0	0	5.61	40c	1100	0	0	30l	2319.8	2322.0	2.2	5403.6	5415.8	12.2	-	Nitesh		
12-12-2023	7.52	35.4	687	0	20	5.59	39c	1185	0	0	30l	2322.0	2324.1	2.1	5415.8	5427.9	12.1	-	Nitesh		
13-12-2023	7.63	35.1	630	1	50	5.60	40c	1180	0	0	30l	2324.1	2326.4	2.3	5427.9	5440.3	12.4	550	Nitesh		
14-12-2023	7.41	36.2	610	1	75	5.70	40c	1185	0	0	25l	2326.4	2328.8	2.4	5440.3	5452.7	12.4		Nitesh		
15-12-2023	7.46	36.1	580	0	95	5.72	40c	1175	0	0	30l	2328.8	2330.9	2.1	5452.7	5464.9	12.2		Nitesh		
16-12-2023	7.53	36.0	545	1	105	5.58	40c	1140	0	0	30l	2330.9	2332.6	1.7	5464.9	5475.8	10.9	500	Nitesh		
17-12-2023	7.61	36.2	450	1	200	5.64	40c	1150	0	0	25l	2332.6	2334.5	1.9	5475.8	5486.7	10.9		Nitesh	Sunday	
18-12-2023	7.60	36.4	340	0	310	5.73	40c	1150	0	0	30l	2334.5	2336.5	2.0	5486.7	5498.2	11.5		Nitesh		
19-12-2023	7.55	36.4	300	0	350	5.63	40c	1150	0	0	30l	2336.5	2338.7	2.2	5498.2	5510.7	12.5	450	Nitesh		
20-12-2023	7.47	36.2	280	0	400	5.56	40c	1180	0	0	40l	2338.7	2341.0	2.3	5510.7	5523.0	12.3		Nitesh		
21-12-2023	7.57	36.4	100	0	500	5.60	40c	1100	0	0	50l	2341.0	2343.4	2.4	5523.0	5535.4	12.4	400	Nitesh		
22-12-2023	7.55	36.1	100	0	500	5.72	40c	1100	0	0	50l	2343.4	2345.5	2.1	5535.4	5547.6	12.2		Nitesh		
23-12-2023	7.60	36.0	90	0	510	5.70	40c	1100	0	0	50l	2345.5	2347.7	2.2	5547.6	5560.0	12.4		Nitesh		
24-12-2023	7.60	36.2	110	1	500	5.58	40c	1110	0	0	50l	2347.7	2350.0	2.3	5560.0	5572.5	12.5	500	Nitesh	Sunday	
25-12-2023	7.40	35.9	75	0	450	5.60	39c	1125	0	0	50l	2350.0	2352.0	2.0	5572.5	5584.5	12.0		Nitesh		
26-12-2023	7.63	35.7	80	1	430	5.66	40c	1110	0	0	60l	2352.0	2354.1	2.1	5584.5	5596.6	12.1		Nitesh		
27-12-2023	7.50	35.4	90	1	450	5.55	40c	1110	0	0	50l	2354.1	2356.3	2.2	5596.6	5609.0	12.4	500	Nitesh		
28-12-2023	7.55	35.2	100	0	400	5.59	40c	1100	0	0	50l	2356.3	2358.1	1.8	5609.0	5619.8	10.8		Nitesh		
29-12-2023	7.42	35.4	100	0	4150	5.54	40c	1150	0	0	50l	2358.1	2359.8	1.7	5619.8	5630.5	10.7	480	Nitesh		
30-12-2023	7.43	35.6	100	0	4150	5.60	40c	1150	0	0	50l	2359.8	2361.4	1.6	5630.5	5641.0	10.5		Nitesh		
31-12-2023	7.50	35.7	100	0	4100	5.62	39c	1100	0	0	50l	2361.4	2363.2	1.8	5641.0	5651.6	10.6		Nitesh	Sunday	

2022-23

AQAR for AY 2022-23

Criteria	Description	Paragraphs for AQAR 2022-23
7.1.4	<p>Water conservation facilities available in the Institution:</p> <p>a) Rain water Harvesting Bore well/Open well recharge</p> <p>b) Construction of tanks and bunds Waste water recycling</p> <p>c) Maintenance of water bodies and distribution system in the campus</p>	<p>The university has implemented a comprehensive rainwater harvesting system across its campus for improving groundwater levels. This includes rainwater harvesting pits covering a 2500 sqm catchment area adjacent to newly constructed academic blocks. The university capitalizes on its extensive 529000 sqm green cover, enabling natural rainwater percolation from neighbouring structures, complementing the campus-wide groundwater enhancement strategy. Notably, rainwater harvesting is integrated into all ongoing construction projects observable in the recently completed academic blocks 3 and 4. In addition to these initiatives, DTU has sought supplementary water supply from Delhi Jal Board to alleviate the strain on existing groundwater boreholes. Moreover, the campus has a 3000 sqm pond, serving as a reservoir for rainwater collection and contributing significantly to the overall augmentation of groundwater levels. Concurrently, the Sewage Treatment Plant efficiently recycles water, catering to the institution's horticultural and cleaning needs. Furthering its commitment to sustainable development, recent proposals gaining approval this year marks DTU's dedication to holistic enhancements. These include the thoughtfully planned improvement of the existing pond with aesthetically managed water overflow, the construction of a G+3 storeys student activity centre with a trapezoidal structure designed to accommodate yoga, meditation, and gymnasium facilities, and the establishment of a spacious 3-meter-wide pathway devoid of any boundary walls. Emphasizing the campus's excitement, forthcoming plans for a mini waterfall adjoining the pond and the installation of appropriate lighting arrangements have been approved. These initiatives reflect DTU's dedication to sustainable practices and infrastructure development for the welfare and engagement of its community.</p>



270

el

ENGINEERING CELL
DELHI TECHNOLOGICAL UNIVERSITY
Shahbad Daultapur, Main Bawana Road, Delhi - 110042

F.NO: DTU/Engg Cell/002591/2019-20/Civil/ 1157

Dated: 28/7/22

To,
The Additional Chief Engineer M-3
Delhi Jal Board, Govt. of N.C.T. of Delhi
H-Block, Sector-15, Rohini, Delhi-110089

Sub: - Augmentation of Water Supply by D.JB in Delhi Technological University-Reg.

Sir,

Kindly refer to letter No. D.JB/ZE-VII (NW)-II/2020/375 dated 01-02-2020 regarding water supply /ferrule connection 25 mm dia. with communication pipe 50 mm dia. (G.I. pipe) approved by D.JB against the total water requirement of 2.44 MLD for DTU Campus. (1.25 MLD Potable water + 1.19 MLD Non-Potable requirements). In this connection it is stated that there is an urgent need of augmentation of water supply in Delhi Technological University due to the following:-

1. Recently the Girls Hostel (660 Bed capacity) & Boys Hostel (330 Capacity) have been constructed and inaugurated by Hon'ble Deputy Chief Minister on 20th July 2022. These hostels are being started w.e.f. 01.08.2022. In view of this, now the water supply available to DTU is insufficient to cater the needs of residents and hostellers.
2. The present demand of potable water supply is about 1.25 MLD to cater the need of resident's hostels and academic buildings. However, the present connection of the water supply is able to deliver only 0.18 MLD against actual demand of 1.25 MLD potable water. Therefore, it is requested to provide one separate connection/meter for academic buildings of the University.
3. Permission for **installation of 08 (Eight) bore wells** in the DTU Campus may be accorded. The treated water can be used for supply potable water to hostels & residents after treatment in the case of emergency as present supply is only about 15% (0.18 MLD) of sanctioned demand of (1.25 MLD).

In this regard a request has been sent through letter No. DTU/Engg Cell/002298/2017-18/Civil/2394 on dated 11.02.2022 addressed to Chief Executive Officer, 1st Floor Varunalaya Ph-I, Jhandewalan, Karol Bagh, New Delhi, Delhi 110005. (Copy enclosed).

You are therefore, requested to augment the water supply and increase the connection size so that university can get the water of demand duly sanctioned vide office letter No. D.JB/ZE-VII (NW)-II/2020/375 dated 01-02-2020 and accord permission to install 8 bore wells to meet out water deficiency in the DTU Campus.

D/K

2
3

(Prof. Madhusudan Singh)
Registrar, DTU

Delhi Technological University
(Formerly Delhi College of Engineering)
Shahbad Daultapur, Bawana Road,
Delhi-110042

ACE(M)-3 1230
Diary No.....
Date 28-7-22



ENGINEERING CELL
DELHI TECHNOLOGICAL UNIVERSITY
Shahbad Daulatpur, Main Bawana Road Delhi - 110042



REMINDER-1

F.NO: DTU/Engg Cell/002591/2019-20/Civil/1519-25

Dated: 21/8/23

To,
The Additional Chief Engineer M-3
Delhi Jal Board, Govt. of N.C.T. of Delhi
H-Block, Sector-15, Rohini, Delhi-110089

Sub: - Augmentation of Water Supply by DJB in Delhi Technological University-Reg.
Ref. :- F.NO: DTU/Engg Cell/002591/2019-20/Civil/1157 on dated 21/07/2022

Sir,

Kindly refer to letter No. F.NO: DTU/Engg. Cell/002591/2019-20/Civil/1157 dated 27/07/2022 vide which it was requested to augment the present DJB water supply connection in the university campus and increase the size of connection so that university can get the adequate water to meet the demand as the present supply of DJB water through existing commercial water connection (approved office letter No. DJB/ZE-VII (NW)-II/2020/375 dated 01-02-2020) is quite insufficient. Further, it is also requested to accord permission to install 08 Nos. bore wells to meet out water deficiency in the DTU Campus after treatment of bore water.

In view of the above facts, it is once again requested to kindly look into matter personally and do the needful at the earliest.

Copy Enclosed:-

1. A copy of this office letter no. F.NO: DTU/Engg. Cell/002591/2019-20/Civil/1157 on dated 27/07/2022

Amit Kumar
21/8/23
(Prof. Amit Kumar Srivastava)
Chief Project Officer, DTU

File No. DTU/Engg.Cell/003359/2023-24/1519-25

Dated: 21/8/23

Copy to:

1. P.S. to Hon'ble VC for kind information. *22/8/23*
2. Registrar, DTU. *22/8/23*
3. COF, DTU
4. Sr.AO- II, DTU *22/8/23*
5. AE/JE concerned. *22/8/23*
5. Guard File

ACE(M)-3

Diary No...1284.....

Date.....22/8/23

o/c

Amit Kumar
21/8/23
Assistant Engineer, Civil



c/18

ENGINEERING CELL
DELHI TECHNOLOGICAL UNIVERSITY
Shahbad Daultapur, Main Bawana Road, Delhi - 110042

F.NO: DTU/Engg Cell/002298/2017-18/Civil/6154

Dated: 20/9/2022

To,
The Zonal Revenue Officer,
Main Safiabab,
Major District Road 138,
Sanjay Colony, Narela,
Delhi, 110040

Sub:- Submitting of Application form for New Connection of Domestic Water supply and Sewerage Connection for DTU at Shahbad Daultapur Bawana Road Delhi.

Sir,

Kindly refer to your office letter No. DJB/ZE-VII (NW)-II/2020/375 dated 01-02-2020, through which water supply /ferrule connection 25 mm dia. with communication pipe 50 mm dia. (G.I. pipe) has been approved by Delhi Jal Board. DJB has allowed 1000 individual water connections. As DTU is a residential campus where in 336 Nos. of different quarters and hostels for about 3000 students are there. Present bulk water supply is used to meet the residential demand only. As the present average water supply is about 0.185 MLD as against actual demand of 1.25 MLD (Potable Water) for both the residential and academic area.

In this matter, a review meeting was held on 29.01.2022 with DJB senior officials & DTU officers after discussion. It was decided that DTU may apply for new domestic connection for the residential area. Accordingly the new domestic water connection is applied online through Application Ref. No.468612674723 on dated 17.09.2022.

Hence, you are requested to provide a separate new domestic water connection for the residential area at earliest.

Please find enclosed herewith details as follows:-

1. Application Form for New Connection water and Sewerage.
2. Adhar Card
3. Photo identity card
4. Khasra No.
5. Master Plan
6. Purposed Area

Amit Kumar
17/9/22
(Prof. Amit Kumar Srivastava)
Chief Project Officer

F.NO: DTU/Engg Cell/002298/2017-18/Civil/6154

Dated: 20/9/2022

Copy to:-

1. PS to Hon'ble Vice Chancellor for kind information of Hon'ble VC, DTU
2. Registrar, DTU
3. Member (Finance), Delhi Jal Board
4. COF, DTU
5. Guard File

Amit Kumar
17/9/22
(Prof. Amit Kumar Srivastava)
Chief Project Officer

o/c



Engineering Cell
DELHI TECHNOLOGICAL UNIVERSITY
 (Formerly Delhi College of Engineering)
 Shahbad Daultapur, Main Bawana Road, Delhi-42



F.NO: DTU/Engg Cell/002298/2017-18/Civil/1526-32

Dated: 21/8/23

REMINDER-I

DELHI JAL BOARD
 Zonal Revenue office (NW)-III
 Narela Zone

To,
 The Zonal Revenue Officer,
 Main Safiabad,
 Major District Road 138,
 Sanjay Colony, Narela,
 Delhi, 110040

Diary No. 2260	NOTICE सूचना
Date 23/8/23	Please Visit Again
K No.	with in 10 to 20 Days
	to Know the Details

Sub:- Submitting of Application form for New Connection of Domestic Water supply and Sewerage Connection for DTU at Shahbad Daultapur Bawana Road Delhi.

Ref: No.DTU/Engg. Cell/002298/2017-18/Civil/6154 dated 20.09.2022

Sir,

With reference to the above, it is to informed you that a commercial connection of 25mm dia. with communication pipe of 50 mm dia. (G.I. pipe) has already been provided by Delhi Jal Board which was approved vide your office letter No. DJB/ZE-VII (NW)-II/2020/375 dated 01-02-2020. Further, it was decided in the review meeting held on 29.01.2022 with DJB senior officials & DTU officers that new separate domestic water connection be applied by DTU. Accordingly, new connection was applied online by DTU vide Application Ref. No.468612674723 on dated 17.09.2022 for Residential Complex. In this connection it is to informed you that this connection has not been approved by DJB till date. University is being facing lot of problems due to scarcity of portable water in the campus.

Keeping in view the above circumnutates you are again requested to provide a separate new domestic water connection for the residential area at the earliest.

Amit Kumar Srivastava
 (Prof. Amit Kumar Srivastava)
 Chief Project Officer

F.NO: DTU/Engg Cell/002298/2017-18/Civil/1526-32

Dated: 21/8/23

Copy to:-

1. PS to Hon'ble Vice Chancellor for kind information of Hon'ble VC, DTU
2. Registrar, DTU
3. Member (Finance), Delhi Jal Board
4. The Additional Chief Engineer M-3, Delhi Jal Board, Govt. of N.C.T. of Delhi H-Block, Sector-15, Rohini, Delhi-110089
5. COF,DTU
6. Guard File

22/8/23

O/C

Assistant Engineer
 Assistant Engineer, C



Engineering Cell
DELHI TECHNOLOGICAL UNIVERSITY
Shahbad Daulatpur, Bawana Road, Delhi – 110042
Telephone: 01127852188

Date: 20.12.2022

F.No. DTU/Engg.Cell/003544/2022-23/Civil/3336-38

To,

Chief Engineer (Other Projects),
P.W.D. (GNCTD) 13th Floor, M.S.O. Building,
IP Estate, New Delhi-110002

Subject: Development of exiting pond including construction of student activity centre at Delhi Technological University Campus, Bawana Road, Delhi.

Sir,

With reference to above subject it is brought to your kind notice that building and works committee of Delhi Technological University has approved the above work and decided to execute this work through PWD Delhi. Therefore, I have been directed by the Competent Authority to place the requisition for taking up the above said work.

Exiting pond inside the DTU main campus is filled up with waste and dirty water for the last several years. Water from the adjoining area is also percolating into the pond and creating water logging. Nearby area of the pond has already been developed with G+8 Academic Block and G+11 Boys Hostel. Therefore, premises of pond is required to be developed with provision of student activity centre for effective use of students and staff.

Scope of work includes following:

1. Development of exiting pond with provision of over flow management of water with aesthetic look.
2. Construction of student activity centre building G+3 with SPS structure of trapezoidal shape having facility for student activity, Yoga, Meditation and Gymnasium.
3. Minimum 3 meter wide pathway without any toe/boundary wall.
4. A mini water fall may be provided along sides of pond.
5. Necessary lighting arrangements in the pond area.

In view of above, it is requested to you direct the concerned engineer to take up the work at priority. It is also requested to prepare and submit the preliminary estimate of above work at the earliest. Necessary A/A & E/S shall be conveyed by the DTU as soon as the PE is received. An immediate action in the matter is requested please.

(Prof. Amit Srivastava)
Chief Project Officer



Copy to:

1. P.S. to Hon'ble V.C. for kind information to Hon'ble V.C., DTU.
2. Registrar, DTU for kind information.
3. Project Manager PWD, (Higher Education Project), PWD Lajpat Nagar-4 near Kendriya Vidyalaya, Andrews Ganj, New Delhi-110024.
4. Executive Engineer, Education Project Division-04, B-Block, 1st Floor, Vikas Bhawan-II, Civil Lines, Delhi-110054.
5. Consultant (Civil), DTU.
6. AE (Civil), DTU.
7. Guard File.

o/c

(Prof. Amit Srivastava)
Chief Project Officer

Email/Speed Post/By Hand

	लोक निर्माण विभाग, कार्यालय कार्यपालक अभियंता शिक्षा परियोजना मंडल-4 लो.नि.वि. दिल्ली सरकार, ए ब्लॉक, प्रथम तल, विकास भवन-2, सिविल लाइन्स दिल्ली-110054	Public Works Department O/o Executive Engineer, Education Project Division-4 P.W.D. Government of NCT of Delhi, A Block, 1 st Floor, Vikas Bhawan-II, Civil Lines, Delhi-110054	
011-23813801	E-Mail : eepwddelhiedu4@gmail.com		

सं. 23(3) / का.अभि. / शिक्षा परि.मं.-4 / लो.नि.वि. / 2023-24 / 455

दिनांक: 07/08/2023

सेवा में,

प्रो. अमित श्रीवास्तव,
मुख्य परियोजना अधिकारी,
दिल्ली टेक्नोलॉजिकल यूनिवर्सिटी,
शाहबाद दौलतपुर, बवानारोड,
दिल्ली-110042

16/8

Mr. Akshay (CDU)

विषय:—Development of existing pond including construction of student activity centre at Delhi Technological University, Bawana Road, Delhi.

संदर्भ:—आपके कार्यालय का पत्र सं. DTU/Engg. Cell/003544/2022-23/Civil/1260-66
दिनांक 27.07.2023

महोदय,

Reference to the above subject, this is to inform that Preliminary Estimate of providing consultancy services for the above mentioned work amounting to Rs. 48,26,046/- has been forwarded to Joint Director (Tech/Planning), DTTE by Chief Engineer (Other Projects) vide their letter No. 23(53) / मु.अभि.(ओ.पी.) / लो.नि.वि. / 2023-24 / 901-हि dated 05.07.2023 (Copy attached). The A/A & E/S of same is awaited.

This is for your information and necessary action please.

संलग्न:—As above

Roshini
07/08/23

कार्यपालक अभियंता
शिक्षा परि.मंडल-4, लो.नि.वि

प्रतिलिपि:—

1. मुख्य अभियंता (अन्य परियोजनायें), लो.नि.वि., दिल्ली सरकार, 13वाँ तल, एम.एस. ओ. भवन, आई. पी.एस्टेट, नई दिल्ली-110002 को सूचनार्थ।
2. परियोजना प्रबन्धक (उच्च शिक्षा परियोजनायें), लोक निर्माण विभाग, लाजपत नगर-4, नियर, केन्द्रीय विद्यालय, एन्ड्रयूज गंज, नई दिल्ली-110024 को सूचनार्थ।
3. सहायक अभियंता-1, शिक्षा परियोजना मंडल-4, लो.नि.वि, दिल्ली को सूचनार्थ एवं आवश्यक कार्यवाही हेतु।
4. गार्ड फाईल।

कार्यपालक अभियंता

11931/00
9/8/23
76/8/23



SURESH GOEL & ASSOCIATES
ARCHITECTS • ENGINEERS • PLANNERS
S-83, PANCHSHILA PARK, NEW DELHI-110017
TEL: (0) 26014466, 26016341 FAX: (011) 26011441
FAX: (011) 26011441 GRAM: SARJAN
E-mail: General@sgadesignlab.com

Ref:-SGA/18006/DTU/2022/6049
Date:- 29.03.2022

To,
The Executive Engineer,
Delhi Technological University,
Shahbad Daultapur,
Main Bawana Road,
Delhi-110042.

Subject : Comprehensive Consultancy Services for Designing & Development of Buildings
of Phase II of Delhi Technological University at Bawana Road, Delhi.

Ref: Rainwater harvesting drawings and calculations

Dear Sir,

As discussed please find enclosed the following drawings and rain water calculations.

- 1-Acdamic Block Run off calculation.
- 2-Rain water harvesting percolation pit(20.0 cu.m)
- 3-Rain water harvesting percolation pit(22.0 cu.m)
- 4-Rain water harvesting percolation pit(32.0 cu.m)

Thanking You

Yours Faithfully





For Suresh Goel & Associates

①

Academic Block									
Runoff Calculation									
	Total Plot Area(SQM)	Area Description	Area(SQM)	Run off co-efficient	Avg Rainfall	Actual Vol. 1 hr	Proposed Volume (Cum) / hr	Proposed Volume for 15 (Cum) / min	
1		Roof Top	2677	90%	0.026	62.64	494.55	123.6372	CUM
		Green	5434.43	15%	0.026	21.19			
		Paved	19746.05	80%	0.026	410.72			
		Total	27857.26		Proposed Cum				
Girls Hostel									
Runoff Calculation									
	Total Plot Area(SQM)	Area Description	Area(SQM)	Run off co-efficient	Avg Rainfall	Actual Vol. 1 hr	Proposed Volume (Cum) / hr	Proposed Volume for 15 (Cum) / min	
2		Roof Top	402	90%	0.026	9.41	164.58	41.14468	CUM
		Green	817	15%	0.026	3.19			
		Paved	7307	80%	0.026	151.99			
		Total	8526		Proposed Cum				
Boys Hostel									
Runoff Calculation									
	Total Plot Area(SQM)	Area Description	Area(SQM)	Run off co-efficient	Avg Rainfall	Actual Vol. 1 hr	Proposed Volume (Cum) / hr	Proposed Volume for 15 (Cum) / min	
3		Roof Top	325	90%	0.026	7.61	100.70	25.17515	CUM
		Green	660	15%	0.026	2.57			
		Paved	4352	80%	0.026	90.52			
		Total	5337		Proposed Cum				
Total (IN CUM) 189.957									
S.No.	Description	Academic Block	Girls Hostel	Boys Hostel	Remarks				
1	Total Discharge	494.5	164.58	100.7					
2	Recharge Volume pit Proposed (25% of total volume)	123.64	41.15	25.18					
3	Pit Volume Proposed in Cum	32	20	22					
	Say	4	2	1	7				



2





Delhi Jal Board (दिल्ली जल बोर्ड)

(Government of NCT of Delhi)

www.djb.gov.in

Regular Water Bill



STOP CORONA:

- Wear Mask.
- Follow Physical Distancing.
- Maintain Hand Hygiene.

Name(नाम): DELHI TECHNOLOGICAL UNIVERSITY
Address(पता): SHAHBAD DAULATPUR, BAWANA ROAD DELHI, SHIV VIHAR, SHAHBAD DAULATPUR VILLAGE, 110042
Mobile No. . (मोबाइल): 8505812925
Zone/Loc (क्षेत्र / स्थान): NW2 / Narela
Area Code (एरिया कोड): A-1
MR Code (एमआर कोड): 387/
KNO(केएनओ): 6033081242

Consumer Category(उपभोक्ता श्रेणी): CAT II
Premise Detail (परिसर विवरण): Individual House(No of floors-1)
Meter No. (मीटर संख्या): 12428/67
Meter Type (मीटर का प्रकार) (DJB/Pvt):
Bill No. (बिल संख्या): 603893909603
Bill Cycle(बिल चक्र): (B3-2023)
Bill Basis(बिल आधार): REGULAR

Bill Date(बिल की तिथि)
19-JUN-2023
Bill Amount (Rs.) (बिल राशि (₹))
480117
Bill Amount Payable (Rs.) (देय बिल राशि (₹))
(Nearest up to Rs. 10) (लगभग 10 ₹ तक)
480120
Bill Due Date(बिल देय तिथि)
06-JUL-2023
Amount Payable After Due Date(Rs.)
(देय तिथि के बाद देय राशि (₹))
504123

Meter No (मीटर संख्या)	UoM	Current Meter Read (मीटर की वर्तमान रीडिंग)		Previous Meter Read (मीटर की पिछली रीडिंग)		Consumption (खपत)	
		Meter Reading Date (मीटर रीडिंग की तारीख)	Reading / Meter Status (रीडिंग / मीटर स्थिति)	Meter Reading Date (मीटर रीडिंग की तारीख)	Reading / Meter Status (रीडिंग / मीटर स्थिति)	Days (दिन)	Units (यूनिट)
12428/67	KL	19-JUN-2023	45163 / OK	24-MAY-2023	42399 / OK	26	2764

Bill Details: Current Period Charges (बिल विवरण: वर्तमान अवधि शुल्क) (24-MAY-2023 to 19-JUN-2023)

Applicable Rate Period	Description	Amount(Rs.)
25-MAY-2023 to 19-JUN-2023	Total Consumption Charges	478976.36
25-MAY-2023 to 19-JUN-2023	Service Charge - Consumption > 100 KL	1142.00
25-MAY-2023 to 19-JUN-2023	Sub Total Bill Amount without Meter Rent	480118.36
25-MAY-2023 to 19-JUN-2023	Subtotal Bill Amount	480118.36

Bill verified of Rs. 4,80,120/-
K. B. Civil
C.P.O

Adjustment Details Are Listed Below

Arrear, if any (Rs.) (बकाया, यदि कोई (₹)) -1.53

Total Consolidated Bill Amount Payable (Rs.) (कुल समेकित बिल राशि देय (₹)) 480117

Late Payment Surcharge (Rs.) (देर से भुगतान पर अधिभार) 2400
 (5% surcharge will be applicable after due date)(देय तिथि के बाद 5% अधिभार लागू होगा)
Amount with LPSC after due date (Rs.) 5,84
 (देय तिथि के बाद अधिभार के साथ राशि (₹)) 504123

PAYABLE AMOUNT TO AVAIL REBATE SCHEME (Rs.) (छूट योजना के लिए देय राशि (₹))

Bill History (पिछला बिल)						Payment History (पिछला भुगतान)			
Bill from Date	Bill to Date	Days	Reading	Status	Units	Amount(Rs)	Receipt Id	Amount(Rs)	Date
18-APR-2023	24-MAY-2023	36	42399	OK	3852	669159	603174177775	669160.00	12-JUN-2023
25-MAR-2023	18-APR-2023	24	38547	OK	2743	476851	603637484463	476850.00	28-APR-2023
25-FEB-2023	25-MAR-2023	28	35804	OK	3159	2068624	603636509982	549094.00	10-APR-2023
27-DEC-2022	25-FEB-2023	60	32645	OK	8721	1519530	603139025443	1519530.00	29-MAR-2023
18-NOV-2022	27-DEC-2022	39	23924	OK	8619	1506043	603824551741	1506040.00	09-FEB-2023

Important Message

If bill is not paid till Bill Due Date- connection may be disconnected (यदि बिल देय तिथि तक बिल का भुगतान नहीं किया जाता है- कनेक्शन काट दिया जा सकता है)

For any assistance / query : Please call 1916 or www.djb.gov.in (किसी भी सहायता / जानकारी के लिए: 1916 पर कॉल करें या www.djb.gov.in पर जाएं)

Delhi Jal Board Bill Payment Counter Foil				Cheque / DD should be drawn in favour of DJB in the following format (चेक / डिमांड ड्राफ्ट द्वारा भुगतान करने के लिए निम्न फॉर्मेट का उपयोग करें) DJB KNO	
KNO(केएनओ)	6033081242	Name(नाम)	DELHI TECHNOLOGICAL UNIVERSITY	Bill No. (बिल संख्या)	603893909603
Bill Date(बिल की तिथि)	19-JUN-2023	Bill Due Date (बिल देय तिथि)	06-JUL-2023	Bill Amount (Rs.) (बिल राशि (₹))	480117
Bill Amount with LPSC (Rs.): (LPSC के साथ बिल राशि (₹)):	504123	Payment Date/ (भुगतान की तारीख)		Cash/Cheque No./DD No.:	
		Amount Paid(Rs.) (राशि का भुगतान (₹))		(कैश / चेक नंबर / डीडी नं. :)	
Name of Bank / Branch (बैंक / शाखा का नाम)					



Delhi Jal Board (दिल्ली जल बोर्ड)

(Government of NCT of Delhi)

www.djb.gov.in

Regular Water Bill



STOP CORONA:

- Wear Mask.
- Follow Physical Distancing.
- Maintain Hand Hygiene.

Name(नाम): DELHI TECHNOLOGICAL UNIVERSITY
Address(पता): SHAHBAD DAULATPUR, BAWANA ROAD DELHI, SHIV VIHAR, SHAHBAD DAULATPUR VILLAGE, 110042
Mobile No. (मोबाइल): 8505812925
Zone/Loc (क्षेत्र / स्थान): NW2 / Narela
Area Code (एरिया कोड): A-1
MR Code (एमआर कोड): 387/
KNO(केएनओ): 6033081242

Consumer Category(उपभोक्ता श्रेणी): CAT II
Premise Detail (परिसर विवरण): Individual House(No of floors-1)
Meter No. (मीटर संख्या): 12428/67
Meter Type (मीटर का प्रकार): (DJB/Pvt)
Bill No. (बिल संख्या): 603466338886
Bill Cycle(बिल चक्र): (B2-2023)
Bill Basis(बिल आधार): REGULAR

Bill Date(बिल की तिथि)
24-MAY-2023
Bill Amount (Rs.) (बिल राशि (रु.))
669159
Bill Amount Payable (Rs.) (देय बिल राशि (रु.))
(Nearest up to Rs. 10) (लगभग 10 रु. तक)
669160
Bill Due Date(बिल देय तिथि)
12-JUN-2023
Amount Payable After Due Date(Rs.)
(देय तिथि के बाद देय राशि (रु.))
702617

Meter No (मीटर संख्या)	UoM	Current Meter Read (मीटर की वर्तमान रीडिंग)		Previous Meter Read (मीटर की पिछली रीडिंग)		Consumption (खपत)	
		Meter Reading Date (मीटर रीडिंग की तारीख)	Reading / Meter Status (रीडिंग / मीटर स्थिति)	Meter Reading Date (मीटर रीडिंग की तारीख)	Reading / Meter Status (रीडिंग / मीटर स्थिति)	Days (दिन)	Units (यूनिट)
12428/67	KL	24-MAY-2023	42399 / OK	18-APR-2023	38547 / OK	36	3852

Bill Details: Current Period Charges (बिल विवरण: वर्तमान अवधि शुल्क) (18-APR-2023 to 24-MAY-2023)

Applicable Rate Period	Description	Amount(Rs.)
19-APR-2023 to 24-MAY-2023	Total Consumption Charges	667576.94
19-APR-2023 to 24-MAY-2023	Service Charge - Consumption > 100 KL	1581.23
19-APR-2023 to 24-MAY-2023	Sub Total Bill Amount without Meter Rent	669158.17
19-APR-2023 to 24-MAY-2023	Subtotal Bill Amount	669158.17

Adjustment Details Are Listed Below

Bill verified of Rs. 6,69,160/-
Page 1 of 1
A.E. Civil C.P.D.

Arrear, if any (Rs.) (बकाया, यदि कोई (रु.))		0.30
Total Consolidated Bill Amount Payable (Rs.) (कुल समेकित बिल राशि देय (रु.))		669159
Late Payment Surcharge (Rs.) (देर से भुगतान पर अधिभार) (5% surcharge will be applicable after due date) (देय तिथि के बाद 5% अधिभार लागू होगा)	3345 7.92	Amount with LPSC after due date (Rs.) (देय तिथि के बाद अधिभार के साथ राशि (रु.)) 702617

PAYABLE AMOUNT TO AVAIL REBATE SCHEME (Rs.) (रुट योजना के लिए देय राशि (रु.))

Bill History (पिछता बिल)					Payment History (पिछता भुगतान)				
Bill from Date	Bill to Date	Days	Reading	Status	Units	Amount(Rs)	Receipt Id	Amount(Rs)	Date
25-MAR-2023	18-APR-2023	24	38547	OK	2743	476851	603637484463	476850.00	28-APR-2023
25-FEB-2023	25-MAR-2023	28	35804	OK	3159	2068624	603636509982	549094.00	10-APR-2023
27-DEC-2022	25-FEB-2023	60	32645	OK	8721	1519530	603139025443	1519530.00	29-MAR-2023
18-NOV-2022	27-DEC-2022	39	23924	OK	8619	1506043	603824551741	1506040.00	09-FEB-2023
15-OCT-2022	18-NOV-2022	34	15305	OK	2248	387774	603517637040	387770.00	05-DEC-2022

Important Message

If bill is not paid till Bill Due Date- connection may be disconnected (यदि बिल देय तिथि तक बिल का भुगतान नहीं किया जाता है- कनेक्शन काट दिया जा सकता है)
 For any assistance / query : Please call 1916 or www.djb.gov.in (किसी भी सहायता / जानकारी के लिए: 1916 पर कॉल करें या www.djb.gov.in पर जाएं)

Delhi Jal Board Bill Payment Counter Foil				Cheque / DD should be drawn in favour of DJB in the following format (चेक / डिमांड ड्राफ्ट द्वारा भुगतान करने के लिए निम्न फॉर्मेट का उपयोग करें) DJB KNO	
KNO(केएनओ)	6033081242	Name(नाम)	DELHI TECHNOLOGICAL UNIVERSITY	Bill No. (बिल संख्या)	603466338886
Bill Date(बिल की तिथि)	24-MAY-2023	Bill Due Date (बिल देय तिथि)	12-JUN-2023	Bill Amount (Rs.) (बिल राशि (रु.))	669159
Bill Amount with LPSC (Rs.): (LPSC के साथ बिल राशि (रु.)):	702617	Payment Date/ (भुगतान की तारीख)		Cash/Cheque No./DD No.:	
		Amount Paid(Rs.) (राशि का भुगतान (रु.))		(कैश / चेक नंबर / डीडी नं. :)	
Name of Bank / Branch (बैंक / शाखा का नाम)					

2021-22

7.1.4 Water conservation facilities available in the Institution: Rainwater harvesting Bore well/Open well recharge Construction of tanks and bunds Waste water recycling Maintenance of water bodies and distribution system in the campus

Rainwater harvesting is adopted across the entire campus to raise the groundwater level. Seven rainwater harvesting pits exist across the classroom blocks and other buildings catering to a catchment area of 2500 sqm. DTU also has more than 529000 sqm of green cover where rainwater from nearby buildings percolates in the ground. In addition to this, all the new buildings under construction have adequate provisions for rainwater harvesting. A pond with a 3000 sqm surface area is located within the campus. It collects rainwater and water from the rooftops to raise the groundwater level. The sewage treatment plant at DTU also serves to recycle water for horticultural and cleaning purposes.

GOVERNMENT OF NCT OF DELHI
DEPARTMENT OF TRAINING & TECHNICAL EDUCATION
MUNI MAYA RAM MARG; PITAM PURA; DELHI-110088.

PHONE: 011-27318548. FAX-27325341.

E-MAIL ID: SPIU.DELHI@YAHOO.IN AND DDPLGTTE.DELHI@NIC.IN
(PLANNING BRANCH)

DELHI GOVERNMENT
Team Delhi. Making things happen

DELHI GOVERNMENT
Team Delhi. Making things happen

F. 75 (0)/DTTE/Plg EFC/2013-14/000323618/

527-35

Date: // -09-2018

To

The Chief Project Manager (Housing),
PWD, 13th Floor, MSO Building,
I. P. Estate, New Delhi-110002,
Through Vice Chancellor,
DTU, Delhi.

SUB: ISSUE OF ADMINISTRATIVE APPROVAL & EXPENDITURE SANCTION.

Sir,

Sanction of the Competent Authority is accorded/ conveyed for A/A & E/S of estimated cost of Rs.291.88 Crore (Rs. Two Hundred Ninety One Crore and Eighty Eight Lakh only) including contingencies, labour cess, third party quality control, Architect consultancy each @ 1% and EPF/ ESI contribution @ 4.25% for civil work as mentioned below for construction of stage-I of DTU phase-II at Bawana, Delhi.

The expenditure involved on this account would be debitible to the under mentioned head of account for the year 2018-19 under Demand for Grant No. 06 - "Major Head 4202- 02.105 Infrastructure project of Autonomous Institution/ University, (Minor Head) 82 00 53 Major Works (Sub-Head) for current financial year i.e. 2018-19:

S. No.	Component	Covered Area (Sq. Mtr)	Remarks
I.	Building	1, 58, 840.41	Total Amount Approved by Council of Minister for the project: Rs. 291.88 Crore
A	Academic Area	69, 146.03	
B.	Hostel	50, 607.40	
C.	Residential Area	39, 086.98	
TOTAL		1, 58, 840.41 sq. Mtr.	
Period of Completion		Call of tender and award of work: 04 Months after date of A/A & E/S Execution of Work: 15 Months from the date of Award of Work	

The sanction is subject to the following conditions:

1. A copy of the detailed estimate may be submitted to the Project Monitoring Committee (PMC) to monitor the progress made by PWD in the concerned work as per the detailed estimate.
2. The monthly financial & physical progress report should be submitted regularly to the PMC/ Joint Director (Planning-TTE).
3. The progress for execution of work will be reviewed and monitored by PMC (consisting of VC-DTU, Registrar-DTU, Ex. Er.-DTU, Nominie of TTE, CPM-PWD-Housing, concerned Ex. Er.-PWD and third party quality assurance) on the basis of monthly progress report as in para 2.
4. The work will be completed by the PWD within time schedule as given by PWD in the estimate & completion certificate must be furnished to the PMC/ Joint Director (Planning), Department of Training & Technical Education, Delhi.


5. That total expenditure will not exceed the budget allocation under the specific sub-head during the financial year 2018-19. Rs. 50.00 Crore are placed/ allocated under above stated Head of Account for execution of this proj in the current financial year 2018-19.

6. All Codal formalities will be observed as per CPWD Manual by the executive agency along with compliance of guidelines issued by Finance Department from time to time and vide order no. DPAR 2012 (Civil), DPAR 2014 (Electrical), DSR 2016 s& Market Rate and other guidelines issued from CVC/ DTTE/ IT Department from time to time.

7. The work has been assigned Job No. 75 (8)/ DTTE/ Ptg EFC/ 2013-14/ 000323618/ 01 Directorate of Training & Technical Education 2018-19, which should invariable be quoted for all further correspondence.

8. This issues with the prior approval of the Council of Ministers vide Cabinet Decision No. 2628 dated 28-08-2018.

Yours faithfully,


(Dr. O. P. Shukla)


Joint Director (Pig)

Date: 11-09-2018


F. 75 (8)/ DTTE/ Ptg EFC/ 2013-14/ 000323618/ 527-33


Copy to:

1. PS to Secretary (TTE)/ PS to Director (TTE) for information please
2. Engineer-in-Chief, PWD, MSO Building, ITO, New Delhi-110002
4. Vice Chancellor, DTU, Bawana Road, New Delhi
5. DCA (HQ) DTTE, Muni Maya Ram Marg, Pitam Pura, New Delhi-110088.
6. Sr. Accounts Officer, Directorate of Audit, Govt. of Delhi, Delhi Sachivalaya, New Delhi.
7. Executive Engineer, Engineering Division, DTU, Bawana Road, New Delhi.


(Dr. O. P. Shukla)
Joint Director (Pig)

CONSTRUCTION OF TANKS AND BUNDS





 GPS Map Camera

Delhi, Delhi, India


H No. A-3 Kh. No. 15/25 & 26/5 Ground floor Prakash Vihar
Shahbad Ext, Ph.-2, Bawana Rd, Delhi Technological University,
Shahbad Daulatpur Village, Rohini, Delhi, 110042, India

Lat 28.750334°

Long 77.112532°

04/11/22 11:21 AM GMT +05:30


WASTE WATER RECYCLING



EXTRA ITEM STATEMENT NO. 15

Name of work: C/o Stage-I of phase II, Delhi Technological University at Bawana Road, Delhi (SH-C/o Academic Blocks AB-3 & AB-4, Boys Hostel H-5 & Girls Hostels HG-5 & HG-6 and all external and internal services including external development and landscaping and allied civil and E & M works).


Agency : M/s SAM (India) Built Well Pvt. Ltd.		Detail of previous sanction/submission EIS/SIS statements					
Agreement No.:	02/EE/EPD-4/PWD/2019-20	S.No.	AE	EE	SE/IPM	CE/CPM	Letter No.
Mode of Agreement : Percentage Rate		EIS No.1	178295				Sanctioned by AE vide letter no. 06 dt. 08.01.20
Estimated cost : Rs. 230,11,53,307/-		EIS No.2		2566493			Sanctioned by EE vide letter no. 46 dt. 22.01.20
Tendered cost : Rs. 227,69,91,197/-		EIS No.3 (Revised)		330227			Sanctioned by EE vide letter no. 183 dt. 07.04.2022
Date of Start : 23/09/2019		EIS No.4			445619		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 584 dt. 10.07.20
Date of Completion:- 23/12/2020		EIS No.5			4575490		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 767 dt. 14.08.20
Actual date of Completion:- In Progress		EIS No.6 (Re-Revised)			5398759		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 841 dt. 27.04.2022
		EIS No.7 (R)			22606778		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 841 dt. 27.04.2022
		EIS No.8 (R)			5135384		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 841 dt. 27.04.2022
		SIS No.1			2651565		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 232 dt. 12.02.2021
		SIS No.2 (R)			2441702		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 842 dt. 27.04.2022
		EIS No.9				53135908	Sanctioned by CE (OP) vide letter No. 1284 dt. 05.08.2021.
		SIS No.3 (R)			4396912		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 842 dt. 27.04.2022
		EIS No.10				21304822	Sanctioned by CE (OP) vide letter No. 1480 dt. 02.09.2021.
		SIS No.4			625846		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 1538 dt. 02.12.2021.
		EIS No.11				12717633	Sanctioned by CE (OP) vide letter No. 414-H dt. 23.02.2022.
		EIS No.12				7610827	Sanctioned by CE (OP) vide letter No. 843-H dt. 31.03.2022.
		SIS No.5			274323		Sanctioned by PM (Hr. Edu. Proj.) vide letter No. 500 dt. 14.03.2022.
		EIS No.13				914771	Sanctioned by CE (OP) vide letter No. 969-H dt. 08.04.2022
		EIS No.14				684076	yet to be sanctioned
		SIS No.6				3846707	yet to be sanctioned
						5,906,850	yet to be sanctioned
Amount of this Statement							
Total		178295	2896720				
Powers to sanction EIS/SIS		180,000	3,000,000				
					48550378	106211594	
					50,000,000	Full Power	




S. No	Description	Qty	Unit	Rate	Amount	Remarks
1	Providing and installation of modular Rain Water harvesting pit with recycled polypropylene Crosswave size 494x494x220 mm with load Bearing capacity of 14 tons per square metre. The crosswave will be wrapped with geotextile fabric material of 400 GSM in two layers to prevent soil insertion in the pit. The geotextile material shall be UV resistant and conforming to ASTM D4595. The cost shall be inclusive of all necessary excavation in all kind of soils, refilling and disposal of surplus earth with in the premises as directed. Depth shall be as per actual site condition and invert level. Each RWH will consists of 1 No. GRHA Approved FRP pure Rain filter 700 mm Dia with 300 mm dia inlet & outlet with necessary connections to filter & desilting Manhole of Brick masonry, Manhole having inside size 1.20mx0.90mx1.20m deep. The pit will consist of FRP based inspection chambers of 500x500x500 mm. Total depth of filter shall be upto 2000mm inclusive of two filter extensions (if required) of 700 mmx600 mm depth each.					
(a)	(Tentative Size-5.5m x 2.0m x 2m mtr complete in all respect and depth of top layer of crosswave copolymer structure below natural ground level is approximately 1.50meter)	2.00	each	835697	1671394	
(b)	(Tentative Size-4.0mtr x 4.0mtr x 2mtr complete in all respect and depth of top layer of crosswave copolymer structure below natural ground level is approximately 1.50meter)	4.00	each	1082280	4329120	This item is required to be executed for storm water collection/disposal in Boys Hostel & Academic block. This item is not in Agreement. Hence an extra item is proposed
		Total		1081659.00	4329120.00	
	Certified that :			5996850.00		
1	The qty taken are approximate and payment shall be made as per actual work executed at site of work.			60100300		
2	The rates are net and nothing extra shall be paid.					
3	This statement contains 1 item only.					
Extra item statement no. 15, for amounting to Rs. 59,96,850/- (Rs. Fifty Nine Lakhs Ninety Six Thousand Eight Hundred Fifty Only) is submitted to P.M. (Hr. Edu. Proj.) for further processing and necessary action please.						





 Assistant Engineer-1
 Assistant Engineer
 Edu. Project Division-4
 PWD, Vikas Bhawan-2,


 Assistant Engineer (P)
 Assistant Engineer
 Edu. Project Division-4
 PWD, Vikas Bhawan-2,


 Executive Engineer
 Executive Engineer
 Edu. Project Division-4
 PWD, Vikas Bhawan-2,


**RAIN WATER HARVESTING PERCOLATION PIT
(CROSS WAVE TECHNOLOGY)**
8.0m² 0m^x2.0m^x32.00Cum



**Rain Water Harvesting Percolation Pit
Cross Section View**
8.0m² 0m^x2.0m^x32.00Cum

Designed By: **Ashwath Interact Pvt Ltd.**
Company: **Ashwath Interact Pvt Ltd.**
Building No.2, 4th floor, Masoodpur Farms,
Vasanth Kunj, New Delhi-110070

**RAIN WATER HARVESTING PERCOLATION PIT
(CROSS WAVE TECHNOLOGY)**
8.0m² 0m^x2.0m^x32.00Cum



**Rain Water Harvesting Percolation Pit
Top view (Plan)**
8.0m² 0m^x2.0m^x32.00Cum

Handwritten signature

2020-21

7.1.4	<p>Water conservation facilities available in the Institution: Rainwater harvesting Borewell /Open well recharge Construction of tanks and bunds Wastewater recycling Maintenance of water bodies and distribution system in the campus</p>	<p>Rainwater harvesting is adopted across the entire campus to raise the groundwater level. Seven rainwater harvesting pits exist across the classroom blocks and other buildings catering to a catchment area of 2500 sqm. DTU also has more than 529000 sqm green cover where rainwater from nearby buildings percolates in the ground. In addition to this, all the new buildings under construction have adequate provisions for rainwater harvesting. A pond with a 3000 sqm surface area is located within the campus. It collects rainwater and water from the rooftops to raise the groundwater level. The sewage treatment plant at DTU also serves to recycle water for horticultural and cleaning purposes.</p>
-------	---	---

C122

Criteria- 7.1.3

Liquid Waste Management/ Waste Water Re-cycle:- DTU established Sewage Treatment Plant (STP) with the capacity of plant 1 MLD (Million Liter per Day) near DTU main gate no.2. The plant established in May,2019 at DTU main campus by M/s Absolute Water Pvt Ltd. The capacity of plant for treated the waste/sewage water is 01 million per day. The treated water used for horticulture purpose and cleaning purpose. The plant has been running by M/s Absolute Water Pvt Ltd. who constructed this plant. DTU concern staff also checked the TDS of treated water.

Data for 2020-21

- a) Average treated water per Day:- 2,70,000 liter or 250 KLD
- b) Average treated water per Month:- $2,70,000 \times 30 = 81,00,000$ litre of 810 KLD
- c) Average treated water per Year:- $81,00,000 \times 12 = 97200000$ litre of 9720 KLD

This treated water used for cleaning purpose, Horticulture purpose and also used at Phase-II site during 2020-21.

Average pH during 2020-21 of treated water was 7.0 pH and average TDS was 650.


JE (C)

Criteria - 7.1.4

Rain water Harvesting

435

The details of rain water harvesting System in DTU main Campus Delhi are as follows.

- i. A pond is situated inside the DTU campus which is having an area more than 3000 sqm, which collects the rain water and surplus water from the roof of the buildings and the treated water from the Sewage treatment Plant of 01 M.L.D capacity installed at DTU is also discharged into the pond, which all contributed in raising of ground water table.
- ii. Rain Water Harvesting Pit has been installed in DTU campus in newly constructed Class Room Blocks, which is having the more than 2500 sqm catchment area.
- iii. Apart from above D.T.U is having more than 5,29,000.00 sq.(Approx.) green area/Park where the rain water from the nearby building's roof percolates into the ground and recharge the ground water table. (As per master plan enclosed)
- iv. The rain water harvesting system is also adopted in all proposed buildings (under constructed) in the campus.
- v. The area details of the campus are as follows:-

S.no	Particulars	Area in (sqm)
1.	Total area of the plot	663154.03
2.	Building roof top area	129602.66
3.	Paved area	4572.92
4.	Green area	528978.45

Signature

9 Cudey

Name of Work: Construction of Rainwater Harvesting Recharge System by Crosswave Technology

Site Location: Delhi Technical University, Bawana Road

1	Roof Top Area	6137.00	Sqm
2	Green /Parking Area	1513.00	Sqm
4	Paved Area	3505.00	Sqm
		11155.00	Sqm

$6137 \times .90 \times .026 = 143.60 \text{ CuM}$
 $1513 \times .40 \times .026 = 15.73 \text{ CuM}$
 $3505 \times .80 \times .026 = 72.90$

TOTAL CuM of Rainfall to be considered for Rain Water Harvesting for 205 minutes 96.75 CuM Say 98 CuM.

WE HAVE PROVIDED 7 PITS OF 14 CuM. Total 98 CuM.

36/C

2020-19